

Environmental and Ecological Planning Advisory Committee

Report

The 6th Meeting of the Environmental and Ecological Planning Advisory Committee
May 17, 2018
Committee Rooms #1 and #2

Attendance PRESENT: S. Levin (Chair), A. Boyer, C. Dyck, C. Evans, P. Ferguson, S. Hall, N. St. Amour, S. Sivakumar and R. Trudeau and H. Lysynski (Secretary)

ALSO PRESENT: D. Baxter, C. Creighton, T. Copeland, A. Macpherson, J.P. McGonigle, L. Pompilii and P. Yanchuck

REGRETS: E. Arellano, E. Dusenge, B. Krichker, C. Kushnir, S. Madhavji, K. Moser, C. Therrien and I. Whiteside

The meeting was called to order at 5:30 PM

1. Call to Order

1.1 Disclosures of Pecuniary Interest

That it BE NOTED that no pecuniary interests were disclosed.

2. Scheduled Items

2.1 Overview of the Parks and Recreation Master Plan update

That it BE NOTED that the Environmental and Ecological Planning Advisory Committee (EEPAC) received the attached presentation from D. Baxter, Manager of Development, Neighbourhood, Children & Fire Services and J.P. McGonigle, Division Manager, Parks and Recreation, with respect to an overview of the Parks and Recreation Master Plan; it being noted that the EEPAC will provide comments at their next meeting.

2.2 William Street Stormwater Outfall and Channel in Huron Street Woods

That it BE NOTED that the Environmental and Ecological Planning Advisory Committee (EEPAC) received the attached presentation from S. Stanlake-Wong, Associate, J. Johnson, Dillon Project Manager and T. Goulet, Project Biologist, Dillon Consulting, with respect to the William Street Stormwater Outfall and Channel in Huron Street Woods; it being noted that the EEPAC will establish a Working Group and provide comments at their next meeting.

3. Consent

3.1 5th Report of the Environmental and Ecological Planning Advisory Committee

That it BE NOTED that the 5th Report of the Environmental and Ecological Planning Advisory Committee, from its meeting held on April 19, 2018, was received.

3.2 4th Report of the Trees and Forests Advisory Committee

That it BE NOTED that the 4th Report of the Trees and Forests Advisory Committee, from its meeting held on April 25, 2018, was received.

3.3 6th Report of the Advisory Committee on the Environment

That it BE NOTED that the 6th Report of the Advisory Committee on the Environment, from its meeting held on May 2, 2018, was received.

3.4 Municipal Council Resolution - 4th Report of the Environmental and Ecological Planning Advisory Committee

That it BE NOTED that the Municipal Council resolution adopted at its meeting held on April 10, 2018, with respect to the 4th Report of the Environmental and Ecological Planning Advisory Committee, was received.

3.5 3614, 3630 Colonel Talbot Road and 6621 Pack Road

That a Working Group BE ESTABLISHED, consisting of S. Levin (lead), S. Sivakumar and R. Trudeau to review the Environmental Impact Study and Hydrogeological Study, relating to the properties located at 3614, 3630 Colonel Talbot Road and 6621 Pack Road; it being noted that the Environmental and Ecological Planning Advisory Committee reviewed and received communications dated May 7 and May 15, 2018, from N. Pasato, Senior Planner, with respect to this matter.

4. Sub-Committees and Working Groups

4.1 Wetlands

That, the following actions be taken with respect to the attached Wetlands Working Group comments:

a) the Working Group comments with respect to a wetland conservation strategy BE FORWARDED to the Upper Thames River Conservation Authority, the Manager, Development Planning and one of the City's Ecologists, for review and to provide comments back to the Environmental and Ecological Planning Advisory Committee; and,

b) the Environmental and Ecological Planning Advisory Committee members BE REQUESTED to review the Working Group comments and report back at the next meeting.

4.2 Southdale Road West Environmental Impact Statement

That the attached Working Group comments with respect to the Southdale Road West Environmental Impact Statement BE FORWARDED to S. Shannon, Technologist II, for consideration.

4.3 Sunningdale Court

That the attached Working Group comments with respect to the Sunningdale Court Environmental Impact Statement (600 Sunningdale Road West) BE FORWARDED to C. Smith, Senior Planner, for consideration.

5. Items for Discussion

5.1 Notice of Completion - Master Plan - London Pollution Prevention and Control Plan

That it BE NOTED that the Notice of Completion relating to the London Pollution Prevention and Control Plan Master Plan from M. McKillop, Wastewater and Drainage Engineering and T. Mahood, Project Manager CH2M, was received.

6. Deferred Matters/Additional Business

6.1 (ADDED) One River Master Plan Environmental Assessment Study - Notice of Stage 2 Public Information Centre

That it BE NOTED that the One River Master Plan Environmental Assessment Study Notice of Stage 2 Public Information Centre, from A. Rammeloo, Manager, Engineering, Rapid Transit and T. Mahood, Project Manager, Jacobs, was received.

7. Adjournment

The meeting adjourned at 7:16 PM.



Parks & Recreation Master Plan Update

May / June 2018

Advisory Committees



Purpose of Connecting With You

Purpose:

1. To review the plan to update the Parks and Recreation Master Plan this year.
2. Ask for your assistance in sharing the Community Survey with your networks and the public.
3. To request your Committee's input.



About the Master Plan

Creating a "Game Plan" for Parks, Recreation Programs, Sport Services and Facilities

- The Master Plan provides an overall vision and direction for making decisions. It is a high level/policy directive document.
- It is based on public input, participation trends and usage, best practices, demographic changes and growth forecasts.
- The Plan will be used by the City to guide investment in parks, recreation programs, sport services and facilities over the next ten years and beyond.




Master Plan Overview

- The City has retained **Monteith Brown Planning Consultants**, **Tucker-Reid & Associates** and **Swerhun Facilitation** to assist in preparing the Update.



Master Plan Building Blocks

1. Public and Stakeholder Input
2. Demographics and Growth
3. Trends and Usage Data
4. Existing Policies and Guidelines
5. Park, Program, and Facility Distribution
6. Facility Inventories and Asset Management Data



Project Scope

Items within Scope:



- **Recreation Programming**, such as aquatic, sport, wellness, arts/crafts, dance/music, and general interest programs provided by the City and other sectors



- **Recreation and Sport Facilities**, such as community centres, pools, sports fields, playgrounds and more



- **Parks & Civic Spaces**, such as major parks, neighbourhood parks, gardens and civic squares



- **Investment in the Community**, such as neighbourhood opportunities, public engagement, sport tourism and more



Project Scope

Items out of Scope:

- **Parkland Dedication Policies** (London Plan)
- **Cycling** (London Plan, Transportation and Cycling Master Plans)
- **Natural Heritage and Trails** (London Plan, Conservation Master Plans, ESA Master Plans)
- **Arts, Culture and Heritage** (Cultural Prosperity Plan and related reports)

Although these items are addressed in other studies, the Master Plan will ensure [alignment](#)



Guiding and Supporting Documents

The Master Plan is a Strategy that guides the provision and management of parks, recreation programs, sport services and facilities. It is influenced by several Overarching Plans and informs several Technical Reports.

Key Overarching Plans	Key Strategies	Key Technical Reports
The London Plan Council's Strategic Plan Accessibility Plan Sector-specific guiding documents, such as the Framework for Recreation in Canada, Parks for All, and others	Age Friendly London Action Plan Child and Youth Agenda Strengthening Neighbourhoods Strategy Transportation and Cycling Master Plans Cultural Prosperity Plan Community Diversity and Inclusion Strategy SHIFT: Rapid Transit Initiative Back to the River / One River Thames Valley Corridor Plan	Development Charges Background Study Conservation Master Plans for Environmentally Sensitive Areas Park-specific Master Plans Business Cases and Feasibility Studies Various By-laws, Policies and Procedures



Deliverables and Timing

- **Background Research** March to June 2018
- **Engagement** May to July 2018
 - Community Survey (Opens May 23rd)
 - Stakeholder Sessions/Focus Groups/Interviews
- **Draft Plan #1** Sept / Oct 2018
- **Draft Plan #2** Oct / Nov
- **Final Plan** presented to the new Council January 2019



Community Survey

Purpose

- To establish a broad picture of usage, satisfaction, priorities, demographics

Timing

- Will be available May 23 until mid-July, hosted through getinvolved.london.ca

How can you help?

- Share the link to the survey with your networks
- Let us know if you would like posters or postcards to distribute




Advisory Committee Input

- Individuals can complete the Community Survey at getinvolved.london.ca
- Tell us about groups or organizations that we should invite to the Stakeholder sessions
- Committee can provide written responses to the Questions AND / OR
- Committee can provide comments on the last Parks and Recreation Strategic Master Plan (2009) and Interim Update (Jan. 2017)

Email to: PlayYourWay@london.ca





Advisory Committee Input


Guiding Questions

1. What are the most pressing **issues and priorities** for your Advisory Committee?
2. How can the City of London's parks, recreation and sport **services and facilities** continue to support the needs of your Committee? Please be specific.
3. How can your Committee, the City and others **work together** to meet future needs?
4. Are there any initiatives that are being contemplated, planned or are being implemented that could tie into these or other priorities for parks, recreation and sport services and facilities?



Parks & Recreation Master Plan Update

Thank you!




WELCOME



The City's 'Old North Servicing Strategy' identified the need to improve drainage in the Old North neighbourhood, which will include constructing a new trunk storm sewer on William Street between Huron Street and Grosvenor Street. The storm sewer will be constructed over a number of years, with the first phase including upgrades to the existing outlet at the end of William Street, in Huron Street Woods.

Presentation Outline:

- ✔ **SUMMARIZE** existing conditions in the Study Area
- ✔ **OUTLINE** alternatives considered and the technically preferred solution
- ✔ **PRESENT** summary of the Environmental Impact Study completed
- ✔ **OUTLINE** the next steps in the planning and design process
- ✔ **DELIVER** a copy of the EIS for EEPAC review and consideration.



The Study followed the requirements of the *Municipal Class Environmental Assessment (EA)* (2015) as a Schedule 'B' project. The study followed Phases 1 and 2 of the Class EA process.



ALTERNATIVE 1 – DO NOTHING



- Description:**
- Basic channel improvements from the existing headwall to the maintenance road
 - Replace existing culvert with a larger culvert or bridge
 - Maintain existing open aquatic/swamp feature but eliminate significant water ponding
- Pros**
- Reduce flooding and standing water on the Thames Valley Parkway
 - Minimal impact on natural environment
 - Improved drainage
 - Lowest construction cost
 - Eliminate standing water at top of slope at rear of Harrison Crescent properties.
- Cons**
- Potential for culvert to be impacted by beaver activity in the future

7

ALTERNATIVE 2 – RECOMMENDED



- Description**
- Remove existing headwall
 - Extend storm sewer approximately 35m
 - Install new energy dissipating headwall
 - Replace existing culvert with a larger culvert or bridge
 - Maintain existing open aquatic/swamp feature but eliminate significant water ponding
- Pros**
- Reduce flooding and standing water on the Thames Valley Parkway
 - Impacts of increased flow are reduced (i.e. storm flow is contained in sewer longer), improving slope stability
 - Minimal impact on natural environment
- Cons**
- Potential for culvert to be impacted by beaver activity

8

ALTERNATIVE 3 – NOT RECOMMENDED



- Description**
- Remove existing headwall and culvert
 - Extend storm sewer under maintenance road before outletting to the existing channel
 - Install new energy dissipating headwall
 - Maintain existing open aquatic/swamp feature but eliminate significant water ponding
- Pros**
- Reduce flooding and standing water on the Thames Valley Parkway
 - Reduce standing water
- Cons**
- Greater impact on natural environment
 - Construction may not be cost effective due to existing soil conditions

9

ALTERNATIVE 4 – NOT RECOMMENDED



- Description**
- Remove existing headwall and culvert
 - Extend storm sewer under maintenance road before outletting to the existing channel
 - Install new energy dissipating headwall
 - Install drain to direct overland flow to the storm sewer
 - Grade and plant existing open aquatic/swamp feature using native species
- Pros**
- Reduce flooding and standing water on the Thames Valley Parkway
- Cons**
- Greater impact on natural environment
 - Construction may not be cost effective due to existing soil conditions

10

Summary of Preferred Alternative



- Extension of the storm sewer will improve slope stability
- New storm headwall will be installed, complete with energy dissipation baffle blocks which will assist with decreasing erosion and sediment transport
- Channel designed with a low flow channel, complete with a slight meander to further assist with energy dissipation

EIS OVERVIEW



An Environmental Impact Study (EIS) was completed for the technically preferred solution.


The EIS included:

- Two years of natural environment inventories (2016-2017).
- An evaluation of significance and impact assessment.
- A summary of impacts and recommended mitigation measures and monitoring to be carried into detail design and construction.

Key objectives of the EIS were to:

- Determine potential impacts on the existing natural heritage system.
- Recommend areas for avoidance of impacts and/or mitigation to ensure protection of significant features and functions.
- Avoid impacts to aquatic resources, Species at Risk (SAR) and natural features.
- Develop recommendations for appropriate mitigation and monitoring plans, including a landscape restoration plan and invasive species management plan.

EIS OVERVIEW



13

EIS FINDINGS



Ecological Land Classification

The site contains a former flooded shallow water aquatic community transitioning to a vegetated terrestrial community. Surrounding communities include a Buckthorn deciduous shrub thicket and low density residential areas. Vegetation species are typical of disturbed sites, with high coverage of invasive species. The study area includes part of Huron Street Woods, which is considered a Significant Woodland.

Aquatic Resources

The storm sewer channel outlets to Huron Creek, a tributary to the North Thames River, and provides seasonal fish habitat with a warm water thermal regime.

14

EIS FINDINGS



Amphibians and Other Fauna

A small population of American Toads was identified in the site, but is not large enough to be considered significant wildlife habitat for amphibians. No other amphibians, reptiles, mammals or insects were identified in the site.

Breeding Birds

Background records found a variety of bird species in the surrounding area, including five Species at Risk or Special Concern (SC) species: Eastern Wood-pewee, Bank Swallow, Wood Thrush, Chimney Swift and Barn Swallow.

Species at Risk and Special Concern Species

No SAR or SC species were observed during the 2016-2017 inventories. The site contains potential habitat for Eastern Wood-pewee, Bank Swallow, and Wood Thrush, as well as Spiny Softshell turtle and Snapping Turtle, but these species were not identified in the site.

15


KEY RECOMMENDATIONS

In addition to typical mitigation measures (erosion and sediment control, timing windows, bird nest searches, etc.), additional key recommendation from the EIS include:

- The works are designed to maintain existing flows in the channel, and to cause no negative impacts to aquatic habitat, shoreline stability and connectivity. The storm sewer extension has been designed to minimize the reduction of habitat to the extent feasible, limited to areas of steep grades with high erosion risk and bank instability, which will be addressed by the extension.
- Fish and wildlife habitat enhancement will be implemented along the remaining portion of the channel from the new outfall location downstream to the new crossing.
- Tree and shrub removal will be limited to the extent feasible, limited to removal of only a few small diameter individuals, including removal of existing invasives. No significant loss of corridor linkage, or fragmentation of the connectivity in Huron Street Woods is expected to occur.
- Wildlife exclusion fencing is recommended to be installed around the project site during construction. A qualified biologist will be available to monitor construction and provide safe relocation of wildlife, if encountered.
- An Invasive Species Management Plan will be implemented to reduce the proliferation of invasives in the Study Area post-construction.
- A Landscape Restoration Plan will be implemented to plant new trees and shrubs of native species.

16

DRAFT RESTORATION PLAN



17

NEXT STEPS

Environmental Impact Study (EIS):

- Receive input from EEPAC, UTRCA and MNRF by June 14, 2018
- Finalize EIS.

Environmental Study Report (ESR):

- Finalize EA document - June 2018
- Present EIS and EA document to Council for endorsement
- 30-day public and agency review period – Anticipated summer 2018.

Construction:

- Construction could begin as early as 2020.

18

Questions?



Environmental and Ecological Planning Advisory Committee

Report

The 5th Report of the Environmental and Ecological Planning Advisory Committee
April 19, 2018
Committee Rooms #1 and #2

Attendance PRESENT: S. Levin (Chair), E. Arellano, A. Boyer, C. Dyck, P. Ferguson, S. Hall, B. Krichker, S. Madhavji, K. Moser, N. St. Amour, S. Sivakumar, C. Therrien, R. Trudeau and I. Whiteside and H. Lysynski (Secretary)

ABSENT: C. Evans

ALSO PRESENT: G. Barrett, C. Creighton and A. Macpherson

The meeting was called to order at 5:03 PM

1. Call to Order

1.1 Disclosures of Pecuniary Interest

That it BE NOTED that no pecuniary interests were disclosed.

2. Scheduled Items

2.1 Southdale Road Environmental Assessment Study

That a Working Group BE ESTABLISHED consisting of R. Trudeau (Lead), S. Levin and C. Therrien to review the Southdale Road West Environmental Assessment Study; it being noted that the Environmental and Ecological Planning Advisory Committee received the attached presentation from T. Koza, Project Manager, B. Huston and B. Fox, Dillon Consulting Limited, with respect this matter.

3. Consent

3.1 4th Report of the Environmental and Ecological Planning Advisory Committee

That part b) of clause 2.2 of the 4th Report of the EEPAC BE AMENDED to read as follows:

"b) the Environmental Study Report BE REQUIRED to be included in the Request for Proposal".

3.2 5th Report of the Advisory Committee on the Environment

That it BE NOTED that the 5th Report of the Advisory Committee on the Environment, from its meeting held on April 4, 2018, was received.

3.3 Natural Resource Solutions Inc. - 3614, 3630 Colonel Talbot Road and 6621 Pack Road: Subject Lands Status Report Agency Comments Responses

That N. Pasato, Senior Planner, BE REQUESTED to attend the next Environmental and Ecological Planning Advisory Committee (EEPAC) meeting and provide a written report with respect to the following, related to the Subject Land Status Report on the properties located at 3614, 3630 Colonel Talbot Road and 6621 Pack Road:

- a) the current status of the Subject Land Status Report;
- b) the current status of the Environmental Impact Study;
- c) what other studies are currently being undertaken and the time line for their completion;
- d) what studies are yet to be undertaken as part of the application and detail design; and,
- e) how EEPAC will be involved in the review of these studies;

it being noted that the EEPAC received a communication dated January 23, 2018, from Natural Resource Solutions Inc., with respect to this matter.

3.4 Medway Valley Heritage Forest Environmentally Significant Area

That it BE NOTED that the Environmental and Ecological Planning Advisory Committee (EEPAC) held a general discussion with respect to the Medway Valley Heritage Forest Environmentally Significant Area (south) Conservation Master Plan and received the presentation that K. Moser presented to the Planning and Environment Committee on Monday, April 16, 2018, on behalf of the EEPAC.

3.5 South London Wastewater Servicing Study

That the Civic Administration BE REQUESTED to provide an electronic copy of the South London Wastewater Servicing Study to the Environmental and Ecological Planning Advisory Committee for its consideration.

3.6 Notice of Project Commencement - Brougdale Dyke Municipal Class Environmental Assessment

That it BE NOTED that the Notice of Study Commencement for the Brougdale Dyke Municipal Class Environmental Assessment, was received.

3.7 Notice of Project Commencement - Riverview Evergreen Dyke Municipal Class Environmental Assessment

That it BE NOTED that the Notice of Project Commencement for the Riverview Evergreen Dyke Municipal Class Environmental Assessment, was received.

- 3.8 Notice of Public Information Centre 3 - Adelaide Street North - Canadian Pacific Railway Grade Separation Municipal Class Environmental Assessment Study

That it BE NOTED that the Notice of Public Information Centre #3 relating to Adelaide Street North Canadian Pacific Railway Grade Separation Municipal Class Environmental Assessment Study, was received.

- 3.9 Notice of Public Meeting Cancellation - Southside Group - 3234, 3263, 3274 Wonderland Road South

That it BE NOTED that the Notice of public meeting cancellation relating to the Southside Group, for the properties located at 3234, 3263 and 3274 Wonderland Road South, was received.

4. Sub-Committees and Working Groups

- 4.1 EEPAC'S Bus Rapid Transit Environment Information Session Review and Recommendations

That the attached Working Group comments dated April, 2018 with respect to the Bus Rapid Transit Environment Information Session review and recommendations BE FORWARDED to the Project Director, Rapid Transit, for consideration.

- 4.2 (ADDED) Wetland Sub-Committee

That it BE NOTED that the Environmental and Ecological Planning Advisory Committee heard a verbal update from R. Trudeau, Chair, Wetlands Sub-Committee, with respect to the Sub-Committee meeting held on April 19, 2018.

5. Items for Discussion

- 5.1 Water and Wastewater Anticipated Environmental Assessments Table

That it BE NOTED that the 2018 Water and Wastewater Anticipated Environmental Assessments table, was received.

- 5.2 Hyde Park Community Storm Drainage and Stormwater Management Servicing Municipal Class EA Addendum – Final Report

That B. Krichker BE REQUESTED to review the Hyde Park Community Storm Drainage and Stormwater Management Servicing Municipal Class Environmental Assessment Addendum - Final Report and report back at the June, 2018, Environmental and Ecological Planning Advisory Committee meeting with respect to this matter.

6. Deferred Matters/Additional Business

- 6.1 (ADDED) Parker Stormwater Management Facility – Water Balance Report

That the attached Working Group comments with respect to the Parker Stormwater Management Facility, Water Balance report BE FORWARDED to P. Titus, Senior Technologist, for consideration.

6.2 (ADDED) Notice of Public Information Centre #2 - Southdale Road West Improvements

That it BE NOTED that the Environmental and Ecological Planning Advisory Committee received the attached Notice of Public Information Centre #2, with respect to the Southdale Road West Improvements - Pine Valley Boulevard to Colonel Talbot Road Municipal Class Environmental Assessment; it being noted that S. Levin will attend the Public Information Centre on behalf of EEPAC.

6.3 (ADDED) Draft Plan of Subdivision and Zoning By-law Amendment - 600 Sunningdale Road West

That, the following actions be taken with respect to the attached Notice of Planning Application for a draft Plan of Subdivision and Zoning By-law Amendment for the property located at 600 Sunningdale Road West:

- a) Working Group BE ESTABLISHED consisting of S. Levin and C. Dyck to review and report back at the next Environmental and Ecological Planning Advisory Committee meeting with respect to this matter; and,
- b) C. Smith, Senior Planner, BE REQUESTED to provide an electronic copy of the hydrogeological study with respect to this property to the EEPAC.

7. Adjournment

The meeting adjourned at 7:13 PM.

Trees and Forests Advisory Committee

Report

4th Meeting of the Trees and Forests Advisory Committee
April 25, 2018
Committee Room #4

Attendance PRESENT: R. Mannella (Chair); T. Khan, J. Kogelhelde, C. Linton, N. St. Amour, M. Szabo and R. Walker and J. Bunn (Acting Secretary)

ABSENT: C. Haindl and G. Mitchell

ALSO PRESENT: A. Beaton, J. Ramsay and J. Spence

The meeting was called to order at 12:15 PM.

1. Call to Order

1.1 Disclosures of Pecuniary Interest

That it BE NOTED that no pecuniary interests were disclosed.

2. Scheduled Items

None.

3. Consent

3.1 3rd Report of the Trees and Forests Advisory Committee

That it BE NOTED that the 3rd Report of the Trees and Forests Advisory Committee, from its meeting held on March 28, 2018, was received.

3.2 Municipal Council Resolution - 4th Report of the Environmental and Ecological Planning Advisory Committee

That it BE NOTED that the Municipal Council resolution from its meeting held on April 10, 2018 with respect to the 4th Report of the Environmental and Ecological Planning Advisory Committee, was received.

4. Sub-Committees and Working Groups

None.

5. Items for Discussion

5.1 Oak Wilt Status Update

That the update on the Oak Wilt Status BE DEFERRED to the next meeting of the Trees and Forests Advisory Committee due to the fact that the individual giving the update was not in attendance at the meeting.

5.2 Suggested Locations for Tree Planting or Naturalization Projects

That the Civic Administration BE REQUESTED to review the attached submission from J. Kogelheide, with respect to suggested locations for tree planting or naturalization projects and report back to the Trees and Forests Advisory Committee on the feasibility of the locations.

6. Deferred Matters/Additional Business

6.1 (Added) Tree Protection By-law Working Group

That a Working Group BE ESTABLISHED, consisting of M. Szabo, C. Linton and A. Morrison, to review the Draft Tree Protection By-law with assistance from J. Spence, Manager, Urban Forestry.

7. Adjournment

The meeting adjourned at 1:37 PM.

Advisory Committee on the Environment

Report

6th Meeting on the Advisory Committee on the Environment
May 2, 2018
Committee Room #4

Attendance PRESENT: S. Ratz (Chair), K. Birchall, M. Bloxam, S. Brooks,
S. Hall, J. Howell, L. Langdon, G. Sass, N. St. Amour, D. Szoller,
A. Tipping and J. Bunn (Secretary)

ABSENT: R. Harvey, M. Hodge and T. Stoiber

ALSO PRESENT: T. Arnos, T. Conlon, D. Pavletic and K.
Teeter

The meeting was called to order at 12:16 PM.

1. Call to Order

1.1 Disclosures of Pecuniary Interest

That it BE NOTED that no pecuniary interests were disclosed.

2. Scheduled Items

2.1 Potential Pollination Initiatives

That the following actions be taken with respect to potential pollination initiatives;

a) the Civic Administration BE REQUESTED to research and report back to the Advisory Committee on the Environment (ACE) with respect to the City of London being certified with Bee City Canada; it being noted that ACE supports the initiatives of Bee City Canada; and,

b) L. McDougall, Ecologist Planner, BE REQUESTED to present at a future meeting of the ACE with respect to an update on pollination work being done by the City of London;

it being noted that the attached presentations from B. Ellis and G. Sass, were received.

2.2 Blue Communities Project

That the Civic Administration BE REQUESTED to report back to the appropriate committee with respect to the feasibility of implementing the Blue Communities Program in London; it being noted that the Advisory Committee on the Environment received a verbal presentation from J. Picton-Cooper with respect to this matter.

3. Consent

3.1 5th Report of the Advisory Committee on the Environment

That it BE NOTED that the 5th Report of the Advisory Committee on the Environment, from its meeting held on April 4, 2018, was received.

3.2 Municipal Council Resolution - 4th Report of the Environmental and Ecological Planning Advisory Committee

That it BE NOTED that the Municipal Council resolution, from its meeting held on April 10, 2018, with respect to the 4th Report of the Environmental and Ecological Planning Advisory Committee, was received.

3.3 ACE Presentation/Meeting List

That it BE NOTED that the list of upcoming Advisory Committee on the Environment presentations and events, as of April 25, 2018, from S. Ratz, was received.

4. Sub-Committees and Working Groups

None.

5. Items for Discussion

None.

6. Deferred Matters/Additional Business

None.

7. Adjournment

The meeting adjourned at 1:32 pm.



P.O. Box 5035
300 Dufferin Avenue
London, ON
N6A 4L9

April 11, 2018

S. Muscat
AECOM
250 York Street
London, ON N6A 6K2

P. Yeoman
Manager, Development Services

S. Shannon
Technologist II

I hereby certify that the Municipal Council, at its meeting held on April 10, 2018 resolved:

That, the following actions be taken with respect to the 4th Report of the Environmental and Ecological Planning Advisory Committee from its meeting held on March 15, 2018:

- a) the following actions be taken with respect to the Victoria Bridge Environmental Assessment:
- i) the detailed design BE REVIEWED by one of the City of London's Ecologist Planners; and,
 - ii) an Environmental Study Report BE REQUIRED in the Request for Proposal;

it being noted that the Environmental and Ecological Planning Advisory Committee received a presentation appended to the 4th Report of the Environmental and Ecological Planning Advisory Committee from S. Shannon, Technologist II, Transportation Planning and Design and S. Muscat, AECOM, with respect to this matter;

- b) the revised You, Your Dog and Environmentally Significant Areas brochure BE REFERRED back to the Working Group for further amendments and to report back at the next Environmental and Ecological Planning Advisory Committee meeting;
- c) clause 4.2 of the 4th Report BE AMENDED by deleting the clause in its entirety and replacing it with the following:

“the fourth draft of the Green Standards for Light Pollution and Bird-Friendly Development BE REFERRED to the Manager, Development Services, to review and to prepare a version for the Municipal Council's consideration; it being noted that three Advisory Committees have made this recommendation; it being further noted that Section 4.1 of the Guidelines contemplates a light curfew for London; the specific times have been left blank; a suggested light curfew would be from 1:00 AM to 7:00 AM.”;

- d) the fourth draft of the Green Standards for Light Pollution and Bird-Friendly Development BE REFERRED to all City of London Advisory Committees for their consideration; and,

e) clauses 1.1, 2.1, 3.1, 3.2, 3.3 and 6.1 BE RECEIVED. (3.1/6/PEC)



C. Saunders
City Clerk
/lm

- cc. Chair and Members, Accessibility Advisory Committee
Chair and Members, Animal Welfare Advisory Committee
Chair and Members, Diversity Inclusion and Anti-Oppression Advisory Committee
Chair and Members, Community Safety and Crime Prevention Advisory Committee
Chair and Members, London Housing Advisory Committee
Chair and Members, Advisory Committee on the Environment
Chair and Members, Transportation Advisory Committee
Chair and Members, Agriculture Advisory Committee
Chair and Members, London Advisory Committee on Heritage
Chair and Members, Trees and Forests Advisory Committee
Chair and Members, Environmental and Ecological Planning Advisory Committee
Chair and Members, Cycling Advisory Committee
Chair and Members, Childcare Advisory Committee
J. Bunn, Committee Secretary
K. M. Myers, Committee Support Clerk

From: [Pasato, Nancy](#)
To: ["s.levin s.levin"](#)
Cc: [Lysynski, Heather](#); [Feldberg, Matt](#); [MacKay, James](#)
Subject: 39T-16509 - 3614, 3630 Colonel Talbot & 6621 Pack Rd
Date: Monday, May 07, 2018 2:06:19 PM
Attachments: [image001.png](#)

Hi Sandy - I understand that EEPAC wants some clarification on the SLSR and EIS and process related to the above site/subdivision.

- The Subject Land Status Report was a requirement of the complete application for subdivision as a result of pre consultation for the file.
- After review of the initial SLSR it became clear that an EIS would also be required for the site
- We met with the applicant and consultants in January to go over the requirements of the EIS
- In the interim, the Consultants (NRSI) submitted a response to the SLSR comments
- We indicated that going forward and for ease of review, we wanted to see the EIS and SLSR as one document, and include any SLSR responses/responses in this document. This allows for me to circulate it as one document and get responses back in one comprehensive review. Otherwise it will be difficult to keep track and get responses from the agencies in a timely fashion and keep the review rolling when documents come in at different times.

The comments, therefore, that were on the EEPAC agenda as responses to the SLSR from NRSI – EEPAC can review and provide comments if they like, or they can wait until the updated EIS/SLSR is provided and provide more comprehensive responses to that.

I spoke with Sifton and they indicated the revised EIS/SLSR and hydrogeological study will be submitted in the next few weeks, so EEPAC should see something on their agenda either in May or June.

Hopefully that clarifies. If my attendance is still needed at EEPAC please let me know.

Thanks.
Nancy



Nancy Pasato, MCIP, RPP
Senior Planner
Development Services
City of London

300 Dufferin Avenue, London, ON N6A 4L9
P: 519.661.CITY (2489) x 4586 | Fax: 519.930.3501
npasato@london.ca | www.london.ca



MEMO

To: Bruce Page, Environmental & Parks Planning
James MacKay, Environmental & Parks
Planning
Jeff Hachey, Stormwater Engineering
Christine Creighton, UTRCA
Heather Lysynski, EEPAC

From: Nancy Pasato, Development Services

Date: May 15, 2018

Re: **39T-16509/Z-8720 - 3614, 3630 Colonel
Talbot Road & 6621 Pack Road – revised
EIS and Hydrogeological Study**

Please see the attached updated Environmental Impact Study and Hydrogeological Report for the above noted application.

A copy of the latest draft plan submission and circulation is attached for your reference. Please note no changes are proposed to the draft plan as a result of the EIS/Hydrogeological Study.

Please review and provide comments or conditions no later than **Tuesday, June 12, 2018**. Please let me know if you need additional time for review.

Cc: Lou Pompili, Development Services
Blair Hammond, Development Services
File 39T-16509



London
CANADA

300 Dufferin Avenue
P.O. Box 5035
London, ON
N6A 4L9

39T-16509/Z-8720
Nancy Pasato
tel: 519-930-3500
fax: 519-930-3501
e-mail: npasato@london.ca
website: <http://www.london.ca>

October 19, 2017

NOTICE OF REVISED APPLICATION for Approval of Draft Plan of Subdivision and Zoning By-law Amendment

The City of London has received a revised application to subdivide a parcel of land as shown on the map attached. The previous notice of application and accompanying location map for the proposed plan was circulated to you on January 11, 2017. The revised draft plan of subdivision is described below. The City of London has also received a Zoning By-law Amendment application. We are advising you of these applications to invite your comments.

APPLICANT: Sifton Properties Limited

LOCATION: **Municipal Address:** Portion of 3614, 3630 Colonel Talbot Road, and 6621 Pack Road

Planning District: Talbot

Watershed: Dingman Creek

Assessment Roll Number: 080070021000000, 080070015000000

PURPOSE AND EFFECT: The purpose and effect of these applications is to permit the development of a subdivision with 84 single detached lots, a range of cluster housing units (approx. 99-212 cluster housing units), 1 park block and several 0.3 m reserves, road widening and future access blocks, all served by four (4) new local roads.

PROPOSAL: Consideration of a Residential Plan of Subdivision with 84 single detached lots, two (2) medium density blocks, one (1) park block and several 0.3 m reserves, road widening and future access blocks, all served by four (4) new local roads (see attached plan for more information).

Possible Amendment to Zoning By-law Z.-1 to change the zoning from an Urban Reserve (UR4) Zone to: A Residential R1 Special Provision (R1-4(30)) Zone, to permit single detached dwellings with a minimum lot frontage of 12 m and a minimum lot area of 360 m² with a special provision for a 4.5 m minimum and a 7.5 m maximum front yard setback to a dwelling (whereas no maximum is required), a 5.5 m minimum setback to a garage (whereas 6.0 m is required), and a maximum lot coverage of 45% (whereas 40% is required); a Residential R5/R6/R8 (R5-6/R6-5/R8-4) Zone, to permit: R5-6 - cluster townhouse dwellings and cluster stacked townhouse dwellings, at a maximum density of 50 units per hectare and a maximum height of 12.0 m; R6-5 - cluster single detached dwellings, cluster semi-detached dwellings, cluster duplex dwellings, cluster triplex dwellings, cluster townhouse dwellings, cluster apartment buildings and cluster fourplex dwellings, at a maximum density of 35 units per hectare, and a maximum height of 12 m; R8-4 - apartment buildings, handicapped person's apartment buildings, lodging house class 2, stacked townhousing, senior citizen apartment buildings, emergency care establishments, and continuum-of-care facilities, at a maximum density of 75 units per hectare and a maximum height of 13 m; a Residential R5/R6/R7/R8 (R5-6/R6-5/R7 D75*H13/R8-4) Zone, to permit all the above uses, as well as: R7*D75*H13 - senior citizen apartment buildings, handicapped persons apartment buildings, nursing homes, retirement lodges, continuum-of-care facilities, and emergency care establishments at a maximum density of 75 units per hectare and a maximum height of 13.0 m;; and An Open Space (OS1) Zone, to permit conservation lands, conservation works, cultivation of land for agricultural/horticultural purposes, golf courses, private and public parks, recreational golf courses, recreational buildings associated with conservation lands and public parks, campground, and managed forest (see attached plan for more information).

**SUBJECT
LAND
STATUS
REPORT:**

The above noted possible changes could permit a mix of residential uses, parks and pathways. Special provisions for reduced setbacks from the street, and reduced side yard setbacks are also being considered.

The City may also consider adding holding provisions for the following: urban design, water looping, municipal services, and phasing.

A Subject Land Status Report (SLSR), prepared by Natural Resource Solutions Inc., dated November 2016 and revised September, 2017 was submitted with the revised application for draft plan of subdivision. The SLSR is available for public review during regular business hours at the City of London, Development Services, 6th Floor, City Hall.

**PLANNING
POLICIES:**

The Official Plan designates the subject site as "Low Density Residential" which allows single detached, semi-detached, duplex dwellings and cluster housing at a maximum density of 30 units per hectare as the main permitted uses; and "Multi-Family Medium Density Residential" which allows multiple attached dwellings at a maximum density of 75 units per hectare as the main permitted uses.

The subject lands are in the "Neighbourhoods" Place Type in *The London Plan* (Ministry-adopted but not in force and effect), permitting a range of housing including single detached, townhouses and low rise apartments.

The site is presently within an Urban Reserve (UR4) Zone which permits existing dwellings, agricultural uses except for mushroom farms, commercial greenhouses livestock facilities and manure storage facilities, conservation lands, managed woodlots, wayside pits, and passive recreation uses, kennels, private outdoor recreation clubs, and riding stables.

**HOW TO
COMMENT:**

Please call in, mail, fax or email your comments by **Monday, December 4, 2017**. Please refer to the file number or municipal address in all correspondence with City staff. Your opinion on this application is important. Comments will be reviewed and summarized in a report that will be submitted to the Planning and Environment Committee of City Council for consideration. **Please Note:** Personal information collected and recorded through the Public Participation Meeting, or through written submissions on this subject, is collected under the authority of the *Municipal Act, 2001*, as amended, and the *Planning Act, 1990* R.S.O. 1990, c.P.13 and will be used by Members of Council and City of London staff in their consideration of this matter. The written submissions, including names and contact information and the associated reports arising from the public participation process, will be made available to the public, including publishing on the City's website. Video recordings of the Public Participation Meeting may also be posted to the City of London's website. Questions about this collection should be referred to Cathy Saunders, City Clerk, 519-661-2500 ext. 4937.

Your representative on City Council, **Councillor Anna Hopkins (City Hall Telephone Number: 519-661-2500 ext. 4009; Cell Number: 226-927-0439, or email: ahopkins@london.ca)**, would be pleased to discuss any concerns you may have with this application.

A neighbourhood or community association may exist in your area. If it reflects your views on this proposal, you may wish to select a representative of the association to submit comments on your behalf.

APPEALS:

If a person or public body does not make oral submissions at a public meeting, if one is held, or make written submissions to the Manager of Development Services in respect of the proposed Plan of Subdivision, Official Plan or Zoning By-law amendment (if applicable) before:

- i. the Approval Authority gives or refuses to give approval to the Draft Plan of Subdivision;
- ii. the Council of the City of London adopts the proposed Official Plan amendment (if applicable); or,
- iii. the Zoning By-law amendment is passed (if applicable),

**PUBLIC
MEETING:**

the person or public body is not entitled to appeal the decision of the Manager of Development Services or the Council of the City of London to the Ontario Municipal Board and the person or public body may not be added as a party to the hearing of an appeal before the Ontario Municipal Board unless, in the opinion of the Board, there are reasonable grounds to do so.


**FOR MORE
INFORMATION**

The appropriateness of the proposed plan of subdivision will be considered at a future meeting of the Planning and Environment Committee. You will receive another notice inviting you to attend this meeting.

**TO BE
NOTIFIED:**

For additional information, please contact Nancy Pasato at 519-661-2489 ext. 4586, referring to "File 39T-16509/Z-8720", or inquire at the Development Services, 6th Floor, City Hall, 300 Dufferin Avenue, between 8:30 a.m. and 4:30 p.m. weekdays.

If you wish to be notified of the decision of the City of London in respect of this proposed plan of subdivision, you must make a written request to the Manager of Development Services, City of London, P.O. Box 5035, London ON N6A 4L9.



©2017 City of London ON

LOCATION MAP


Subject Site: 3614 Colonel Talbot Road
 Applicant: SIFTON PROPERTIES LIMITED
 File Number: 39T-16509
 Planner: Nancy Pasato
 Created By: Nancy Pasato
 Date: 2017-10-17
 Scale: 1:10100

LEGEND

-  Subject Site
-  Parks
-  Assessment Parcels
-  Buildings
-  Address Numbers

Corporation of the City of London
 Prepared By: Planning and Development





mpc
McCarthy & Brown
 Planning Consultants
 1000 West 10th Street, Suite 100
 Vancouver, BC V6H 2G6
 Tel: 604-681-1111

DRAFT PLAN OF SUBDIVISION
 3614 and 3630 COLONEL TALBOT ROAD
 6621 PACK ROAD
 PROPOSED ZONING
 IN THE CITY OF LONDON
 COUNTY OF MIDDLESEX

Sifton
 Experience. The Difference.SM

DATE SCALE
 1:1,500

3614 and 3630 COLONEL TALBOT ROAD, 6621 PACK ROAD PROPOSED ZONING

PROJECT NO.	12-905
DATE	NOV 11 2011
SCALE	1:1,500
PROJECT	1

Decision making: Comprehensive assessment of trade-offs between wetland protection and potential benefits of development.

A Wetland Conservation Strategy for London.

Recommendations for the City of London and Our Development Partners

Prepared for the City of London by the Ecological and Environmental Planning Advisory Committee

1. Introduction

One of the most ecologically diverse and productive ecosystems in the world, wetlands are rich in biodiversity, providing habitat for many species. In the Great Lakes region, wetlands are vital for sustaining populations of a variety of wildlife species and plant life. They also render many ecological services including, water purification, flood regulation, sediment trapping and nutrient cycling. And as we navigate the uncertainties of a changing climate in the coming years, wetlands provide crucial services, removing greenhouse gas from the atmosphere, regulating temperatures and decreasing the urban heat island effect, slowing the impact of droughts, and reducing flood and erosion risks. While they provide 40 percent of all ecosystem services worldwide, they only cover 1.5 percent of the Earth's surface, with Russia and Canada home to the largest wetland areas. Canada's wetlands are diverse, consisting of marshes, bogs, fens, swamps and open water. Wetlands in Ontario currently cover 350,000 square kilometres, comprising 25 percent of all the wetlands in Canada and six percent of the world's wetlands (A Wetland Conservation Strategy, p.2). In addition, they keep communities healthy and safe, and provide opportunities for recreation.

Though wetlands are one of the most important ecosystems on the planet, they are also one of the most threatened due to human activities -- urbanization, economic development and climate change (Pattison-Williams et al., 2017). Wetland loss and degradation around the world has occurred at an alarming rate; over 64 percent of the world's wetlands have disappeared in a little over a century (Pattison-Williams et al., 2017). In Canada, approximately twenty million hectares of wetland have been drained for agricultural purposes since European settlement, totalling an approximately 70 percent loss of wetlands from historical highs (Pattison-Williams et al., 2017). In southern Ontario in the 19th century, two million hectares -- or 25 percent of the terrestrial area -- consisted of wetlands. By 2002, 72 percent (1.4 million hectares) had been lost largely due to agriculture and expanding urban and suburban development. (Ducks Unlimited, p. 1). From 1982 until 2002, southern Ontario lost another 3.5 percent of its pre-settlement wetlands, equally 70,854 hectares, at an average of 3545 hectares per year (Ducks Unlimited, 2010, p.1).

In southwestern Ontario, the loss of wetlands has been the most dramatic, with over 85 percent of the areas originally covered in wetlands converted to other uses. In Middlesex County, 5.1-20 percent of the area was covered by wetlands prior to settlement, but by 2002 less than five percent was covered in wetlands (Ducks Unlimited, 2010, p.9). Between 85 and 100 percent of the wetlands were converted in Middlesex county between 1800-2002 (Ducks Unlimited, 2010, p. 14). These

studies only covered wetlands that are greater than 10 hectares in area, which signifies that if smaller wetlands were included, the annual loss of wetlands would be even greater, especially since smaller wetlands are frequently filled in for development projects, such as construction of housing. With that degree of destruction, southern Ontario has foregone ecosystem services locally and beyond, lost essential habitats for threatened, endangered and/or migratory species, and witnessed a decrease in species' populations.

Until recently, our understanding of wetlands -- and the services and functions they provide -- was limited. Though our knowledge is expanding and society increasingly recognizes the importance of wetland preservation and, in some cases, restoration, wetland losses still continue at an astonishing rate. Wetlands are often considered insect-infested wastelands, and as such land use policies have not and do not prioritize their conservation. Instead, they were (and are) drained and/or filled in for roads, agricultural use, housing developments, new shopping complexes, or even used as waste sites. As Pattison-Williams et al. noted, "Loss of riparian wetlands has occurred because natural ecosystems such as wetlands are not currently valued by the market system and few financial incentives exist for landowners to maintain them" (Pattison-Williams et al., 2017).

At the same time that they are threatened by development projects, wetlands are subject to several stressors, such as encroachment by invasive species, sedimentation, nutrient loading and pollution from agricultural and urban runoff (e.g. phosphorus from fertilizers, de-icing salts), and climate change. In London, urban expansion and development pose a serious threat to wetlands. In year 2017, a large number of development projects involving wetlands were undertaken in London, Ontario. Wetlands are rarely exposed to a single threat; multiple stressors usually interact to exacerbate problems. For instance, invasive species thrive in areas where native species are struggling due to a changing climate. Indeed, climate change has emerged as a major threat to wetlands, as alterations in temperatures and weather patterns may lead to shrinking or disappearance of wetlands. With altered rain patterns, and severe rain events, wetlands may shift from one form to another, or the vegetation may change as native species struggle with temperature differences, or animal species' relationships may alter (A Wetland Conservation Strategy for Ontario, 2017).

Ontario's public strongly supports wetland conservation (Lantz et al., 2013). Given the significant loss of wetlands globally and the large area of wetlands in Ontario, the province has a duty to protect the remaining wetlands it has, and to restore and/or rehabilitate destroyed and/or degraded wetlands. Ontario's wetlands contribute to the province's rich biodiversity and promote the health and safety of its citizens. Going forward, the province's population will continue to grow, placing increasing demands on resources. Consequently, efforts to conserve natural areas, like wetlands, will continue bump up against economic interests. Therefore, the City of London requires a clear set of guidelines governing development projects, such as housing plans and expanded transportation infrastructure, to avoid disturbance, reduce impacts and mitigate unavoidable damage.

2. Definitions

- **Wetland** -- An ecosystem which is seasonally or permanently covered in standing water or saturated with water for a least part of the year, or where the water table is close to or at the surface, such that vegetation has adapted for growth in saturated conditions.
- **Swamp** -- A wetland with trees, associated with flowing water, and tends to be highly productive.
- **Marsh** -- A wetland without trees, associated with flowing water, and tends to be highly productive. Dominated by non-woody plants such as cattails, rushes, pond lilies and submerged plants.
- **Bog** -- A wetland with acidic soils that may or may not have trees, with waterlogged soils -- fed solely by precipitation -- that tend to accumulate peat, and is associated with low productivity. They are often very old, perhaps thousands of years. Bogs often have a low diversity of species. Rare in southern Ontario.
- **Fen** -- A wetland dominated by grasses, sedges and rushes that may or may not have trees, with waterlogged soils that tend to accumulate peat. Fens are fed by groundwater and surface water runoff, and is associated with low productivity. Rare in southern Ontario.
- **LID** -- Low Impact Development
- **Restoration** -- Bringing back areas degraded through actions such as in-filling, changes in drainage patterns, sedimentation, vegetation removal and pollution
- **Rehabilitation/Creation/Re-creation** -- Bringing back once-existing wetlands
- **Biodiversity Offsetting** -- Compensating (or attempting to compensate) for losses of biodiversity at an impact site by either creating ecologically equivalent gains or credits at an in-site or off-site location. The purpose of biodiversity offsetting is to incur no-net loss of biodiversity.
- **Mitigation Hierarchy** -- A tool used in biodiversity offsetting to minimize the harm that occurs due to a project. The preference should be given first to avoiding negative impacts, then to minimizing impacts at a project site, followed by restoration/rehabilitation and finally, offsetting biodiversity losses that cannot be avoided.
- **Urban Heat Island Effect** -- When an urban or metropolitan area is significantly warmer than rural areas due both to human activities and the built environment.
- **Additionality** -- To what degree does an offsetting project generate new and additional contributions to biodiversity conservation/wetland conservation.
- **Wetland Offsetting** -- Compensation for the negative impacts of development through the restoration or creation of new wetlands to achieve no-net-loss or a net environmental gain.
- **Mitigation banking** -- The developer purchases offset credits from a wetland bank, that is, an area that has been previously restored, created, enhanced or preserved and set aside by a third party, and certify for compensation. The banker is responsible for the success of the compensation project.
- **Invasive species** -- a non-native species that outcompetes native species and becomes a nuisance or threat to ecosystems.

2. Purpose and Justification

London is a growing and dynamic city. Development projects, especially housing and commerce, continue to expand, regularly coming into conflict with natural areas. With a growing population and economic and social pressures to expand infrastructure and development, project proposals will increasingly come into conflict with our remaining wetlands. Ecosystem services -- considered free, common goods -- provided by wetlands are regularly omitted in the market prices of projects. Consequently, wetland loss and/or disturbance is rarely given adequate consideration in land-use planning decisions. Currently, land conversion is the biggest threat in southern Ontario. Urban pressures are driving up the price of land, making land markets highly competitive, which ultimately leads to significant rates of wetland conversion (Lantz et al., 2013).

Provincial and municipal action is vital to ensure that the region's wetlands can continue to provide ecosystem services, the benefits of which are manifold for both the environment and society. Ontario is moving forward with a strategy to stop wetland loss and to restore wetlands where the largest losses have occurred. The City of London likewise needs to have clear guidelines regarding wetlands, their preservation, restoration and rehabilitation.

International Law and Wetlands. Globally nations have recognized the need to preserve wetlands. Internationally, the protection of wetlands is governed by Ramsar, adopted in 1971 and came into force in 1975. Canada ratified Ramsar in 1982, committing itself to wetland conservation. Ontario has eight registered wetlands. The Ramsar Convention conceived to protect "the fundamental ecological functions of wetlands as regulators of water regimes and as habitats supporting a characteristic flora and fauna, especially waterfowl" (Birnie and Boyle, 2002, p. 611). It obliges nations to identify special wetland areas, to list them on the List of Wetlands of International Importance, and to "promote" their protection and wise use.

At a subsequent conference in Regina in 1987, "wise use" of wetlands was defined as "their sustainable utilization for the benefit of humankind in a way compatible with the maintenance of the natural properties of the ecosystem" (Birnie and Boyle, 2002, p. 618). Later, the Working Group on Criteria and Wise Use defined "sustainable utilization" as "human use of a wetland so that it may yield the greatest continuous benefit to present generations whilst maintaining its potential to meet the needs and aspirations of future generations" for the purposes of Article 3 of the Ramsar convention (Birnie and Boyle, 2002, p. 618). They also found that activities involving wetlands should be governed by the precautionary principle, and when complete knowledge is lacking regarding the outcomes of an activity, that activity should be prohibited (Birnie and Boyle, 2002). To date however, the majority of nations are not applying the precautionary principle regularly in regards to wetlands, as evidenced by the continued rapid loss of wetlands.

Wetlands are also governed by the 1972 World Heritage Convention, as they form part of our "natural heritage" -- "areas which constitute the habitat of threatened species of animals of outstanding universal value from the point of view of science and conservation" (Article 2).

Beyond Ramsar, wetlands also receive protection through the 1979 Bonn Convention on Migratory Species, through its calls for conservation of habitat for migratory species. Habitat is defined as "any

area in the range of a migratory species which contains suitable living conditions for that species” (Birnie and Boyle, 2002, p. 611). Wetlands clearly fall under this realm as these ecosystems provide crucial habitat for a wide range of migratory species.

The Convention on Biological Diversity likewise indirectly provides protection for wetlands through Articles 8(d) which “[p]romote[s] the protection of ecosystems, natural habitats and the maintenance of viable populations of species in natural surroundings”. Article 8(e) also asks for signatories to “Promote environmentally sound and sustainable development in areas adjacent to protected areas with a view to furthering protection of these areas. Also relevant to wetlands, given that many have been destroyed and/or degraded is Article 8(f), which asks states to “[r]ehabilitate and restore degraded ecosystems and promote the recovery of threatened species, inter alia, through the development and implementation of plans or other management strategies. Finally, Article 8(h) is important when we consider development projects within the City in or around wetlands as it asks states to “[p]revent the introduction of, control or eradicate those alien species which threaten ecosystems, habitats or species”. Invasive species regularly take hold after wetland disturbance, either due to species’ stress or due to contaminated construction equipment (like we have seen with the spread of Phragmites in our region). Finally, the Aichi Targets of 2010 (particularly Target 11) requires signatories to protect 17 percent of their nation’s terrestrial area by 2020. However, the majority of nations are not on track to meet that goal; Ontario has only succeeded in protecting 11 percent of its terrestrial area so far.

Often conservation is limited to areas within parks and protected areas; more must be done to protect biodiversity and ecosystem services beyond reserves in daily operations and land use planning. The Convention on Biological Diversity states in Article 6(b) Contracting Parties shall [...] “Integrate, as far as possible and as appropriate, the conservation and sustainable use of biological diversity into relevant sectoral or cross-sectoral plans, programmes and policies. Conservation must be incorporated into all areas of policy and development to ensure that wetlands are afforded the appropriate level of protection.

Finally, since wetlands are an integral part of dealing with climate change, both mitigation and adaptation, their protection also falls under the United Nations Framework Convention on Climate Change 1992.

Provincial Legislation: Since 1982 wetland conservation has grown in importance, as the province recognizes wetlands as one of its most important natural capital assets. In the early 1980s, Ontario issued a discussion paper titled “Toward a Wetland Policy for Ontario”. From that, the government developed a policy paper called “Guidelines for Wetland Management in Ontario” (1984). In 1992 the government issued the Wetland Policy Statement. Now, over twenty different pieces of legislation govern wetland management, while five provincial ministries, two federal departments, a provincial agency, 36 conservation authorities (which are meant to support municipalities) and 444 municipalities implement wetland policies (A Wetland Conservation Strategy for Ontario, 2017).

Perhaps the most important piece in wetlands conservation today is the 2014 *Provincial Policy Statement*, which prohibits development or site alterations in all provincially significant wetlands, or in lands adjacent to provincially significant wetlands, unless it can be demonstrated that the wetland and/or its ecological functions will suffer no negative impacts (PPS 2.1.4(a)) and that 2.1.6 “[d]evelopment and site alteration shall not be permitted in fish habitat except in accordance with provincial and federal requirements” (PPS 2.1.6). It also states: “The diversity and connectivity of natural features in an area, and the long-term *ecological function* and biodiversity of *natural heritage systems*, should be maintained, restored or, where possible, improved, recognizing linkages between and among *natural heritage features and areas, surface water features, and groundwater features*” (PPS 2.1.2). Furthermore, the *Provincial Policy Statement* makes clear that all of the policies contained within it are minimum standards only and that planning authorities and decision-makers are free to take even more stringent measures regarding conservation. The *Provincial Policy Statement* asserts that our natural heritage is a resource: “The Province must ensure that its resources are managed in a sustainable way to conserve biodiversity, protect essential ecological processes and public health and safety, provide for the production of food and fibre, minimize environmental and social impacts, and meet its long-term needs” (p.4).

2.1.1 “Natural features and areas shall be protected for the long-term” (PPS, p. 22).

Currently, Ontario’s wetlands strategy is guided by “A Wetland Conservation Strategy for Ontario 2017-2030”. It strives for a social and political climate where “Ontario’s wetlands and their functions are valued, conserved and restored to sustain biodiversity and to provide ecosystem services for present and future generations” (A Wetland Conservation Strategy for Ontario, 2017, p. iii). The strategy comprises two targets: the net loss of wetland area and function will stop by 2025 where wetland loss is the greatest, and a net gain in wetland area and function will occur by 2030 where wetland loss has been the greatest. The Strategy also puts forth the principle that wetlands should be conserved according to three hierarchical priorities -- protect (retain area and functions of wetlands), mitigate (minimize further damage), restore (improve and re-establish wetland area and function).

Most significantly, the fourth principle in “A Wetland Conservation Strategy for Ontario” calls for a precautionary approach regarding wetlands and development and other projects affecting wetlands. This stipulation means incorporating wetland conservation into environmental impact statements provincially and municipally.

Wetland conservation equally appears in other provincial environmental policies. In 2011 Ontario published its biodiversity strategy called “Biodiversity: It’s in our Nature”, which outlined the province’s plan to protect biodiversity from 2012-2020. It specifically includes actions to improve wetland conservation. This strategy falls in line with the *Provincial Policy Statement* what addresses the preservation of the habitat of endangered and threatened species (PPS 2.1.7). Additionally, Ontario’s Climate Change Strategy and Action Plan views wetland conservation as key to mitigating carbon emissions and the impacts of climate change. Ontario has been updating its climate change adaptation planning with “Climate Ready: Ontario’s Adaptation Strategy and Action Plan, 2011-

2014”, which has many reference to maintaining and restoring ecosystem resilience, including protecting and restoring wetlands. And, the *Provincial Policy Statement* asserts that “Healthy, liveable and safe communities [should be] sustained by promoting development and land use patterns that conserve biodiversity and consider the impacts of climate change” (PPS, 1.1.1(h)).

Municipal Policies: The London Plan

Land use planning has the greatest influence on the conservation of wetlands. Official plans (e.g. The London Plan), local decisions on land use, and community based land use plans have far reaching impacts on the green spaces of our City, and how the City moves forward with approval for development projects that conflict with conservation values. The London Plan has clear provisions for the “identification, protection, conservation, enhancement, and management of our Natural Heritage System” (1293.1). Of particular importance for London as it considers the retention of its wetlands, no matter how small, is The London Plan’s statement that “[t]he diversity and connectivity of natural features and areas, and the long-term ecological function and biodiversity of Natural Heritage Systems, will be maintained, restored or, where possible, improved, recognizing linkages between and among natural heritage features and areas, surface water features, and groundwater features” (*The London Plan* 1301). The City plans to ensure that its Natural Heritage System is “protected, conserved, enhanced, and managed for present and for future generations by [...] [p]rotect[ing], maintain[ing], and improv[ing] surface and groundwater quality and quantity by protecting wetlands [...]” (*The London Plan*, 1308).

The London Plan specifies that no development or alteration shall occur in provincially significant wetlands as evaluated and confirmed by the Ministry of Natural Resources and Forests (MNR), designating them instead as Green Space (*The London Plan*, 1332, 1333, 1390). This provision is in accordance with the *Provincial Policy Statement*, but in essence it only applies to Sifton Bog and Westminster Ponds, the two PSWs located within London.

The key clause of *The London Plan* for the purposes of these guidelines is 1334, which states that “[d]evelopment and site alteration shall not be permitted within a wetland. There shall be no net loss of wetland features or functions. In some instances, and in consultation with the conservation authority having jurisdiction, the City may consider the replacement of wetlands where the features and functions of the wetland may be provided elsewhere and would enhance or restore the Natural Heritage System” (*The London Plan*, p. 350). Moreover, 1335 goes on to say “Development and site alteration shall not be permitted within and/or adjacent to an unevaluated wetland identified on Map 5 and/ or if an Ecological Land Classification determines that a vegetation community is a wetland that has not been evaluated”. And 1391 again reiterates that ““Development and site alteration shall not be permitted in [...] wetlands [...] unless it has been demonstrated that there will be no negative impacts on the natural heritage features or their ecological functions”. These paragraphs do not specify that the wetland must be “provincially significant” nor does they qualify ‘wetland’ with a size. However, clause 1334 does suggest an opening for relocation and/or offsetting disturbed wetlands, but without specifications on how these projects should be undertaken or monitored. It is this gap that these guidelines will attempt to fill.

2.1 Habitat and Species Impacts

While the economic benefits of wetlands tend to focus on flood control and water purification, wetlands provide other irreplaceable ecological services. One of the economically unappreciated features of wetlands is their contribution to biodiversity conservation and maintenance of the web of life. Since marshes and swamps are usually shallow enough to allow sunlight to penetrate and to allow for seasonal warming, they support photosynthetic activity, making them highly productive areas, full of diverse and abundant species. In Ontario, wetlands are biodiversity hotspots, supporting a variety of plants, birds, insects, amphibians and fish. Wetlands provide food and habitat for a large variety of species, and are particularly valuable to migratory water and shore bird species for breeding and nesting.

Wetlands come in a variety of types each with their own characteristics and suite of species. Wetland types are recognizable by their indicator and keystone species (Table 1).

Table 1: Common keystone and indicator species in Southwestern Ontario's Wetlands

Species	Habitat Types	Habitat requirements
Broadleaf cattail <i>Typha latifolia</i>	<ul style="list-style-type: none"> • Marshes • Bogs • Fens 	<ul style="list-style-type: none"> • A common resident of the marsh environment, it is usually one of the first species to colonize new habitats • It is common in early-seral and open-canopy communities • This species requires full sunlight • Light and warmth from sunlight are required to germinate seeds • Seeds germinate in all conditions, acidic, neutral or basic but will not germinate in waters above 1 atm of osmotic pressure • Seeds will also germinate in low oxygen conditions • Cattails can occur in sand, silt, loam and clay substrates
Small-fruited bulrush <i>Scirpus microcarpus</i>	<ul style="list-style-type: none"> • Marshes • Fens 	<ul style="list-style-type: none"> • A common resident of the marsh environment, it can tolerate both full-sunlight and shade • This species requires silty/mucky soil with a high water holding capacity • This species grows best in neutral but can also grow in acidic conditions
Soft maples <i>Acer saccharinum, A. rubrum</i>	<ul style="list-style-type: none"> • Swamps 	<ul style="list-style-type: none"> • These species are commonly found along the edges of swamps and is tolerant to waterlogged soils and flooding. • They can tolerate sun or shade and in all soil types. • They can thrive in acidic, neutral and basic conditions
Black spruce	<ul style="list-style-type: none"> • Bogs • Swamps 	<ul style="list-style-type: none"> • This species is indicative of a bog environment and is also found in coniferous swamps. • It is tolerant of highly acidic soils and is most abundant in peat bogs. • It is a pioneer species in bogs and can invaded the <i>Spaghnum</i> spp. mat. It grows well in a variety of soils, moisture levels and light conditions.
Common cottongrass <i>Eriophorum angustifolium</i>	<ul style="list-style-type: none"> • Bogs • Fens • Marshes 	<ul style="list-style-type: none"> • These species are commonly found in bog and fen environments and can be occasionally found in open wetlands

		<ul style="list-style-type: none"> • This species prefers calcareous peat and acidic soil. It grows well in poorly drained peat, sand, clay or loam and can survive in chalybeate (iron-enriched) water. • This species survives best in full sun but can grow in partial sun.
<p>Fragrant white water lily <i>Nymphaea odorata</i></p>	<ul style="list-style-type: none"> • Marshes 	<ul style="list-style-type: none"> • The fragrant white water lily is a perennial plant floating aquatic plant that can grow in up to 8' of water. • It is common in wetlands and can be found in wetlands, lakes and slow-moving areas of rivers. • These plants have faunal associations with a large number of insect species and have food value for ducks. • This species prefer slightly acidic water rather than calcareous and alkaline.
<p>Purple pitcher plants <i>Sarracenia purpurea</i></p>	<ul style="list-style-type: none"> • Bog • Fen 	<ul style="list-style-type: none"> • This species is indicative of a bog environment and has evolved to survive in the low nutrient and highly acidic environment. It can also be found in fens, although is much less common. • This species is adapted to a nutrient poor soil that are deficient from trace elements such as molybdenum. It requires acidic soils for growth. • This species obtains its essential elements by preying upon invertebrates such as flies, ants and spiders. These species fly into the pitcher and drown in the pitcher water. Digestion is performed through a number of digestive enzymes released by the pitcher plants in addition to a digester community comprised of bacteria, protists, rotifers and other invertebrates such as the mosquito <i>Wyeomyia smithii</i>, the majority of these species being specialists and reliant on the pitcher plant.

<p>Sphagnum moss <i>Sphagnum</i> spp.</p>	<ul style="list-style-type: none"> • Bogs • Fens 	<ul style="list-style-type: none"> • These species are the keystone species of the bog and fen environments. • They retain a large amount of water while both living and while dead. Further, they do not decay readily as a result of the phenolic compounds found in their tissues. As such, their presence forms large mats of vegetation on acidic water, the basis for bogs. • Their presence helps shape the wetland environment for other species such as carnivorous plants (ie. Purple pitcher plant) and other acidic tolerant plants.
---	--	---

Wetlands are also a home to a number of Ontario’s species at risk (Table 2).

Table 2: Species at risk that occur in London’s wetlands

Species	Status in Ontario	Habitat type	Habitat requirements	Threats
Eastern Ribbonsnake <i>Thamnophis sauritus</i>	Special concern	<ul style="list-style-type: none"> • Marshes • Fens • Bogs • Swamps 	<ul style="list-style-type: none"> • Found in areas with permanent water near terrestrial habitat (Harding 1997; Schribner and Weatherhead 1995) with shallow water and low, dense shoreline vegetation (Minton 1992; Cosewic 2002) • Habitat includes bare substrate near wetlands including gravel, cobble and boulders (Desroches and Leparé 2004). • Terrestrial habitats close to wetlands include open and sunny areas where there are clumps of grasses, sedges or low shrubbery (Harding 1997; Imlay 2009). • Habitats used by Eastern ribbonsnakes must have a high abundance of amphibians, particularly frogs, as these are their primary food source (Carpenter 1952; Brown 1979; COSEWIC 2012). 	<ul style="list-style-type: none"> • Their biggest threats are loss of habitat including loss of wetland and riparian habitat (Environment Canada 2015).
Eastern prairie fringed orchid <i>Platanthera leucophaea</i>	Endangered	<ul style="list-style-type: none"> • Marshes • Fens • Swamps 	<ul style="list-style-type: none"> • Requires open conditions with full sunlight and is restricted to graminoid-dominated vegetation communities (Bowles 1993). • It requires soil that is neutral to slightly calcareous (Bowles et al. 2005, Case 1987, Bowles 1983) and can tolerate 	<ul style="list-style-type: none"> • The largest threats to the orchid are the lack of suitable habitat due to its specific

			<p>pHs of between 5.3 and 7.5 (Zambrana Engineering Inc. 1998).</p> <ul style="list-style-type: none"> • It is also found in a range of soil types, including deep, black calcareous silt loams, and muck soils (Zambrana Engineering Inc. 1998). • Wetland habitats where it occurs in ontario are fens dominated by Wire Sedge (<i>Carex lasiocarpa</i>), fens dominated by Common Reed (<i>Phragmites australis</i>) and other sedges (<i>Carex</i> spp.) and poor fen mats around lakes dominated by sphagnum moss and ericaceous shrubs (Eastern Prairie Fringed-orchid Recovery Team 2010) • The eastern fringed-orchid is adapted to fluctuations in water levels (COSEWIC 2003) 	<p>habitat needs as well as habitat loss and degradation (Eastern Prairie Fringed-orchid Recovery Team 2010)</p>
<p>Spotted turtle <i>Clemmys guttata</i></p>	<p>Endangered</p>	<ul style="list-style-type: none"> • Marshes • Bogs 	<ul style="list-style-type: none"> • This species is commonly found in areas with water associated with lake, marsh, pond and bog environments. • These species rely on connected wetlands and do not disperse more than 3km between suitable wetland habitat 	<ul style="list-style-type: none"> • Two of its major threats are habitat loss and degradation. The loss of wetlands and wetland degradation, especially by way of common reed (<i>Phragmites australis</i>), are

				devastating to these turtles and the current state of many wetlands may not support populations long term
--	--	--	--	---

2.2 Physical Environment Impacts

Wetlands are vital for people and their health and safety, through their ability to control flood waters, protect against natural disasters, mitigate and adapt to climate change, and purify water. In a bid to encourage preservation and restoration of wetlands, the economic benefits of these ecosystems are often highlighted. In particular, economists point to the monetary value of clean water, flood and erosion mitigation and climate moderation. This ability to store flood water and reduce the amount of water flowing downstream alone is valued at billions of dollars a year. The natural water purification system within wetlands removes silt and sediments, preventing them from entering rivers, gathering nutrients and forming fertile agricultural land. Chemical reactions detoxify and neutralize toxic substances in the water, thereby protecting us from pollution. London is surrounded by agricultural land and wetlands easily remove organic material, particularly phosphorus and nitrogen, preventing it from flowing into our river system. They alleviate drought by holding water when conditions are dry. Water accumulated in wetlands also seeps into the ground, helping to replenish underground aquifers. Wetlands work to mitigate climate change by absorbing greenhouse gases, acting as carbon sinks that stabilize climate conditions. In places in Ontario, such as Lake Simcoe, it has been shown that loss of wetland ecosystems leads to eutrophication of lakes. Simply put, wetlands are an environmentally positive and cost effective means by which to treat a variety of environmental issues

3. General Information

3.1 Wetlands as an important natural heritage feature of our city

Our wetlands are important for our city. With rapid urban growth and development projects, they are a vanishing ecosystem within and beyond the city limits. They provide green space, stepping stones for species on migratory routes, habitat for insects and amphibians, and recreational opportunities for London's citizens. London's wetlands help maintain and enhance the city's biodiversity, forming a network of linkages connecting species. They are transitional habitats, that connect aquatic and terrestrial habitats. As more of the city's land is transformed with impervious covers, the remaining wetlands become increasingly important for flood management. And with climate change, the city's wetlands lessen the urban heat island effect and help combat drought that comes with altered weather patterns. They form a significant part of our natural and cultural heritage landscapes. London is fortunate to have two Provincially Significant Wetlands in two of its Environmentally Significant Areas -- Sifton Bog and Westminster Ponds.

Wetlands can range in size from very small (only a few metres squared) to hundreds of kilometres squared. Wetlands may be isolated, occur along the edges of lakes and rivers, or exist in conjunction with other natural areas such as woodlands, shrublands and native grasslands. In some cases, closely spaced wetlands related in a functional way can also form what is known as a wetland complex. In southern Ontario the average wetland is 25 hectares and most are swamps, dominated by trees and shrubs. They take many years to develop. London has many small wetlands that

frequently come into conflict with development projects and so the city must have clear guidelines on how to deal with wetlands going forward.

3.2 Primary screening when changes to a wetland are proposed

The simple procedure systematically considers key criteria to assess the opportunities and implications of whether or not to implement changes to a specific wetland.

1. Identify present ecological classification of the wetland

- a) Is the wetland “evaluated wetland” [Ontario Wetland Evaluation System](#)
 - i) Yes.....Access the evaluation file
 - ii) No.....Go To 2. Perform Comprehensive evaluation

Wetlands are ranked to determine whether they should receive special protection as “provincially significant”. Significance is determined by the Ontario Wetland Evaluation System (OWES) . Provincially Significant Wetlands (PSWs) are those areas identified by the province as being the most valuable. Provincially Significant Wetlands are identified using objective criteria based on the best available science The OWES ranking system is a standardized method of assessing wetland functions and societal values, which enables the province to rank wetlands relative to one another. A wetland that has been evaluated using the criteria outlined in the OWES is known as an "evaluated wetland" and will have a "wetland evaluation file. As wetlands may change over time OWES files for a given wetland is considered as an “open file”.

2. Perform Comprehensive evaluation of Present Ecological Condition

- a) Undisturbed Go To 3.1, 3-2
- b) Moderate disturbed..... Go To 3.1, 3.2, 3,3
- c) Highly disturbed.....Go To 3.1, 3.2, 3,3

3. Perform Comprehensive evaluation of Present Ecological Services and Restoration

(3.1) Services	(3.2) 1= no effect, 10=highest effect	(3.3) Restoration strategy
Regulating		
Influence on air quality how if <.5ha size?		
Climate regulation How if <.5ha?		
Moderation of extreme events		

How if <.5ha?		
Regulation of water flows Is it part of complex, connected to water table?"		
Waste treatment?		
Erosion prevention		
Maintenance of soil fertility		
Pollination		
Biological control		
Habitat Service/Gene Pool	Identify diverse species	
Plant Species		
Animal Species		
Microbes		
Cultural	1= No effect 10=High	
Aesthetic		
Recreation/tourism		
Cognitive information		
Total Evaluation		

4. If Total evaluation is poor (scale less than) Wetland Relocation can be considered
5. If Total evaluation is moderate (scale between xxxx) wetland Restoration recommended
6. If Total evaluation is high Wetland need to be protected

4. General Recommendations

The purpose of wetland conservation is to both halt wetland loss as well as to restore and rehabilitate wetlands that have been lost.

4.1 *Preservation should be the norm*

“Natural ecosystems provide the foundation of a functioning human society” (Pattison-Williams et al., 2017, p. 400).

According to the mitigation hierarchy, preservation or avoidance of harm should always be the first priority. Wetlands are, in fact, afforded even greater protection under any offsetting policy and multiplier ratios due to the recognition of the vital ecosystem services they provide, and the realization that wetland areas have already declined dramatically. Consequently, in London, preservation of our wetlands, no matter their size, should be paramount. The possibility of relocating a wetland for a development project should not be used as an excuse to undertake that project, when avoidance of disturbance is equally an option. Economic concerns should not be given greater weight than environmental concerns where wetlands are concerned.

The more complex the hydrology or the ecological system, the more difficult it is to restore a wetland completely and in fact, in many cases it may be impossible. Very little is known about restoring inland freshwater wetlands, such as ponds, forested wetlands, bogs or fens (Kentula). With forested woodlands, woody vegetation takes so long to grow that often monitoring has ceased before these species have had time to establish. For London, where many of the affected wetlands are in, near or support woodlands, this time lag is significant and should be accounted for in development and post-disturbance monitoring plans.

International, national and provincial legislation and policies stress the importance of employing the precautionary principle in regards to environmental problems. This principle should be applied more rigorously in regards to wetlands where our knowledge of their functions and processes is limited. Instead, too much faith is put into the ability of restoration, relocation and recreation of wetlands to recover lost biodiversity (Maron et al., 2012). This misguided faith has led to an increase in biodiversity loss, as decision-makers, believing that restoration can deliver equivalent or better results, approve development projects that promise to damage ecosystems and functions. Time lags, uncertainty and problems with the measurability of the value being offset can seriously limit the technical success of offsets (Maron et al., 2012). As long as evidence is lacking to prove that restoration science and practice can achieve no-net loss of biodiversity, the precautionary principle should prevail. As Maron et al. advise, “the less certain we are that we possess the knowledge and technological ability to restore a biodiversity value, the less appropriate is offsetting as a response to potential loss of the value” (Maron et al., 2012, p. 145). It is the case that “project impacts cause immediate and certain losses, whereas the conservation gains of an offset are uncertain and may require many years to achieve” (McKenney and Kiesecker, 2010, p. 171).

Of particular importance to London where most of the wetlands that would be affected by development are quite small, studies have shown that larger wetlands recover faster than smaller ones, and that restored and/or created wetlands that are small may become more isolated, surrounded by fragmented landscapes. Small wetlands may only be able to support a limited number of individuals and they may not be connected enough to larger systems for local biota to restore the wetland to pre-impact functioning (Moreno-Mateos et al., 2012).

Restoration, relocation and recreation projects seldom meet targets. As Poulton and Bell noted, “[n]owhere is there a resounding success story, where offsetting has been demonstrated to achieve its full potential” (Poulton and Bell, 2017, p. i). In a study by Suding (2011), reviewing the successes and failures of restoration projects around the world, it was found that only a third to a half of projects were successful where restoration was used to fix a degraded system, and that when restoration was used to re-create a habitat, the success rate was even lower (Maron et al., 2012). Re-vegetated areas on highly degraded sites rarely resemble the target ecosystem (Maron et al., 2012). The actual recovery after ecological restoration is uncertain. In a meta-analysis of restored wetland systems around the world by Moreno-Mateos et al. (2012), it was found that even after a century, the biological structure (i.e. plant assemblages) and biogeochemical functioning (storage of carbon in wetland soils) was on average 26 percent and 23 percent lower respectively than reference sites. Recovery is clearly very slow, or in some cases the post-disturbance systems move toward an alternate state that is different from the reference conditions (Moreno-Mateos et al., 2012). Therefore, wetland offsetting should be used as an absolute last resort in the mitigation sequence, especially in the absence of proof that offsetting consistently leads to no net loss or a net gain in biodiversity. Preservation should always be the first option.

4.3 Relocation and Monitoring

Wetland relocation (a compensation plan) is considered when the wetland feature does not achieve a provincially or municipally significance designation or significant wildlife habitat is not confirmed, but the wetland feature provides productive amphibian breeding habitat and habitat for terrestrial crayfish. Under the ‘The London Plan’ (2016) all wetlands regardless of size, are to be protected under the Natural heritage system policies. In every case before we relocate or alter a wetland, we must consider the merits of destroying the functionality of an existing wetland and replacing it with a wetland that may in the future only operate at 75 percent functionality (in the best case scenario) or which may transform into a different type of wetland. In that case we need to ask, is the existing or replacement function more important, will the proposed wetland increase wetland diversity, and is the increased biodiversity worth any loss to habitat of endangered species that may result from a project (Kentula).

If the wetland functions can be replicated, a similar habitat is created elsewhere on the subject lands and target wildlife are gathered and trapped from the wetland habitat lost due to the development project and transported to the compensation wetland.

Wildlife Transfer Steps use by Stantec at 905 Sarnia Road

1. Construction of the compensation wetland. (timelines between construction and transfer??)
2. Grading of the new habitat features, and the addition of root wads to the new feature banks.
3. Native seeds are broadcast in the deep pool, shallow pool, riparian areas and dry upland areas surrounding the feature.
4. Dewatering and water transfer of the old pond.
5. Wildlife transfer begins with 7 days of baited minnow trapping.
6. On the drainage date, wildlife capture techniques included dip netting, seine netting and

hand picking. Captured wildlife are placed in tall buckets and transported to the compensation pond.

7. Selective transfer of riparian vegetation from the existing to the compensation pond.

Riparian top soil is not transfer because of the possible presence of invasive seed banks.

8. Aquatic and substrate are removed from the existing wetland and released in the compensation wetland along with the wildlife captures.

9. Downed woody debris are collected from around the existing wetland and placed strategically around and in the compensation area to provide basking opportunities for wildlife transfers.

10. On the final day, additional muck is transferred to the compensation pond.

11. Timing: Period length of transfer? Preparation of compensation pond?

'Target' Wildlife in a Wetland

The ecology and life history of 'target' wildlife such as terrestrial crayfish, western chorus frogs, northern leopard frog, eastern newt, brock stickleback, midland painter turtle, and snapping turtle must be considered before wildlife transfer.

For Example:

1. Terrestrial Crayfish

There are nine species of crayfish in Ontario and three of them are consistent (obligate) burrowers . Their names are: *Cambarus d. Diogenes* (Meadow or Devil crayfish), *Fallicambarus fodiens* (Chimney or Digger crayfish) and *Orconetes immunis* (Calico or Papershell crayfish).

Orconetes immunis (Calico Crayfish)

Calico crayfish are found in stagnant ponds and ditches and slow-moving streams. The bottom is mud with a heavy growth of rooted aquatic vascular plants. Because this species can burrow (1 metre deep) in the ground when necessary, it can utilize temporary pond habitat and spend the winter in the burrows. This species is largely herbivorous, feeding on the abundant vegetation of a pond, or, at night, on terrestrial plants close to shore. They are active both by day and night, but the adults are more strictly nocturnal. The species can travel across dry land at night, especially if there is rain or a heavy dew, and in this way can move from pond to pond. Copulation takes place from mid-July to early October, mostly yearling individuals participating. Eggs are laid in late October, and are carried on the underside of their abdomen through the winter. Hatchling .. Juveniles spend the summer growing, may become sexual active in September, but most wait until late the following summer. The normal lifespan is two years. (Crocker, 1968)

2. *Pseudacris triseriata* (Western Chorus Frog)

These small frogs weigh as much as a paperclip and are less than half as long as your thumb.

Adaptations prevent their cells from freezing. They require 25 days to travel 200 metres. Most individuals live no longer than 1 year, some for 2-3 years. They feed on small insects and other invertebrates. During breeding, western chorus frogs use shallow, fishless ponds and large puddles that dry up in the summer. Reproduction happens just after ice-out in early spring. Eggs hatch and tadpoles grow into adults in as little as two months depending on the water temperature. After breeding, the adults move overland to protected areas (woodlands) where they remain active the rest of the summer and spend the winter in undisturbed soft soil.

Meadows and forests located right next to breeding ponds provide great habitat where frogs can spend the summer and overwinter undisturbed. (Bird Studies Canada pamphlet)

Annual Post-Construction Monitoring

Before the monitoring process even begins, practitioners, developers, and the City must clearly define what a “successful” relocation or restoration would entail for each *individual* project, and outline a clear set of objectives. For instance, even if a site has revegetated, it could be functionally inadequate, and/or the plant composition may differ from the initial goals.

The three, five, ten year annual monitoring report includes qualitative and quantitative observations of water level, riparian and aquatic vegetation, overflow, breeding birds, amphibians, terrestrial crayfish chimneys and incidental wildlife associated with the constructed feature. However, given that significant time lags occur before a mitigation project can be determined a success, the time scale may require adjustment. Evidence has demonstrated that even 100 years after disturbance and restoration, the functions of a wetland may not have fully recovered. Indeed, to date restoration ecologists have been unable to re-create full functional replacement; it may not even be possible to fully re-create all the functions of a wetland. Careful and regular monitoring over a long period of time is vital to catch any problems that may arise (wetland shrinkage, incursion by invasive species) and to ensure greater probability of success of any wetlands project. In the absence of sufficient monitoring and adaptive management, designing wetlands to be self-sustaining and self-managing will better guarantee that they succeed.

Quantitative observations include an amphibian call survey (3 spring visits), crayfish burrow count using the quadrat method, baited minnow trapping, riparian and aquatic vegetation inventory, and the measuring of spring, summer and fall water levels.

Qualitative observations include turtles, any incidental wildlife, backyard encroachment and the health of neighbouring woodlots and other vegetation (invasive species) near and beyond the wetland.

If monitoring indicates that certain populations are in decline, additional individuals can be transferred into the compensation wetland (e.g. import tadpoles, broadcast more native seeds). Wetlands are particularly vulnerable to invasive species, due to their interconnection with waterways, their proximity to roads (paths along with invasive species may travel), and due to climate change which puts stress on wetlands due to changing weather patterns (increased rainfall

and/or drought). Re-created, restored or relocated wetlands will be particularly vulnerable to invasive species as they have suffered a disturbance and opportunistic plants can establish themselves quickly in areas where native species are stressed. If an invasive species (e.g. phragmites, purple loosestrife) is observed, the growing population can be carefully removed.

4.4 Wetland Offsetting

An option to prevent the net loss of wetlands in Ontario is the development of a wetland offsetting policy. Recently offsetting has become a popular approach to balance development projects with the need to protect biodiversity. However, it must be made clear that offsetting will not replace other legislation that provides protection for certain wetlands (i.e. provincially significant wetlands) where disturbance is prohibited. Wetland offsetting involves mitigating negative impacts upon one wetland by intentionally restoring or creating a new wetland at a different location. This type of policy is typically set within a mitigation hierarchy and involves the hierarchical progression of alternatives, including avoidance of impacts, minimization or mitigation of avoidable impacts and offsetting of impacts that cannot be avoided. The Ontario government remains committed to offsetting only being used as a last resort (OMNF, 2017). Wetland offsetting is meant to ensure no net loss of biodiversity, and, ideally, a net gain of biodiversity. However, there is always the risk that the offset never achieves an equivalent conservation value.

Several jurisdictions in Canada and around the world have developed wetland offsetting policies. Accepted methods of compensation include wetland restoration, creation, enhancement and preservation. The London Plan touches on offsetting or “compensatory mitigation” in 1402, stating that it may be provided through “[a]dditional rehabilitation and/or remediation beyond the area directly affected by the proposed works” and/or “[o]ff-site works to restore, replace or enhance the ecological functions affected by the proposed works” (The London Plan, 1402).

Biodiversity offsetting usually involves restoration as a way to offset specific losses in biodiversity or to trade for losses that may occur in the future. Biodiversity offsetting and wetland offsetting in particular, is meant to follow the mitigation hierarchy which calls for projects to avoid impacts, then minimize impacts that cannot be avoided, to then mitigate unavoidable impacts and finally to offset impacts that cannot be avoided. The Ontario government has said that it will use offsetting as a last resort in regards to wetlands. A common concern with biodiversity offsetting is that it exchanges “certain losses for uncertain gains” (Maron et al., 2012). And uncertainty regarding the outcome of an offset are significantly higher if the restoration is occurring at a significantly modified site.

There really is no one-size-fits all guidance for offset; local contexts can provide a variety of challenges. As McKenney and Kiesecker (2010) point out, no two areas are exactly ecologically identical and we cannot expect with relocation or re-creation to produce an exactly equivalent wetland. So then, how do we best create “equivalency” to address the losses of biodiversity and functionality? Questions that must be addressed prior to any relocation or offset project are: where

should the offset be located, when and for how long should it be operational, how should we manage risk of failure, and what will we do if an offset fails to reach its goals (McKenney and Kiesecker, 2010). Timing is a major issue with offsetting, whether restoring, relocating or re-creating. It could be many years, if ever, that a wetland project reaches maturity. Sometime policy statements require offsets to be in place before a project takes place, but with the pace of development in London, this provision may not be practicable.

Multiplier ratios. To address the problem that restoration or re-creation projects rarely, if ever, produce an equally biodiverse and functional wetland, multipliers are used to determine the scope of an offset project. Since wetlands are particularly valuable, the offset multiplier for wetlands is usually higher compared to other areas. Specifically, a restoration area should be several times larger than the impact site to compensate for the very high risk of failure or low performance. The London Plan specifies that “mitigation shall mean the replacement of the natural heritage feature removed or disturbed on a one-for-one land area basis (The London Plan, 1401), which seems insufficient given the uncertainties of success and the the goal of the provincial wetland strategy aiming for a net gain of wetland area. However, The London Plan goes on to say “[c]ompensatory mitigation shall mean additional measures required to address impacts on the functions of the Natural Heritage System affected by the proposed works. The extent of the compensation required shall be identified in the environmental impact study, and shall be relative to both the degree of the proposed disturbance, and the component(s) of the Natural Heritage System removed and/or disturbed” (The London Plan, 1401). And 1402 (3) does state that “[r]eplacement ratios greater than the one-for-one land area [are] required to mitigate the impacts of the proposed works” (The London Plan, 1402).

Duration. Ontario is still determining the duration of wetland offsets, whether they should be for the duration of the negative impacts or whether they should be in perpetuity. Given the ongoing losses of wetlands across southern Ontario, it can be assumed that wetland restoration projects or relocation should continue in perpetuity, especially since it has been demonstrated that evidence does not exist that these wetlands recover full functionality. Moreover, once a wetland has been moved for one project, that “relocated” or offset wetland, should not then itself become the subject of another development project and be relocated again.

A number of factors will have to be determined for offsets: the appropriate policy mechanisms for implementation, the roles and responsibilities for implementation, reviewing long-term results of wetland offsetting and restoration, and establishing monitoring requirements to make sure that the wetlands’ functions have been properly restored (A Wetland Conservation Strategy for Ontario). The three existing mechanisms for compensation are permittee-responsible mitigation and two forms of third party mitigation: mitigation banking and in-lieu mitigation. In permittee-responsible mitigation the development permit holder is responsible for delivering the offset. In the case of mitigation banking, the permit holder purchases offset credits from a wetland bank. In-lieu fee mitigation involves paying funds to an in-lieu fee sponsor (e.g. Ducks Unlimited) that later uses the funds for mitigation purposes (Poulton, 2017).

As Ontario develops its own unique wetland offset policy, lessons learned from other jurisdictions have helped to establish four key considerations (Poulton, 2017). Four of these lessons are:

1. Need for reliable tracking, reporting and record keeping: Baseline data on wetland functions lost to development must be recorded. Establish long-term monitoring requirement to ensure that wetland functions are restored.
2. Need for a watershed-based approach: Rather than a piecemeal approach, decisions are based on an assessment of the wetland needs in the watershed and the potential for the compensatory wetland to persist over time. The individual offset site should be designed to maximize the likelihood that they will make an ongoing ecological contribution to the watershed.
3. Need to adhere to the mitigation sequence: Avoidance and minimization of adverse impacts must be vigorously applied first. Skipping directly to the compensation step leads to opportunities lost to preserve natural heritage.
4. Need to ensure compliance: Compliance monitoring before and after project construction should endure inspection and enforcement by the municipality.

4.4.1 Restoration and Rehabilitation

There is two kinds of restoration: “re-establishment” which is returning the natural or historic function of a former wetland with the goal of increasing wetland area, and “rehabilitation” which is repairing the natural or historic functions of a wetland, such that there is an increase in functions but not in the area of wetlands (McKenney and Kiesecker, 2010). Wetland restoration rehabilitates a degraded wetland or it recreates a wetland that was destroyed. It takes place on land that is or was a wetland. In North America (Canada, US, Mexico) US\$70 billion spent attempting to restore 3 million hectares of wetlands from 1992-2012 (Moreno-Mateos et al., 2012). Restoration ecology is a relatively young discipline. Insufficient evidence is available to demonstrate that it is successful.

Several authors warn that “it cannot be assumed that restoration efforts will successfully return a degraded area to a state which is comparable or equivalent to the reference condition” (Matthews and Spyreas, 2010, 143). Hydrologic structure in restored and created wetlands is usually only followed 1-15 years following a project so the long-term changes are unknown (Moreno-Mateos et al., 2012). The abundance, species richness and diversity of native animals and plants in affected wetlands decreases dramatically following disturbance. Many macro-invertebrates cannot recolonize created or restored wetlands by themselves; they must be brought in by flowing waters or be brought in by other organisms (Moreno-Mateos et al., 2012). Moreover, climate variability and changing weather patterns will make predicting restoration outcomes difficult.

Restoration ecologists are increasingly recognizing that, given their complexity, restoring or (re)creating an ecosystem to some specified state, especially within a short time frame, is not particularly feasible (Hobbs et al., 2011 in Maron et al., 2012). Restoring just the functions of ecosystems can take several decades, and evidence has shown that even after a century, wetlands on average only operate at 75 percent functionality compared to reference sites (Moreno-Mateos et al., 2012). So, while plant biomass or species richness may return to pre-disturbance levels in a

shorter period of time, the actual composition of the plants may differ, and the soil composition, chemical properties and ecosystem functions (i.e. nutrient cycling) take significantly longer to be restored (Maron et al., 2012). For instance, Hossler et al. (2011 in Maron et al., 2012) discovered that even though restored and reference wetlands may have similar vegetation and hydrology, restored and created wetlands stored significantly less carbon in their soils and litter and also had much lower rates of denitrification.

Plant assemblages actually take the longest to be restored or created, particularly woody vegetation. It takes an average of thirty years for restored/created wetland sites to converge with the reference states of wetlands. However, the absolute average values of the structural features of plant assemblages was shown to be lower than reference levels even after a hundred years (Moreno-Mateos et al., 2012). Slow or incomplete recovery may be due to dispersal limitation, vulnerable early life history stages or sensitivity of any life stage to altered conditions (Moreno-Mateos et al., 2012). In addition, opportunistic invasive or non-native species may quickly colonize a disturbed area, outcompeting native species, thereby altering the plant assemblage in comparison to reference sites. Moreno-Mateos et al. (2012) also found that carbon and nitrogen storage and cycling drastically decreased in comparison to pre-impact levels.

Restoration can be even more difficult due to challenging situations occurring outside of the site, such as continued urbanization or new development projects that exercise negative influences on the restoration site (Maron et al., 2012). Stranko et al. (2012) looked at the effectiveness of stream restoration in urban areas and found that these restoration activities failed to improve any of eight biodiversity indices. The authors determined that the impacts of urbanization on stream ecology are irreversible and consequently it is unlikely that any biodiversity gains can come from stream restoration projects in urban areas (Maron et al., 2012). The same is likely true of wetlands, and particularly small wetlands, in urban settings.

Recommendations for using restoration to deliver biodiversity offsets or to compensate for wetland loss with development projects.

1. The impacted biodiversity and ecosystem values should be clearly defined and measured.
2. Time lags and uncertainties should be explicitly accounted for in any loss/gain calculation. Time lags should not pose an interim threat to biodiversity values.

Moreno-Mateos et al. (2012) found in their survey of restored wetland ecosystems that those restored wetlands that enjoyed the greatest success were larger wetland areas (greater than 100 hectares) in temperate or tropical climates. Smaller wetlands in colder climates fared least well, which is something important to consider regarding restoration projects in London which are going to involve smaller wetlands in a non-tropical setting. Current restoration practice does not recover original levels of wetland ecosystem functions, even after many decades (Moreno-Mateos, 2012).

4.4.2 Artificial Wetlands

Before constructing artificial wetlands, the impacted wetland should be looked at within a larger landscape context and a social context to determine what roles it plays within the larger ecosystem/social structure. For instance, is the current wetland a stop on a migratory route? Does it contribute to the watershed levels? It is necessary to look beyond municipal boundaries, which are artificial limits when applied to ecosystems.

Wetland creation -- construction of a wetland where one did not previously exist -- is much more complicated than restoration.

The elements that must be considered when planning to design and create a wetland are:

- Site-selection
- Hydrologic analysis
- Water source and quality
- Substrate augmentation and handling
- Planter material selection and handling
- Buffer zone placement
- Long-term management (Kentula)

Site selection usually is determined based on the availability of land or on policies that require the restored or created wetland to be in close proximity of a wetland loss (usually due to migration considerations). Location is extremely important in terms of influencing the structure and function of the wetland, and guaranteeing its longevity. Planners must consider both present and future land uses.

The hydrologic conditions are probably the most important factor for determining what type of wetland can be established and what kind of wetland processes can be maintained (Kentula). These include inflows and outflows of groundwater and surface water, the resulting water levels and the timing and duration of soil saturation and flooding (Kentula). Hydrology is greatly influenced by the configuration of the basin (i.e. the depression which will contain the wetland). The position of the basin surface relative to the water table affects the degree of soil saturation and flooding (Kentula). To ensure that water is present year-round, many wetlands are excavated such that the deepest part of the basin is below the lowest anticipated water level. The slope of the basin banks determine how much of the site will become vegetated, and by what kinds of plants (Kentula). In a properly constructed freshwater marsh wetland, the lowest point of the wetland will be inundated with water to a depth and for a period long enough that emergent vegetation can persist, but not for so long that it destroys the plants (Kentula).

The water quality of the wetland is highly important, yet often overlooked. If there are chemical inputs from the surrounding area, these can overwhelm a wetland. This is particularly important if the wetland is close to a road due to the de-icing salts. They can alter the productivity and composition of the plant community of the wetland, possibly favouring nuisance species, and they may harm animal species that cannot survive and breed in highly chemically altered waters.

The soils of a wetland are also really important, since though a created wetland may be structurally similar to a natural wetland, its hydrology may differ greatly if the permeability of the substrates are different (Kentula). Often the soils in created wetland contain less organic matter, which may affect plant growth. Using soils from a “donor” wetland or the impacted wetland to help create the new wetland may be able to increase the soil organic matter and provide the nutrients necessary for plant species, microbes and invertebrates (Kentula). Created wetlands will do better if the plants chosen closely resemble those of similar, local wetlands.

Microbes in the wetland play a crucial role in biogeochemical reactions which causes nutrient cycle and sustain other higher plants and animals. Comprehensive understanding of microbial composition and population will facilitate better understanding about a wetland condition (Bodelier and Dedysh 2013).

Garbisch (1986) suggested choosing herbaceous species that would rapidly stabilize the substrate and have potential value for fish and wildlife; to select species that can adapt to a wide range of water depths; to avoid choosing only species that are favoured by animals or you risk denuding the site (i.e. with geese), and to select “low maintenance” vegetation (Kentula).

Ducks Unlimited Publication - Wetlands on My Lands?

Steps to Creating a Wetland

1. Site Selection - Select the site during spring runoff to get an idea of where water flows and lies in your property. The catchment area (area that provides surface runoff into your wetland) should also be estimated at this time. A topographic survey can also provide more accurate data about surface flow. If the survey determines that there is less than a 0.6 m drop across the site, then excavating a basin is required.

2. Test the Soil - Impermeable soils are an important characteristic of wetlands. Soils that are fine-textured and not sandy and gravelly are suitable. It is also possible to bring in suitable soils (clay) to line the basin so the wetland will hold water.

3. Size and Shape - Wetlands come in all sizes. Make the wetland irregular in shape with many bends in the shoreline to mimic a natural wetland.

4. Wetland Depth - Excavate the wetland with an undulating bottom to encourage various types of vegetation. Emergent vegetation will grow in water depths of 1 m or less. It is advisable that approximately 25% of the area is 1 m or more in depth to ensure an ideal mixture of vegetation and open water. Excavating some deeper pockets will ensure some area will remain free of vegetation and allow the addition of native fish.

5. Wetland and Upland Enhancements - Establish a buffer around the wetland of undisturbed grasses, trees and shrubs. Install nest boxes to increase cavity nesting birds. Drag a few branches or logs into the wetland to provide basking areas for frogs, turtles and ducklings.

5. Conclusion

We need better scientific understanding of biotic and abiotic factors that hamper the success of restoration and relocation projects before we embrace these policies as a means to compensate for losses stemming from development and urban expansion.

6. Policy Recommendations

- a. When wetlands are involved in an infrastructure project, the priority should always be to avoid impacts to the maximum extent possible.
- b. Any wetland conservation strategy should integrate climate change adaptation and mitigation into its policies and outlook.
- c. Compensatory mitigation should not be used to make a potentially avoidable project seem more acceptable.
- d. Economic criteria should not be given priority over ecological criteria in development decisions.
- e. Restoration and recreation wetlands should be designed to both technically and legally last in perpetuity.
- f. A wetland which has been restored or relocated in compensation for another project should not subject to removal or further threats because of its “unnatural” status. It cannot be used as an excuse for future disturbance. See recommendation d.
- g. All restored and relocated and disturbed wetlands must be monitored for a period of no less than 10 years.
- h. Adaptive management must be incorporated into any and all wetland restoration and relocation projects, including removal of invasive species and other necessary actions to achieve desired outcome.
- i. The precautionary principle should influence all projects involving wetlands.
- j. Buffer zones are very important especially in urban areas. There should be undeveloped, vegetated land around wetlands and/or a fence or barrier. The composition and width of the buffer depends on the land use that is occurring adjacent to the created wetland, and also the requirements of the animals that will use the wetland and the buffer area.

k. The guidelines should apply to ephemeral water bodies (i.e. those present in spring and early summer). Such bodies are present in many areas of London and play a significant role in the maintenance of life systems in green areas.

7. References

EEPAC COMMENTS

Southdale Road West Class

Environmental Assessment

Subject Lands Status Report and Environmental Impact study

Reviewers: S. Levin, C. Therrien, R. Trudeau

9 May 2018

The main issues identified in this report were as follows:

1. Trees with cavities suitable for roosting bats may be removed from within the study area. Section 10 of the Endangered Species Act forbids the damage to or destruction of SAR habitat. Without acoustic surveys it is unknown which bats species might be present.
2. The Western Tributary is conveyed beneath Southdale Road West through a Corrugated Steel Pipe (CSP) culvert approximately 650 mm in diameter. After field visits, it was determined that it had become buried and serves as a dispersal barrier for fishes. Based on this, it can be concluded that keeping a culvert of the same size will “limit or diminish the ability of fish to use such habitats as spawning grounds and as a migration corridor” which is a direct violation of the Fisheries act section 4.
3. The OMNRF has released a May 2018 report titled “Considerations for the Development of a Wetland Offsetting Policy for Ontario. The document outlines a mitigation sequence that has four steps: Avoid, Minimize, Mitigate and Compensate. The sequence is intended to be applied in a stepwise fashion and since so much in this report is left for the detailed design process, it is important to emphasize that offsetting is considered only when all other steps have been accomplished.
4. A proposed ESA north of Southdale, a potential ESA south of Southdale and an eventual four lane footprint will lead to greater fragmentation and reduced wildlife movement.
5. A detailed tree survey and a tree compensation plan should be included within this EIS.
6. The loss of habitat for species protected by the Endangered Species Act
7. Invasive species management plan should start now

Theme #1: Bat habitat.

“While specific studies for bats were not conducted for the woodland areas, the two forest areas have potential to support bat maternity colonies as habitat for bat SAR.” (Southdale Road West Class EA, EIS, 2018)

Specific studies were conducted for the Boler Mountain Access Road EIS 2016. The study area stretched from Wickerson Road to the west boundary of the Boler Mountain property and south to include part of the northern boundary of the proposed extension of the Dingman Creek ESA. During the 2016 tree inventory, six (6) trees were observed with cavities suitable for roosting bats. Candidate maternity roost habitat is determined by a density of >10 cavities/hectare within a forest, as described in the Significant Wildlife Habitat Criteria Schedules for Ecoregion 7E (OMNRF,2015a). The survey did not meet the Ontario requirement in the Boler Access Road study area as the tree inventory was completed within the proposed access road footprint only and not the entire forest community. The EIS did recommend additional cavity surveys if future development is proposed. The Southdale Road Widening study area, located 200 m south is part of that same forest community.

Replacing snags with bat boxes has had mixed results. See [Acta Chiropterologica](https://doi.org/10.3161/15081109ACC2016.18.1.017), “**Bat Boxes — A Review of Their Use and Application, Past, Present and Future,**” 18(1):279-299. 2016
<https://doi.org/10.3161/15081109ACC2016.18.1.017>

Recommendation 1: Complete a June snag survey to determine potential bat cavities.

Recommendation 2: Complete a June bat acoustic survey as there may be a need to seek an overall benefit permit if there is loss of bat SAR habitat.

Theme #2. The Western Tributary and its culvert under Southdale Road

The description of the current Aquatic Resources (section 4.11) is outdated and incomplete. Since the site visit and its description in 2016, the new SWM pond has been completed and is providing inputs into the west branch of the western tributary. This increased input of water could increase the discharge of the tributary and result in water present in the tributary for more of the year. As such, the EIS should be updated.

The proposed Boler Mountain Access Road project crosses the Western Tributary. A 1050 mm CSP culvert has been proposed. South of that, the Western Tributary is conveyed

beneath the current Boler Mountain Access Road. The size of the pipe/culvert is not known. Culvert sizing is left to the detailed design.

Provincial policy statement: Policy 2.1 and 2.2 states alteration of fish habitat is prohibited unless it can be demonstrated that no negative impacts will occur (2.1.5). The current Southdale culvert size is too small and cannot handle flows. Current condition of the culvert is buried as a result of a build up of sediment and detritus around its northern opening (Fig. 1). This build up of debris has cut off much of the opening and future flooding events could result in the complete blockage of the culvert and cause flooding in the surrounding area. As such, keeping it in its current condition will result in negative impacts to fish habitat and culvert size must be address during the design phase.

Include in the detail design requirements, improvements to the watercourse north of Southdale where it crosses the current Boler Mountain Access Road. It is assumed that the area the access road encompasses will be restored to its original state, capable of supporting a forest community.

In section 7.1.3. Watercourse Crossing/Aquatic habitat, it is mentioned that “there may be opportunity to improve fish passage and riparian areas adjacent to the channels”. Keeping a culvert of the same size in the current design will not improve access to fish habitat but will continue to inhibit access to it. As such, a large box culvert is recommended. In addition, riparian areas can be improved if erosion control measures such as bank stabilization are included and a large box culvert is installed as increasing the cross-sectional area of the culvert is found to reduce surface flow and cause less erosion (Booth and Henshaw 2013).

In the report it is mentioned that there is moderate bank erosion downstream of the CSP and transitions to a poorly defined channel. Much of this erosion and channelization is most likely due to the stream passing through a CSP of 650mm in width. Several studies have shown that too small a culvert actually increase downstream erosion and the major cause of this erosion is most likely the result of this undersized culvert (Booth and Henshaw 2013).

Measures to control bank erosion are recommended in addition to increasing the size of the culvert, especially since the mitigation measure include to improve fish passage at watercourse crossings and the fact that the road will be expanded.

Recommendation #3: There is an opportunity to enhance (a net gain) the fish habitat upstream and downstream of the Southdale crossing by installing a large box culvert where the Western Tributary goes under the road.

Recommendation #4: Given the extent of cut and fill, consult landowners near the Western Tributary now with a mitigation plan to add a riparian zone south along private land. Also consult with UTRCA.

Reference: Booth, D. B. and P. C. Henshaw. 2013. Rates of channel erosion in small urban streams. Pages 17–38 in M.S. Wigmosta and S. J. Burges, editors. Land use and watersheds: human influence on hydrology and geomorphology in urban and forested areas. American Geophysical Association, USA.



Figure 1. Image of the partially buried culvert on the north side of Southdale Road. The image shows a large build-up of detritus causing the burying of the opening and restricting fish passage.

Theme #3: Wetland Management – Avoid, Minimize, Mitigate, Compensate (Offset)

Sections 4.4, 6.1 and 8.3.2 summarized:

The wetland features near and west of the Eastern Tributary are too small to be evaluated, isolated and vary in their ability to provide ecological function. The more westerly feature contains significant amphibian breeding habitat and is being treated as locally significant. The wetland feature nearest the Eastern Tributary would require minimal encroachment (0.03ha). Public lands adjacent to the wetland features are limited, so compensation for the loss of wetland habitat will take place elsewhere.

The OMNRF May 2018 document suggests that offsetting does not only refer to wetland area; it should also compensate for loss of ecological function (e.g. hydrologic functions, carbon storage and biodiversity), and traditional, cultural and Indigenous values. A baseline assessment of each impacted wetland is necessary to determine its function and their value within the sub-watershed or watershed.

Some wetland features are just depressions in the soil surface relying on surface flow for their water supply. However, these wetland features are situated relatively close to the Eastern Tributary and appear to serve as natural stormwater facilities. The tributary overflows its banks and the wetland features will: 1. help to control flooding and reduce flood damage, 2. maintain and improve water quality by filtering contaminants and excessive nutrients, 3. trap moderate amount of soils off nearby uplands before they enter Dingman Creek.

The road profile and design will incorporate LID measures in the form of stormwater storage in oversize pipes or perforated pipes to convey roadway runoff. Storage systems called “wetlands” already exist, ready to accept roadway runoff. In the near future, the south side of Southdale will be filled with Low Impact Development. Enhancing these wetland features will support these future LIDs as well.

Recommendation #5: The road improvement has a defined footprint and therefore avoidance and minimizing the project are not options. However, Southdale will eventually become a four lane road. To insure mitigation measures are long lasting, they should be drawn up based on the eventual four lane footprint.

Recommendation #6: A baseline assessment of each impacted wetland is necessary to determine its ecological function.

Recommendation #7: Consult landowners near the Eastern tributary now with a mitigation plan to add a riparian zone south along agricultural land. Consult with UTRCA.

Recommendation #8: If there is no possibility of avoidance or minimization to the wetlands, there must be a mitigation and/or compensation plan approved by the UTRCA prior to construction. Ideally it is included as a requirement in the bid documents for the construction.

Theme #4: Enhancing Wildlife Movement across Southdale Road

The Boler Mountain Lands Status Report (2012) describes the natural areas within the Boler Mountain study area as having a strong ecological connection to the Dingman Creek ESA located approximately 300 metres to the south of Southdale Road. The large area of native woodland present within the study area is connected to the Dingman Creek ESA through a corridor of similar woodland 100 to 200 metres wide south of Southdale Road. An extension of the existing Dingman Creek ESA boundary is proposed for the Boler Mountain study area. The area between the Dingman ESA and Boler Mountain is an unevaluated, potential ESA.

Leveling Southdale Road will improve sightlines and possibly reduce deer collisions. Upgrading the culverts and adding riparian zones along the Western and Eastern Tributaries will enhance fish migration. Tree planting along Southdale Road will close the forest canopy somewhat to aid bird movement. Terrestrial wildlife (e.g. red fox, coyote, turtles, amphibians chipmunks, squirrels) require a wildlife corridor for safe passage across Southdale Road.

Recommendation #9: The city should begin acquiring lands south of Southdale Road for long term management ecosystem planning (re: to create a continuous ESA from Boler Mountain to Pack Road.

Recommendation #10: Add grassed edges to the box culvert conveying the tributary waters or build a designated wildlife box culvert (tunnel) lined with vegetation for reptile and amphibian movement.

Theme #5: Tree Removal and Compensation

Tree removal must be outside the breeding season. No removal April 1st to Aug 31st as per Migratory Bird Convention.

300 trees documented, only 9 dead 78 over 50 DBH and 97.5% healthy. How do you replace that loss of tree mass and over what period? You cannot claim no net loss of features and functions as Dillon has done in the net impacts table. Page 44 also says compensation planting and “enhancement” to keep natural cover. Where? Not going to be able to replace feature and function of 78 50+DBH trees within the Road Allowance. Missing from the document is a map of where the trees will be lost.

It is inadequate that in the two years between 2016 when the field work was done and the publication of the EIS that NO work appears to have been done on any of the “Plans” for compensation, mitigation or edge effects. It is simply NOT adequate to leave this to “detail design” given the significant cut and fill and limited area for compensation.

In the Boler Mountain Lands Status Report, section #5 – Recommended Designations and Management, two restoration areas were identified for an active restoration program. The areas border both sides of the existing Boler Access Road.

Recommendation #11: The tree compensation plan should target these degraded woodland areas as well as the existing Boler Access Road which should be restored to its original state.

Recommendation #12: Start now with working with adjacent landowners for compensatory mitigation for tree loss as well as loss of wetland and grassland features.

Recommendation #13: Identify land for acquisition or City lands for tree planting as it is unlikely sufficient land is available to compensate for the loss of tree ecological functions.

Theme #6: Provincially Significant Bird Species observed in the general area

The Boler Mountain Lands Status Report (2012) reported the following:

One provincially significant bird species was noted on the site: Barn Swallow (with a status of threatened). This species was seen in the west portion of the site, in the strip of successional habitat along the small tributary parallel to Wickerson Road. The Barn Swallow was noted foraging over the fields on the western side of the site and was not noted breeding on the site. Barn Swallow nests were searched for in the barn/shed structure located in the western portion of the site; however, no nests were located within this structure.

An additional provincially significant bird species was noted on adjacent property: Eastern Meadowlark (threatened) was noted on the fence adjacent to the agricultural fields to the west (2011), and from agricultural fields to south of the study area (2012). Although Eastern Meadowlark was not noted on the subject property, this species likely incorporates areas of the site into its breeding territory as there is suitable habitat on the southwestern part of the property (grassy fields). This species is area-sensitive, and depends on large tracts of grassland habitat. It is generally found in broad agricultural landscapes and is extremely rare in urban settings. An adjacent landowner has also identified Bobolink in the grazing lands on the south side of Southdale, east of Wickerson. Ontario’s Endangered Species Act protects both species and their breeding habitat.

Pending and ongoing development in the general area includes: road work on Wickerson Road, a new subdivision under construction along Wickerson Road, a new stormwater pond built between Wickerson Road and Boler Mountain, an Access Road between Wickerson Road and Boler Mountain is nearing the construction phase and the Southdale Road widening project in the design stage.

Recommendation #14: Reducing habitat of the Eastern Meadowlark is contrary to the Endangered Species Act. Adjacent landowners must be consulted and cooperate in a compensation plan to create and enhance grassland habitat.

Theme #7 – An Aggressive Invasive Species Strategy.

8.2 “The Study Area was observed to contain high abundance of non-native and/or invasive species which may be attributed to existing negative impacts. An Invasive Species Management Plan is to be developed during the Detailed Design to target aggressive invasive flora which include White Sweet-clover, European Common Reed (Phragmites), Common Buckthorn and Periwinkle.”

Table 4, page 21 - Common Reed Graminoid Mineral Meadow Marsh (MAMM1-12, ELC Community #4). “ This small meadow marsh feature is situated around the outlet of a stormwater management pond located north of Southdale Road West ROW. The outlet forms the headwater for the East Tributary. This small meadow marsh community is dominated by European Common Reed which appears to be taking over a Cattail dominated meadow marsh.”

Table 4, page 21 – Cattail Graminoid Mineral Meadow Marsh (MAMM1-2, ELC Community #5). This community is adjacent to ELC Community #4 which was described in the above paragraph. “The small meadow marsh community is dominated by Cattails and transitions into European Common Reed dominated meadow marsh.”

Following road construction, invasive species are the first to invade. A post-construction plan for their removal is needed. The existing wetlands have already been invaded. Offsetting (compensation) measures have been suggested for wetland habitat loss due to construction. Mitigation, which is step three in the Wetland Strategy mitigation sequence, involves rehabilitation and restoration of features and functions. This should be a pre-construction strategy.

Recommendation #15: Start the eradication of European Common Reed before construction begins. Rehabilitate the wetland features in the Study Area that will not be impacted by the road construction.

Sunningdale Court EIS (600 Sunningdale Road West)

October 12, 2017

Reviewed by C. Dyck and S. Levin

MAJOR CONCERNS:

Size of buffers where the buffer is less than 10 m

Lack of information on protection of S2 plant (Two flowered Cynthia) – we believe this omission is sufficient grounds to reject the current version of the EIS

Date of field work predates the construction of the multi-use pathway and bridges

Lack of detail on restoration plans and insufficient monitoring period post restoration

BUFFERS

The rationale for a “relatively small buffer areas” given on page 7.7 is unclear, particularly in explaining why 5 m is sufficient. No explanation is given as to why the construction buffer is only 5 m. Page 7.7 indicates that final buffer requirements are to be determined as part of a site specific EIS. Were these words written at a different time? Isn't the document a final EIS? Regardless, there is no explanation of the buffer widths or a clear buffer management plan (very limited information appears in Table 7-2).

RECOMMENDATION 1: Either the EIS be revised to explain why the buffer widths are as narrow as 5 m. Otherwise, 10 m buffers should be the minimum requirement.

RECOMMENDATION 2: A buffer management plan with ecosite specific native planting recommendations be a condition of the development agreement.

Figures 6 and 7 note there is a 30 m buffer for fish habitat but the legend indicates “no buffer for the golf course pond.” EEPAC assumes this refers to the pond at the west end of the development in an area that, according to the zoning map that went out with the public notice, will be lands zoned OS5. Therefore, EEPAC is unclear how the pond is not buffered.

RECOMMENDATION 3: EEPAC requests that staff ensure that this pond is retained.

TWO FLOWERED CYNTHIA

In Appendix B, two CC of 10 plants are noted. There is some discussion in the text about one of the plants – Twinleaf. Its general location is noted in the report (7.6). This plant is listed as S4. However, there is absolutely no mention in the text of the other CC 10 plant – Two-Flowered Cynthia. This plant is listed as S2 which means Very Rare (page 3.5 uses the word ‘imperiled’ for S2) in Ontario; usually between 6 and 20 occurrences in the province, or found in only a few remaining hectares. For comparison, False Rue Anemone, which is listed as Threatened, also has an S2 ranking.

RECOMMENDATION 4: Until it is clarified if this plant is off the development site and protected from disturbance, the EIS be considered incomplete.

EDUCATION

It is unclear to the reviewers how access to the ESA from Block 115 will be limited. Although many will stay on the paved path, there are others who will stray. The EIS mentions in a number of places “education” but does not detail what steps will be taken to “educate.” It is also unclear how fencing will help homeowners avoid fertilizer and herbicide use, or avoid planting invasive species (p. 7.6, section 7.1.6)

EEPAC believes the following recommendation would address both of these.

RECOMMENDATION 5:

As a condition of development

- the proponent be required to install signage at Block 115 and 116 with information on the ESA including why it is significant and with normative messages consistent with behaviour science (‘nudges’), that encourage people to do the right thing and stay on designated paths, keep dogs on leash, etc. This is more likely to be considered “ongoing public education” (pgs 7.6 and 7.7). In return, EEPAC recommends the requirement for a home owner “package” be deleted from the development agreement.
- 6 months after assumption, the City send each resident the “Living With Natural Areas” brochure

NET EFFECTS ASSESSMENT (Section 7)

RECOMMENDATION 6: Page 7.13 - EEPAC strongly discourages installing bird boxes as a means of mitigating the impacts of this development and recommends that this be removed from the EIS.

As the EIS points out domestic pets are a threat to birds. It is unlikely that birds will “learn” to avoid domestic pets and installing bird boxes simply makes it easier for cats to find nesting birds. Numerous studies indicate that domestic animals increase stress in wildlife populations as they devote energy to avoidance and flight rather than on reproduction.

ENVIRONMENTAL MANAGEMENT PLAN (Section 8)

The report is very general in terms of the restoration and compensation plantings and plans. For example, page 7.4 says “...buffer management techniques will be used to reduce indirect impacts during construction and over the long term.” There is no clear explanation for this assertion.

In Table 7-3 under “ground disturbance and grading” the report recommends “regular inspection and repair of erosion and sediment control measures” and “regular inspection of the outlet and downstream for evidence of erosion.” It is unclear how often “regular” inspection will be and who or what agency will be responsible for monitoring and repair.

The EIS has two different proposed monitoring periods, neither of which, in EEPACs opinion and from examples from other developments, is sufficient.

RECOMMENDATION 7: An Environmental Management Plan be prepared for approval by the City and the UTRCA as a condition of development. The EMP must include a clear explanation for how the Plan will minimize indirect impacts on the Natural Heritage features and functions over the long term as well

as how often inspections will occur during construction. EEPAC recommends the following elements be included in the EMP:

- a. The areas north and to the south (including the area south of the pathway) of the proposed outlet spillway be restored. It is unclear why this area was not restored when the sewer or the path were built. However, it does provide an opportunity for compensation, given the rip-rap spillway will not provide much opportunity for riparian habitat replacement.
- b. Post construction monitoring be for three springs and three falls subsequent to the buffer and restoration plantings.
- c. An Invasive Species Management Plan be required as part of the development agreement, including for lands to be dedicated to the City as part of the City owned ESA (see Table 4-1)
- d. All restoration be with species that are native and appropriate for each ecosite.
- e. Clarification of the proposed "qualitative vegetation monitoring" be provided to EEPAC and if necessary, City staff. Does "quality" refer to the individual plants (i.e. poor health of planted species due to stressors like drought) or does it refer to the "quality" of the overall species composition (i.e. heavy presence of invasive species)? This recommendation should perhaps read "qualitative and quantitative" to determine the degree to which the newly planted vegetation has survived and is thriving. Indicators of overall plant health should be clearly outlined, such that when individual plants do not thrive the warranty period would be triggered, and the vegetation would be replaced.

CONSTRUCTION RECOMMENDATIONS

In section 8.3, it states "while the site is actively being developed/constructed with a log of dates when the facilities (i.e. erosion and sediment controls, construction fencing) were inspected, the condition of the facilities at the time and remedial actions, if any, that were taken." This also appears on page 9.2, recommendation #8. Are these activities that get reported to Development Services? It is unclear which City department receives these reports, or if there any random site visits to see if there is compliance specifically when the development is adjacent to a part of the Natural some other point in time?

As a result of this lack of clarity, EEPAC recommends:

RECOMMENDATION 8:

- a) The city conduct random visits to ensure sediment control measures are in place, particularly when the outlet channel is being constructed.
- b) Clean Equipment Protocol be followed.
- c) No equipment shall be stored or refuelled within 30 m of any natural feature or watercourse.
- d) Gates with no fences must (not should as shown on page 7.4) be erected between the development and the ESA.
- e) Removal of vegetation must (not should as stated on page 8.2) take place outside the nesting period of migratory birds.
- f) Invasive plants be removed.

STORMWATER

Page 7.3 indicates at the bottom that the proposed outflow is at “an appropriate spot for discharge to Medway Creek.” Nowhere does the report explain why the proposed location is better there than any other spot along the Creek.

RECOMMENDATION 9: A clear rationale for this location be provided before the EIS is accepted.

RECOMMENDATION 10: The development agreement be clear in who (the proponent or the City) is responsible for the ongoing maintenance of the OGS and outlet after assumption (see page 7.11, Table 7-3)

TO BE FORWARDED TO TRANSPORTATION DIVISION

EEPAC notes on page 4.10 that there is a perched culvert preventing fish passage. This should be rectified with the road widening. A box culvert is the preferred option.

QUALITY OF DATA COLLECTION - AMPHIBIAN SURVEYS

EEPAC questions if the frog call count surveys were done in a manner consistent with the Marsh Monitoring Protocol. Although the stations are located in areas off the developable lands, it is unusual to see the 3 required surveys done in two different years. It was also unclear as to when the three minute samples were taken, given the wide range of times shown in Table 3-2 on page 3.4. EEPAC notes that sundown on June 16, 2011 was roughly one hour prior to the time period shown in the Table. As well, two of the survey stations were closer than the 500 m recommended in the Protocol.

OTHER EDITS, ERRORS and OMISSIONS

The legend in Figure 7 notes ‘Fence’ but it is not clearly shown on the Figure. It would be helpful to know if the proposed fencing with no gates is actually along all properties particularly the ones abutting Blocks 115 and 116.

- References to UTRCA Watershed Report Card for the Medway should be updated to the most recent version, released this year.

- The first three paragraphs on page 4.2 appear to be unnecessary as:

- the proponent will not be addressing the lack of interior forest in the watershed.
- it is unclear when the benthic survey after 2001 was conducted
- there is little in this EIS that will implement the recommendations in the third paragraph which seem to relate to needs in other parts of the Medway Creek Subwatershed.

EEPAC believes Table 7.1 on pages 7.2/7.3 includes fewer direct impacts than is likely.

Page 9.2 ends abruptly. It is unclear whether a ‘period’ is simply missing to end the sentence, or whether a portion of the sentence/page is missing.

Notice of Completion

Master Plan

London Pollution Prevention and Control Plan

The City of London initiated a Pollution Prevention and Control Plan (PPCP) in 2012 as part of its ongoing efforts to improve the performance of the City's sanitary and storm sewer infrastructure. The goal of the PPCP is to reduce and mitigate sewer system overflows (SSOs) and wastewater treatment plant (WWTP) and pumping station (PS) bypasses that are discharged into receiving streams during extreme wet weather events.

The PPCP was conducted in accordance with the master planning process following the requirements of Phases 1 and 2 of the Municipal Class Environmental Assessment process (October 2000, as amended in 2007, 2011 and 2015), which is an approved process under the Ontario Environmental Assessment Act. The PPCP addresses the need and the justification for SSO mitigation and recommends infrastructure projects that will be implemented in accordance with the next steps of the Municipal Class Environmental Assessment process.

Preferred mitigation measures were selected to reduce the SSOs and PS bypasses and include sewer separation projects, source control measures such as targeted weeping tile disconnection, inflow/infiltration reduction, and pipe capacity upgrades. Existing planned or recently completed infrastructure improvement projects that are aligned with the PPCP were also incorporated into the PPCP implementation plan.

The PPCP report has been prepared to document the planning and decision-making process undertaken for this environmental assessment. By this notice, the PPCP report is being placed on the public record for 30 calendar days for review from Tuesday, May 15, 2018 to Thursday, June 14, 2018. Copies of the complete report will be available for review at:

- City Hall - Clerks Office (3rd floor), 300 Dufferin Avenue, London, ON
- Cherryhill Public Library, 301 Oxford Street, London, ON

The report will also be available online at: <https://www.london.ca/ppcp>

We are interested in receiving your comments on the study. If you have any comments, questions or concerns regarding the PPCP, please provide written comments to the following no later than June 14, 2018:

Marcy McKillop, P.Eng.
Wastewater and Drainage Engineering
City of London
300 Dufferin Avenue
London, ON N6A 4L9
Phone: 519-661-2489 (CITY) ext. 4976
Fax: 519.661.2355
Email: mmckillop@london.ca

Tom Mahood, P.Eng.
Project Manager
CH2M
72 Victoria Street South
Kitchener, ON N2G 4Y9
Phone: 519-579-3500 ext. 73241
Fax: 519-579-8986
E-mail: tom.mahood@ch2m.com



Please note that comments will be maintained for reference throughout the project and will become part of the public record. Under the *Municipal Freedom of Information and Protection of Privacy Act (MFIPPA)* and the *Environmental Assessment Act*, any personal information such as name, address and telephone number included in a submission will become part of the public record unless the commenter specifically requests that such personal details not be included in the public record.

One River Master Plan Environmental Assessment Study Notice of Stage 2 Public Information Centre

The City of London has retained Jacobs to undertake the One River Master Plan Environmental Assessment (EA) to identify the preferred strategy for the Thames River to improve the overall health of the River. This study has been divided into two stages, with the first stage considering the future of the Springbank Dam and the second stage assessing options for the Thames River in the City. With a free-flowing river selected as the preferred option for Springbank Dam in Stage 1, Stage 2 of the One River Master Plan EA is proceeding.

Stage 2 of the One River Master Plan EA will have three components for which options will be developed and assessed, and preferred solutions selected: the inaugural Back to the River project at the Forks of the Thames, the decommissioning of Springbank Dam, and the overall River Management Strategy. The Forks of the Thames and decommissioning of Springbank Dam components of the project will proceed as Schedule B EAs and will be integrated with the overall preferred River Management Strategy.

Two Public Information Centres (PICs) are being held to provide details on the Stage 2 EA process. The first PIC will provide information on alternatives for each component of the One River EA, and how these alternatives will be evaluated, as well as to receive input and comments from interested parties and the public. The details of the first Stage 2 PIC are below.

Date: Wednesday, June 6, 2018
Time: 4:00 to 8:00 pm
Location: Museum London, 421 Ridout Street,
London, ON N6A 5H4

City Staff and the project team from Jacobs will be available to discuss the information presented. Comments received at the PICs will be considered in the evaluation of options for each component of the project. A second PIC will then be held in September 2018 to present the results of the evaluation and the recommended solutions.

For further information or if you are unable to attend a PIC and wish to provide your comments, please contact a member of the project team:

Ashley M. Rammeloo, P.Eng
Manager, Engineering
Rapid Transit
City of London
300 Dufferin Ave P.O. Box 5035
London, ON N6A 4L9
Email: arammelo@london.ca

Tom Mahood, P.Eng
Project Manager
Jacobs

72 Victoria Street South, Suite 300
Kitchener, ON N2G 4Y9