Report to Planning and Environment Committee

To: Chair and Members

Planning and Environment Committee

From: Scott Mathers, MPA, P. Eng.,

Deputy City Manager, Planning and Economic Development

Subject: Designation of 6092 Pack Road under Section 29 of the

Ontario Heritage Act

Date: June 20, 2022

Recommendation

That, on the recommendation of the Director, Planning and Development, with the advice of the Heritage Planner, with respect to the designation of the property at 6092 Pack Road, that the following actions **BE TAKEN**:

- a) Notice **BE GIVEN** under the provisions of Section 29(3) of the *Ontario Heritage Act*, R.S.O. 1990, c. O. 18, of Municipal Council's intention to designate the property to be of cultural heritage value or interest for the reasons outlined in Appendix E of this report; and,
- b) Should no objections to Municipal Council's notice of intention to designate be receive, a by-law to designate the property at 6092 Pack Road to be of cultural heritage value or interest for the reasons outlined in Appendix D of this report BE INTRODUCED at a future meeting of Municipal Council within 90 days of the end of the objection period.

IT BEING NOTED that should an objection to Municipal Council's notice of intention to designate be received, a subsequent staff report will be prepared.

IT BEING FURTHER NOTED that should an appeal to the passage of the by-law be received, the City Clerk will refer the appeal to the Ontario Land Tribunal.

Executive Summary

The property at 6092 Pack Road is currently a LISTED property on the City's *Register of Cultural Heritage Resources*. A development is proposed on the property which includes a mix of housing forms with retention of an existing 20th-century farmhouse on the property (Z-9493); long term conservation of the farmhouse is being sought. As a component of a complete zoning application, per *The London Plan* policy 565, a heritage impact assessment was prepared by the applicant's representative and a cultural heritage evaluation was completed using the criteria of O. Reg 9/06. The evaluation determined that the property is a significant cultural heritage resource that merits designation pursuant to Section 29 of the *Ontario Heritage Act*.

Linkage to the Corporate Strategic Plan

This recommendation supports the following 2019-2023 Strategic Plan area of focus:

- Strengthening Our Community:
 - Continuing to conserve London's heritage properties and archaeological resources.

Analysis

1.0 Background Information

1.1 Property Location

The subject property at 6092 Pack Road is located on the north side of Pack Road, between Regiment Road and Bostwick Road (Appendix A). Historically, the property is part of the South Half of Lot 76, in the former Westminster Township.

1.2 Cultural Heritage Status

The property at 6092 Pack Road is a heritage listed property, included on the *Register of Cultural Heritage Resources*. The property is considered to be of potential cultural heritage value. The listing of the property on the *Register of Cultural Heritage Resources* came into force and effect on March 26, 2007.

1.3 Description

The property at 6092 Pack Road is approximately 1 hectare (2.5 acres), with a gated entrance along Pack Road and a windbreak of spruce trees along the western edge of the property (Appendix A; Appendix B). The house on the property faces Pack Road and is accessed through the set of gates and entrance drive on the east. In addition to the house on the property, there is a contemporary garage addition at the rear, northwest corner, along with a small added rear entrance.

Several outbuildings are located on the property. There is a pool and cabana located not far from the house to the north of the property. At the north end of the property there is a metal storage/shipping container, and an outbuilding measuring (7.5m x 10m) set on concrete footings and clad in timber siding. Located southeast of the outbuilding are the ruins of a barn. The area around the former barn contains various debris and is overgrown with vegetation.

The house at 6092 Pack Road was likely built between 1900-1910 and is a two-and-a-half-storey, buff brick vernacular farmhouse exhibiting Queen Anne design elements. The footprint measures approximately 10m x 15m (33ft x 49ft). The roof is a cross-hipped roof, clad in asphalt, with a medium pitched, and with a gabled dormer on the main (south) elevation.

The house has a simple compound plan and contains a projecting bay on the east elevation. The foundation of the residence is rusticated concrete block. The main (south) elevation has a front gabled dormer, framed with bargeboard, containing fish scale shingling, and a small one pane window with a wood surround with decorative pilasters on each side. A front porch, with a rusticated concrete block surround, wraps around and returns on the east elevation. The porch is supported by classically inspired wood columns. The underside of the porch roof is finished in tongue and groove wood slats.

The main entrance to the house is located off the porch, tucked around onto the projecting east bay, and consists of a modern door with an original stained-glass transom. Near the entrance, on the east elevation, is an oval shaped stained-glass window with a buff brick window surround. Most windows openings throughout are segmental arch windows openings, with buff brick voussoirs and concrete sills. Most windows frames and doors are contemporary replacements with the exception of the decorative oval-shaped window and stained-glass transoms (all with a similar motif) located at the following: (2) on the front porch, south facing windows on the 1st floor; (1) east facing window on the 1st floor, nearest to the porch; and the entrance door transom. The basement window openings are visible on the east and west elevation and are topped with buff brick voussoirs and contain cotemporary replacement windows.

Based on the architectural style of the residence and the use of rusticated concrete block as a foundation material, the residence was likely built between 1900 and 1910 (Stantec, 2022 p30).

1.4 Property History¹

The property at 6092 Pack Road is located on part Lot 76, East of Talbot Road which was granted by the Crown to Peter Swartz in 1835 (see Stantec, 2022; ONLand 2021a). Soon after Swartz obtained patent to the lot, he began to subdivide the property. In 1836, he sold 25 acres of the northwest part of the lot to Jesse Cornell, 50 acres of the northeast quarter to James Upgrove, and 50 acres of the southeast quarter – containing the current address at 6092 Pack Road – to William Adair (see Stantec, 2002; ONLand 2021a). In 1842, Adair and his wife sold the southeast quarter – containing the current address at 6092 Pack Road – to David Dale. In 1845, Upgrove sold the northeast

¹ This section is excerpted from Stantec, 2022 (p15-16).

quarter to David Dale, resulting in Dale owning the entire east half of Lot 76, East of Talbot Road (see Stantec 2022; ONLand 2021a).

David Dale was a son of Jacob Dale, an immigrant from Pennsylvania who moved to Upper Canada in 1811. The Dale family were prominent early settlers in Westminster Township and became extensive landowners. From the mid-1800s to the 1970s, the Dale family and decedents have owned property at 6092 Pack Road and the surrounding land parcels. Several Dale family members are also buried at Brick Street Cemetery on Commissioners Road (see Stantec 2002; Find-A-Grave 2021a, 2021b). Part of the township at the intersection of present-day Southdale Road and Wharncliffe Road is known as Dale's Corners (present-day Glendale) (see Stantec, 2022; WTHS 2006b:144).

2.0 Discussion and Considerations

2.1 Legislative and Policy Framework

Cultural heritage resources are recognized for the value and contributions that they make to our quality of life, sense of place, and tangible link to our shared past. Cultural heritage resources are to be conserved as per the fundamental policies in the *Provincial Policy Statement* (2020), the *Ontario Heritage Act*, *The London Plan*. It is important to recognize, protect, and celebrate our cultural heritage resources for future generations.

2.1.1 Provincial Policy Statement

Heritage conservation is a matter of provincial interest (Section 2.d, *Planning Act*). The *Provincial Policy Statement* (2020) promotes the wise use and management of cultural heritage resources and directs that "significant built heritage resources and significant cultural heritage landscapes shall be conserved" (Policy 2.6.1).

"Significant" is defined in the *Provincial Policy Statement* (2020) as, "resources that have been determined to have cultural heritage value or interest." Further, "processes and criteria for determine cultural heritage value or interest are established by the Province under the authority of the Ontario Heritage Act."

Additionally, "conserved" means, "the identification, protection, management and use of built heritage resources, cultural heritage landscapes and archaeological resources in a manner that ensures their cultural heritage value or interest is retained."

2.1.2 Ontario Heritage Act

Section 29 of the *Ontario Heritage Act* enables municipalities to designate properties to be of cultural heritage value or interest. Section 29 of the *Ontario Heritage Act* also establishes consultation, notification, and process requirements, as well as a process to object to a Notice of Intention to Designate (NOID) and to appeal the passing of a bylaw to designate a property pursuant to Section 29 of the *Ontario Heritage Act*. Objections to a Notice of Intention to Designate are referred back to Municipal Council. Appeals to the passing of a by-law to designate a property pursuant to the *Ontario Heritage Act* are referred to the Ontario Land Tribunal (OLT).

To determine eligibility for designation under Section 29 of the *Ontario Heritage Act*, properties are evaluated using the mandated criteria of Ontario Regulation 9/06.

2.1.2.1 Ontario Regulation 9/06

The criteria of *Ontario Heritage Act* Regulation 9/06 establish criteria for determining the cultural heritage value or interest of individual properties. These criteria are reinforced by Policy 573_ of *The London Plan*. These criteria are:

- 1. Physical or design value:
 - i. Is a rare, unique, representative or early example of a style, type, expression, material or construction method;
 - ii. Displays a high degree of craftsmanship or artistic merit; or,
 - iii. Demonstrates a high degree of technical or scientific achievement.
- 2. Historical or associative value:
 - i. Has direct associations with a theme, event, belief, person, activity, organization or institution that is significant to a community;

- ii. Yields, or has the potential to yield, information that contributes to an understanding of a community or culture; or,
- iii. Demonstrates or reflects the work or ideas of an architect, artist, builder, designer or theorist who is significant to a community.
- 3. Contextual value:
 - i. Is important in defining, maintaining or supporting the character of an area;
 - ii. Is physically, functionally, visually or historically linked to its surroundings; or,
 - iii. Is a landmark.

A property is required to meet one or more of the abovementioned criteria to merit protection under Section 29 of the *Ontario Heritage Act*.

2.1.2.2 Ontario Regulation 385/21

Ontario Regulation 385/21 was proclaimed on July 1, 2021. This regulation prescribes certain requirements for a heritage designating by-law. The following information is a prescribed requirement of a heritage designating by-law, per Section 3(1), O. Reg. 385/21:

- 1. The by-law must identify the property by,
 - i. The municipal address of the property, if it exists;
 - ii. The legal description of the property, including the property identifier number that relates to the property; and,
 - iii. A general description of where the property is located within the municipality, for example, the name of the neighbourhood in which the property is located and the nearest major intersection to the property.
- 2. The by-law must contain one or more of the following that identifies each area of the property that has cultural heritage value or interest:
 - i. A site plan.
 - ii. A scale drawing.
 - iii. A description in writing.
- 3. The statement explaining the cultural heritage value or interest of the property must identify which of the criteria set out in subsection 1(2) of Ontario Regulation 9/06 (Criteria for Determining Cultural Heritage Value or Interest) made under the Act are met and must explain how each criterion is met.
- 4. The description of the heritage attributes of the property must explain how each heritage attribute contributes to the cultural heritage value or interest of the property.

2.2 The London Plan

The Cultural Heritage chapter of *The London Plan* recognizes that our cultural heritage resources define our City's unique identity and contribute to its continuing prosperity. It notes, "The quality and diversity of these resources are important in distinguishing London from other cities and make London a place that is more attractive for people to visit, live or invest in." Policies 572_ and 573_ of *The London Plan* enable the designation of individual properties under Section 29 of the *Ontario Heritage Act*, as well as the criteria by which individual properties will be evaluated.

3.0 Financial Impact/Considerations

None

4.0 Key Issues and Considerations

4.1 Current Proposal and Cultural Heritage Evaluation

A development is proposed on the property at 6092 Pack Road which includes a mix of housing forms with retention of an existing 20th-century farmhouse on the property; long term conservation of the farmhouse is being sought (Appendix C). Notices of Application were circulated April 20, 2022, and May 6, 2022. As a component of a complete zoning application (Z-9493), per *The London Plan* policy 565, a heritage impact assessment was prepared by the applicant's representative and a cultural heritage evaluation was completed using the criteria of O. Reg 9/06 (Appendix E).

These criteria are:

- i. Physical or design value;
- ii. Historical or associative value; and,
- iii. Contextual value (see Section 2.1.2.1)

A property is required to meet one or more of the abovementioned criteria to merit protection under Section 29 of the *Ontario Heritage Act*. A summary of the evaluation of the property at 6092 Pack Road is highlighted in the table below:

Criteria of O. Reg. 9/06		
cal/ gn	Is a rare, unique, representative or early example of a style, type, expression, material or construction method	<u>YES</u>
Physical/ Design	Displays a high degree of craftsmanship or artistic merit	no
출입	Demonstrates a high degree of technical or scientific achievement	no
al/ tive	Has direct associations with a theme, event, belief, person, activity, organization or institution that is significant to a community	<u>YES</u>
Historical/ Associative	Yields, or has the potential to yield, information that contributes to an understanding of a community or culture	<u>YES</u>
His	Demonstrates or reflects the work or ideas of an architect, artist, builder, designer or theorist who is significant to a community	no
nal	Is important in defining, maintaining or supporting the character of an area	no
Contextual	Is physically, functionally, visually or historically linked to its surroundings	no
	Is a landmark	no

Table 1: Summary of the evaluation of the property at 6092 Pack Road using the criteria of Ontario Regulation 9/06

The Heritage Planner concurs with the evaluation of the property at 6092 Pack Road by Stantec Consulting Ltd. as being a significant cultural heritage resource (Appendix E). As the property at 6092 Pack Road has met the criteria for designation, a Statement of Cultural Heritage Value or Interest and heritage attributes have been identified (Appendix D).

4.1.1 Physical or Design Values

The house at 6092 Pack Road has design value as a representative example of an early 20th- century Ontario vernacular farmhouse with the use with Queen Anne design elements that were popular in the late 19th and early 20th-centuries. Vernacular elements include the use of buff brick and rusticated concrete block for the foundation and porch surround. Design elements specific to the Queen Anne style found on the farmhouse include: a 2 ½ -story structure with compound plan, hip roof, front facing gable, wrap around porch, and use of details such as voussoirs, bargeboard, fish scale shingling, stained-glass, and unique shaped window openings (i.e. oval shaped window near main entrance).

As a vernacular structure, the building materials, construction methods, and quality of craftsmanship were typical of the time. By its very nature, the house does not demonstrate a high degree of craftsmanship or a high degree of technical or scientific achievement. As well, the house is not known to demonstrate or reflect the work or ideas of an architect, artist, builder, designer, or theorist who is significant to a community.

4.1.2 Historical or Associate Values

The property at 6092 Pack Road is directly associated with the Dale family and was occupied by members of the Dale family from 1842 until at least the early 1970s. The Dale family in the former Westminster Township traces its origins to Jacob Dale, an early settler to Westminster Township originally from Pennsylvania. Dale and descedents became extensive landholders in Westminster Township, particularly around the intersection of present-day Southdale Road and Wharncliffe Road. The Dale

family, through their extensive landholdings have made a notable contribution to the pattern of settlement of the former Westminster Township. This area is still referred to as Glendale in recognition of the family.

The property at 6092 Pack Road is not known to demonstrate or reflect the work or ideas of an architect, artist, builder, designer, or theorist who is significant to a community.

4.1.3 Contextual Values

The property at 6092 Pack Road is set in a landscape that remains largely rural and agricultural but is in the process of transitioning to a suburban landscape. The property consists of a house and outbuildings set on a large lot that has been severed from agricultural fields; little tangible signs remain of the former agricultural use of the property. The property at 6092 Pack Road is one of many rural properties located on the southern outskirts of London. It is not believed to be a landmark in the community.

4.2 Comparative Analysis

The house at 6092 Pack Road is an Ontario vernacular farmhouse which exhibits Queen Anne design elements. A comparative analysis of other properties LISTED on the City's *Register of Cultural Heritage Resources*, based on form and style, found many properties identified as "vernacular" (n=470; 7½ %) or having "Queen Anne" (n=538; 9%) styling. Although not conclusive, the house shouldn't be considered rare or unique as many examples of Ontario vernacular farmhouses and Queen Anne houses remain in the City of London and were a common design style throughout Ontario in the late 19th to early 20th centuries.

4.3. Integrity

Integrity is not a measure of originality, but a measure of whether the surviving physical features (heritage attributes) continue to represent or support the cultural heritage value or interest of the property. Likewise, the physical condition of a cultural heritage resource is not a measure of its cultural heritage value. Cultural heritage resources can be found in a deteriorated state but may still maintain all or part of their cultural heritage value or interest (Ministry of Culture, 2006).

The house at 6092 Pack Road demonstrates a high degree of integrity. Many of the original physical features representative of the Queen Anne style have been retained. This can be found in the retention of the wrap-around porch, exterior woodworking details on the front facing gable, and countless stained-glass transoms exhibiting a similar motif. Aside from the replacement of windows and the addition of an attached garage, the house remains relatively unmodified.

4.4 Consultation

In compliance with Section 29(2) of the *Ontario Heritage Act*, consultation with the Community Advisory Committee on Planning (CACP) is required before Municipal Council may issue its notice of intent to designate the property at 6092 Pack Road pursuant to the *Ontario Heritage Act*. The CACP was consulted at its meeting on June 15, 2022.

Conclusion

The evaluation of the property at 6092 Pack Road found that the property met the criteria for designation under Section 29 the *Ontario Heritage Act*. The house at 6092 Pack Road is a significant cultural heritage resource that is valued for its physical or design values and its historical or associative values. The property at 6092 Pack Road should be designated pursuant to Section 29 of the *Ontario Heritage Act* to protect and conserve its cultural heritage value for future generations.

Prepared by: Laura E. Dent, M.Arch, PhD, MCIP, RPP

Heritage Planner

Reviewed by: Jana Kelemen, M.Sc.Arch., MUDS, MCIP RPP

Manager, Urban Design, and Heritage

Recommended by: Gregg Barrett, AICP

Director, Planning and Development

Submitted by: Scott Mathers, MPA, P. Eng.

Deputy City Manager, Planning and Economic

Development

Appendices

Appendix A Property Location

Appendix B Images

Appendix C Proposal Rendering

Appendix D Statement of Cultural Heritage Value or Interest – 6092 Pack Road

Appendix E Heritage Impact Assessment 6092 Pack Road, London, ON

(Stantec, February 17, 2022)

Sources

2022, May 6 – Notice of Planning Application, Zoning By-Law Amendment – 6092 Pack Road (Z-9493). London, ON: Corporation of the City of London.

2022, April 20 – Notice of Planning Application, Zoning By-Law Amendment – 6092 Pack Road (Z-9493). London, ON: Corporation of the City of London.

2021, October 7 – E-mail Correspondence to Barb Debbert, Senior Planner, from Laura E. Dent, Heritage Planner. re: Pre-Application Consultation (ZBA) – 6092 Pack Road – Heritage Commenting.

Corporation of the City of London. n.d. Property files: 6092 Pack Road.

Corporation of the City of London. (2016, consolidated 2021, May 28). The London plan. London, ON: Author.

Corporation of the City of London. (2020, Dec 8). City of London Register of Cultural Heritage Resources. London, ON: Author.

Government of Canada. Parks Canada. Standards and Guidelines for the Conservation of Historic Places in Canada. 2010.

Ministry of Municipal Affairs and Housing. (2020). Provincial policy statement, 2020. Ontario: Queen's Printer for Ontario.

Ontario Heritage Act, (last amendment 2021, c. 4, Sched. 6, s.74). Retrieved from e-Laws website https://www.ontario.ca/laws/statute/90018

Ontario Land Registry. 6092 Pack Road, City of London. Accessed June 4, 2022. www.onland.ca.

Ontario Ministry of Culture. (2006). Heritage resources in the land use planning process information sheet series. "InfoSheet #5, Heritage impact assessments and conservation plans." Ontario: Queen's Printer for Ontario.

Ministry of Culture. (2006). *Ontario Heritage Toolkit: Heritage Property Evaluation*. Ontario: Queen's Printer for Ontario.

Phillips, S. J. (1989). Old-house dictionary: An illustrated guide to American domestic architecture 1600 to 1940. Lakewood, Colorado: American Source Books.

[siv-ik] Planning/Design. (2021, Sept 21). Vision Brief – Background Info and Summary of Development Vision. London, ON: Author.

Stantec Consulting Ltd. (2022, Feb 17). Heritage Impact Assessment 6092 Pack Road, London, Ontario – (final report). London, ON: Author. [Where applicable, see additional sources referenced in report].

Appendix A - Property Location





Figure 1: Property Location for 6092 Pack Rd

Corporate City Map



The Corporation of the City of London | Produced For: Environmental & Engineering Services – Transportation Planning & Design | Produced by: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Produced For: Environmental & Engineering Services - Geomatics | Corporation of the City of London | Corporation of the City of London | Corporation of the City of London | Corporation of the City of Lo

Figure 2: Aerial view of property showing outbuildings

Appendix B – Images



Image 1: Street view of property at 6092 Pack Road, as seen from Pack Road looking northeast



Image 2: South-east elevations of house on property showing wrap-around veranda and hip roof



Image 3: Front, south elevation of house with hip roof and front facing gable with decorative bargeboard



Image 4: West, side elevation of house on property



Image 5: North-west elevations of house on property showing contemporary garage addition



Image 6: Rear, north elevation of house on property showing contemporary garage additions and added rear entrance



Image 7: North-east elevations of house on property showing rear entrance addition



Image 8: East, side elevation of house on property showing wrap-around veranda



Image 9: Stained glass transom located above first storey window on east elevation



Image 10: Oval shaped stained-glass window on east elevation




Image 11: Stained glass transom located above entrance door off veranda



Image 12: Stained glass transom located above first storey window on south elevation



Image 13: Stained glass transom located above first storey window on south elevation



Image 14: Porch details showing wood columns with concrete block surround



Image 15: Row of spruce trees along western edge of property



Image 16: Outbuildings at rear of property – metal shed, barn, and storage container



Image 17: Outbuilding at rear of property – storage container



Image 18: View of rear of property pool and cabana

Appendix C – Proposal Rendering



Appendix D – Statement of Cultural Heritage Value or Interest – 6092 Pack Road

Legal Description

PART LOT 76 ETR WESTMINSTER, PART 1 33R19090

PIN

08209-0008

Description of Property

The property at 6092 Pack Road is located in the City of London on the north side of Pack Road, approximately 280 metres west of the intersection of Bostwick Road and Pack Road. Historically, the property is part of the South Half of Lot 76, in the former Westminster Township. The property contains a house, spruce windbreak, pool with cabana, outbuilding, storage container and barn ruins. The house at 6092 Pack Road was likely built between 1900-1910 and is a two-and-a-half-storey, buff brick vernacular farmhouse exhibiting Queen Anne design elements.

Statement of Cultural Heritage Value or Interest

The property at 6092 Pack Road is of significant cultural heritage value or interest because of its physical or design values and its historical or associative values.

The house at 6092 Pack Road has design value as a representative example of an early 20th century Ontario vernacular farmhouse with the use with Queen Anne design elements that were popular in the late 19th and early 20th-centuries. Vernacular elements include the use of buff brick and rusticated concrete block for the foundation and porch surround. Design elements specific to the Queen Anne style found on the farmhouse include: a 2 ½ -story structure with compound plan, hip roof, front facing gable, wrap around porch, and use of details such as voussoirs, bargeboard, fish scale shingling, stained-glass, and unique shaped window openings (i.e. oval shaped window near main entrance).

The property at 6092 Pack Road is directly associated with the Dale family and was occupied by members of the Dale family from 1842 until at least the early 1970s. The Dale family in the former Westminster Township traces its origins to Jacob Dale, an early settler to Westminster Township originally from Pennsylvania. Dale and decedents became extensive landholders in Westminster Township, particularly around the intersection of present-day Southdale Road and Wharncliffe Road. The Dale family, through their extensive landholdings have made a notable contribution to the pattern of settlement of the former Westminster Township. This area is still referred to as Glendale in recognition of the family.

Heritage Attributes

Heritage attributes which support and contribute to the cultural heritage value or interest of this property include:

- Representative example of an early 20th century Ontario vernacular farmhouse with Queen Anne design elements, including:
 - Two- and one-half storey structure with compound plan
 - Hip roof with brick chimney and gable dormer containing bargeboard and fish scales
 - o Buff brick exterior
 - Segmental arch window openings with buff brick voussoirs and concrete sills
 - Stained glass transoms located above main entrance and first storey windows on the south and east elevations
 - Wrap around rusticated concrete block porch with classically inspired wood columns
 - Oval shaped stained-glass window on east elevation
 - Rusticated concrete block foundation

The contemporary garage and entrance addition at the rear, north elevation are not considered to be heritage attributes.

The outbuildings at the north, rear of portion of the property (including a metal shed, barn, and storage container) are not considered to be heritage attributes.

Appendix E – Heritage Impact Assessment – 6092 Pack Road, London, ON (Stantec, February 17, 2022)

Attached separately.



FINAL REPORT

February 17, 2022

Prepared for:

2847011 Ontario Inc. 509 Commissioners Road West Suite 425 London, Ontario N6J 1Y5

Prepared by:

Stantec Consulting Ltd. 600-171 Queens Avenue London, Ontario N6A 5J7

Project Number: 160940814

Executive Summary

2847011 Ontario Inc. retained Stantec Consulting Ltd. (Stantec) to prepare a Heritage Impact Assessment (HIA) for the property located at 6092 Pack Road in the City of London, Ontario. In accordance with Section 27(1) of the *Ontario Heritage Act* (OHA), the City of London (the City) maintains a register of properties that are of cultural heritage value or interest (CHVI). The property at 6092 Pack Road is a listed resource and is described as a Vernacular structure built in 1900. The property was added to the register on March 26, 2007. 2847011 Ontario Inc. is proposing to redevelop the property to include 40 new units consisting of cluster townhouse units, back-to back townhouses, and the retention of the existing residence.

The residence at 6092 Pack Road was determined to demonstrate design/physical value and historic/associative value. The residence at 6092 Pack Road has design value as a representative example of an early 20th century Ontario vernacular structure with Queen Anne design elements. The property at 6092 Pack Road is directly associated with the Dale family and was occupied by members of the Dale family from 1842 until at least the early 1970s. The Dale family were prominent early settlers in the Township of Westminster.

The proposed undertaking will conserve the built heritage resource at 6092 Pack Road. The proposed undertaking would not result in direct impacts to the property at 6092 Pack Road. The existing residence will be retained *in situ* and no heritage attributes will be alterted as part of the proposed undertaking. While the existing shed roof addition and hip roof addition of the residence will be removed, both do not contain heritage attributes. No indirect impacts are anticipated from shadows, isolation, or obstruction. There may be potential for indirect impacts related to land disturbance during the construction phase that could result in vibrations that are damaging to the structure. While a change in land use is anticipated to allow for higher residential density than is currently permitted, the property will remain residential in nature and the proposed changes are not anticipated to impact the heritage attributes or heritage value of the property.

An assessment of impacts resulting from the proposed undertaking at 6092 Pack Road has determined the undertaking may possibly result in indirect impacts from land disturbance. On site construction activity could result in vibrations that have potential to affect historic foundations. Based on the impacts identified to the cultural heritage resource and the proposed undertaking, the following mitigation measure is recommended:



i

- Retain a qualified person(s) to complete a pre-construction vibration assessment to determine acceptable levels of vibration given the site-specific conditions (including soil conditions, equipment proposed to be used, and building characteristics)
- Should the residence be determined to be within the zone of influence, additional steps should be taken to secure the building from experiencing negative vibration effects (i.e., adjustment of machinery or establishment of buffer zones

The Executive Summary highlights key points from the report only; for complete information and findings, the reader should examine the complete report.



ii

Table of Contents

1.0	Introduc	ction	1
2.0	Methodo	ology	4
2.1	,	ramework	
	2.1.1		
	2.1.2		
	2.1.3	City of London Official Plan	
2.2		ound History	
2.3		ogram	
2.4		on of Cultural Heritage Value or Interest	
	2.4.1	Ontario Regulation 9/06	
2.5		nent of Impacts	
2.6	Mitigatio	on Options	8
3.0	Historic	cal Overview	g
3.1	Introduct	tion	<u>9</u>
3.2	Physiogr	raphy	9
3.3	Townshi	ip of Westminster	9
	3.3.1	Survey and Settlement	9
	3.3.2	, I	
	3.3.3	· · · / · · ·	
3.4	Property	y History	15
4.0	Site Des	scription	21
4.1	Introduct	tion	21
4.2	Landsca	ape Setting	21
4.3	Residen	nce	24
4.4	Outbuild	dingsdings	28
5.0	Compar	rative Analysis	30
6.0	-	ion of Cultural Heritage Value or Interest	
6.0 6.1		tion	
6.2		or Physical Value	
6.2 6.3		or Associative Value	
6.4		ual Value	
6.5		ry of Evaluation	
6.6			
0.0	6.6.1	ent of Cultural Heritage Value Description of Property	
	6.6.2	Cultural Heritage Value	
	6.6.3	Heritage Attributes	
		G	
7 0	Impact A	Assessment	37



7.1	Description of Proposed Undertaking	37
7.2	Assessment of Impacts	
7.3	Discussion of Impacts	
8.0	Mitigation	40
8.1	InfoSheet #5 Mitigation Options	
8.2	Mitigation Discussion	
9.0	Recommendations	42
9.1	Deposit Copies	42
10.0	Closure	43
11 0	References	44

List of Appendices

Appendix A: Concept Plan Appendix B: Renderings



Project Personnel

Project Manager: Meaghan Rivard, MA, CAHP

Heritage Consultant: Meaghan Rivard, MA, CAHP

Report Writer: Frank Smith, MA

GIS Specialist: Baljeet Kaur

Administrative Assistant: Carol Naylor

Quality Reviewer: David Waverman BLA, OALA, CSLA, CAHP

Independent Reviewer: Tracie Carmichael, BA, B.Ed. (R140)



Abbreviations

BLA Bachelor of Landscape Architecture

CAHP Canadian Association of Heritage Professionals

CHVI Cultural Heritage Value or Interest

CSLA Canadian Society of Landscape Architects

HIA Heritage Impact Assessment

MA Master of Arts

MHSTCI Ministry of Heritage, Sport, Tourism and Culture

Industries

OALA Ontario Association of Landscape Architects

OHA Ontario Heritage Act

O. Reg. Ontario Regulation

PPS Provincial Policy Statement

RPA Registered Professional Archaeologist



Introduction February 17, 2022

1.0 Introduction

2847011 Ontario Inc. retained Stantec Consulting Ltd. (Stantec) to prepare a Heritage Impact Assessment (HIA) for the property located at 6092 Pack Road in the City of London, Ontario (Figure 1 and Figure 2). In accordance with Section 27(1) of the *Ontario Heritage Act* (OHA), the City of London (the City) maintains a register of properties that are of cultural heritage value or interest (CHVI). The property at 6092 Pack Road is a listed resource and is described as a Vernacular structure built in 1900. The property was added to the register on March 26, 2007. 2847011 Ontario Inc. is proposing to redevelop the property to include 40 new units consisting of cluster townhouse units, back-to back townhouses, and the retention of the existing residence.


The purpose of the HIA is to respond to policy requirements regarding the conservation of cultural heritage resources in the land use planning process. Where a change is proposed within or adjacent to a protected heritage property, consideration must be given to the conservation of cultural heritage resources. The objectives of the report are as follows:

- Identify and evaluate the CHVI of the Study Area
- Identify potential direct and indirect impacts to cultural heritage resources
- Identify mitigation measures where impacts to cultural heritage resources are anticipated to address the conservation of heritage resources, where applicable

To meet these objectives, this HIA contains the following content:

- Summary of project methodology
- Review of background history of the Study Area and historical context
- Evaluation of CHVI
- Description of the proposed site alteration
- Assessment of impacts of the proposed site alterations on cultural heritage resources
- Review of development alternatives or mitigation measures where impacts are anticipated
- Recommendations for the preferred mitigation measures











Study Area



- Notes
 1. Coordinate System: NAD 1983 UTM Zone 17N
 2. Base features produced under license with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2022.
 3. Orthoimagery © First Base Solutions, 2021. Imagery Date, 2020.



Project Location City of London

160940814 REVA Prepared by SW on 2022-01-21 Technical Review by DH on 2022-01-21

Client/Project
MAGNIFICENT HOMES
6092 PACK ROAD, LONDON, ONTARIO

Study Area

Methodology February 17, 2022

2.0 Methodology

2.1 Policy Framework

2.1.1 Planning Act

The *Planning Act* provides a framework for land use planning in Ontario, integrating matters of provincial interest in municipal and planning decisions. Part I of the *Planning Act* identifies that the Minister, municipal councils, local boards, planning boards, and the Municipal Board shall have regard for provincial interests, including:

(d) The conservation of features of significant architectural, cultural, historical or scientific interest

(Government of Ontario 1990)

2.1.2 The 2020 Provincial Policy Statement

The Provincial Policy Statement (PPS) was updated in 2020 and is intended to provide policy direction for land use planning and development regarding matters of provincial interest. Cultural heritage is one of many interests contained within the PPS. Section 2.6.1 of the PPS states that, "significant built heritage resources and cultural heritage landscapes shall be conserved".

(Government of Ontario 2020)

Under the PPS definition, conserved means:

The identification, protection, management and use of built heritage resources, cultural heritage landscapes and archaeological resources in a manner that ensures their cultural heritage value or interest is retained. This may be achieved by the implementation of recommendations set out in a conservation plan, archaeological assessment, and/or heritage impact assessment that has been approved, accepted, or adopted by the relevant planning authority and/or decision maker. Mitigative measures and/or alternative development approaches can be included in these plans and assessments.

Under the PPS definition, significant means:

In regard to cultural heritage and archaeology, resources that have been determined to have cultural heritage value or interest. Processes and criteria for determining cultural heritage value or interest are established by the Province under the authority of the Ontario Heritage Act.



Methodology February 17, 2022

Under the PPS, "protected heritage property" is defined as follows:

property designated under Parts IV, V or VI of the Ontario Heritage Act; property subject to a heritage conservation easement under Parts II or IV of the Ontario Heritage Act; property

identified by the Province and prescribed public bodies as provincial heritage property under the Standards and Guidelines for Conservation of Provincial Heritage Properties; property protected under federal legislation, and UNESCO World Heritage Sites.

(Government of Ontario 2020)

2.1.3 City of London Official Plan

The City of London's Official Plan, *The London Plan*, contains the following policy regarding development within or adjacent to designated and listed heritage properties:

586_ The City shall not permit development and site alteration on adjacent lands to heritage designated properties or properties listed on the Register except where the proposed development and site alteration has been evaluated and it has been demonstrated that the heritage attributes of the heritage designated properties or properties listed on the Register will be conserved.

The London Plan also contains the following general objectives regarding cultural heritage resources:

- 1. Promote, celebrate, and raise awareness and appreciation of London's cultural heritage resources.
- 2. Conserve London's cultural heritage resources so they can be passed on to our future generations.
- 3. Ensure that new development and public works are undertaken to enhance and be sensitive to our cultural heritage resources.

(City of London 2016)

2.2 Background History

To understand the historical context of the property, resources such as primary sources, secondary sources, archival resources, digital databases, and land registry records were consulted. Research was also undertaken at the London Public Library. To familiarize the study team with the Study Area, historical mapping from 1862, 1878, and 1913 was reviewed.



Methodology February 17, 2022

2.3 Field Program

A site assessment was undertaken on July 19, 2021, by Frank Smith, Cultural Heritage Specialist and Lashia Jones, Heritage Consultant. The weather conditions were seasonably warm and clear. The site visit consisted of a pedestrian survey of the property. Interor access was not granted.

2.4 Evaluation of Cultural Heritage Value or Interest

2.4.1 Ontario Regulation 9/06

The criteria for determining CHVI is defined by *Ontario Regulation* (O. Reg.) *9/06*. In order to identify CHVI at least one of the following criteria must be met:

- 1. The property has design value or physical value because it:
 - a. is a rare, unique, representative or early example of a style, type, expression, material or construction method
 - b. displays a high degree of craftsmanship or artistic merit
 - c. demonstrates a high degree of technical or scientific achievement
- 2. The property has historical value or associative value because it:
 - a. has direct associations with a theme, event, belief, person, activity, organization or institution that is significant to a community
 - b. yields, or has the potential to yield, information that contributes to an understanding of a community or culture
 - c. demonstrates or reflects the work or ideas of an architect, artist, builder, designer or theorist who is significant to a community
- 3. The property has contextual value because it:
 - a. is important in defining, maintaining or supporting the character of an area
 - b. is physically, functionally, visually or historically linked to its surroundings
 - c. is a landmark

(Government of Ontario 2006a)



Methodology February 17, 2022

2.5 Assessment of Impacts

The assessment of impacts is based on the impacts defined in the Ministry of Heritage, Sport, Tourism and Culture Industries (MHSTCI) *Infosheet #5 Heritage Impact Assessments and Conservation Plans* (Infosheet #5). Impacts to heritage resources may be direct or indirect.

Direct impacts include:

- Destruction of any, or part of any, significant heritage attributes or features
- Alteration that is not sympathetic, or is incompatible, with the historic fabric and appearance

Indirect impacts do not result in the direct destruction or alteration of the feature or its heritage attributes, but may indirectly affect the CHVI of a property by creating:

- Shadows that alter the appearance of a heritage attribute or change the viability of a natural feature or plantings, such as a garden
- Isolation of a heritage attribute from its surrounding environment, context or a significant relationship
- Direct or indirect obstruction of significant views or vistas within, from, or of built and natural features
- A change in land use such as rezoning a battlefield from open space to residential use, allowing new development or site alteration to fill in the formerly open spaces
- Land disturbances such as a change in grade that alters soil, and drainage patterns that adversely affect an archaeological resource

(Government of Ontario 2006b)

In addition to direct impacts related to destruction, this HIA also evaluated the potential for indirect impacts resulting from the vibrations of construction and the transportation of project components and personnel. This was categorized together with land disturbance. Although the effect of traffic and construction vibrations on historic period structures is not fully understood, vibrations may be perceptible in buildings with a setback of less than 40 metres from the curbside (Crispino and D'Apuzzo 2001; Ellis 1987; Rainer 1982; Wiss 1981). For the purposes of this study, a 50-metre buffer is used to represent a conservative approach to delineate potential effects related to vibration. The proximity of the proposed development to heritage resources was considered in this assessment.



Methodology February 17, 2022

2.6 Mitigation Options

In addition to providing a framework to assess the impacts of a proposed undertaking, the MHSTCI Infosheet #5 also provide methods to minimize or avoid impacts on cultural heritage resources. These include, but are not limited to:

- Alternative development approaches
- Isolating development and site alteration from significant built and natural features and vistas
- Design guidelines that harmonize mass, setback, setting, and materials
- Limiting height and density
- Allowing only compatible infill and additions
- Reversible alterations
- Buffer zones, site plan control, and other planning mechanisms

(Government of Ontario 2006b)



Historical Overview February 17, 2022

3.0 Historical Overview

3.1 Introduction

The Study Area is located at 6092 Pack Road, between the intersections of Regiment Road and Bostwick Road. The legal description of the property is 'CON ETR PT LOT 76 REG 2.46 AC 200.00FR 536.26D.' Historically, the Study Area is located on part of Lot 76, East of Talbot Road in the former Township of Westminster. The following sections outline the historical development of the Study Area from the period of colonial settlement to the present-day.

To understand the historical context of the property, resources such as primary sources, secondary sources, archival resources, digital databases, and land registry records were consulted. Due to COVID-19 pandemic restrictions, access to some sources was limited or unavailable.

3.2 Physiography

The Study Area is situated within the "Mount Elgin Ridges" physiographic region (Chapman and Putnam 1984: 144-146). The region is located between the Thames Valley and Norfolk Sand Plain and consists of a succession of ridges and vales. The southern portions of the region drain to Lake Erie via Kettle, Catfish, and Otter Creeks. Northerly parts of the region drain to the Thames River. The two landforms of the region contain contrasting soils. The ridges contain well drained soil while the hollows contain poor drainage. In general, low-lying land in this region is used for pasture while the rolling hills are cultivated. Corn is the most important crop grown in the region and other crops include wheat, grain, and oats. The Mount Elgin Ridges is also considered one of the most prosperous dairy and livestock regions in Ontario (Chapman and Putnam 1984: 145).

3.3 Township of Westminster

3.3.1 Survey and Settlement

The former Township of Westminster and City of London is located on the traditional territory of the Attawandaron, Anishinaabeg, Haudenosaunee, and Lunaapeewak Indigenous peoples (City of London 2021). From the 17th century until 1763, southwestern Ontario was part of the sprawling colony of New France. The French colony was ceded to the British and Spanish following their victory in the Seven Years War in 1763. Much of this new British territory was administered as the Province of Quebec. In 1783, Great Britain recognized the independence of the United States and



Historical Overview February 17, 2022

about 50,000 Loyalists left the fledgling republic for British lands, including Canada (Craig 1963: 3). To accommodate the Loyalists, the British parliament passed the *Constitutional Act of 1791*, which divided Quebec into Upper and Lower Canada. The division was both geographic and cultural: French laws would be preserved in Lower Canada, while the British constitution and laws would be implemented in Upper Canada (Craig 1963: 17).

John Graves Simcoe was selected as Lieutenant Governor of the newly created province. Simcoe was a veteran of the American Revolution, having served in the Queens Rangers, and eagerly planned to build a model British society in Upper Canada. He desired to "inculcate British customs, manners, and principles in the most trivial as well as serious matters" in the new colony (Craig 1963: 20-21). Simcoe intended to populate the new colony with Loyalists and new immigrants from the United States (Taylor 2007: 4-5).

The survey of the Township of Westminster began in 1810 under the direction Deputy Surveyor Simon Zelotes Watson. He began a preliminary survey of the township on May 27, 1810, and the following day started the survey in the northeast corner of the township south of the Thames River. The first line across the township that Watson surveyed was referred to as the baseline and roughly follows the present-day alignment of Baseline Road East (Baker and Neary 2003: 12). Watson was authorized to place settlers along the road and recruited about 300 Americans for settlement. However, Watson's plans were blocked by Colonel Thomas Talbot, causing considerable acrimony between the two men (Paddon 1976: 45).

The overall settlement of Westminster Township during much of the first half of the 19th century was under the superintendence of Colonel Thomas Talbot. He was responsible for the settlement of 26 townships in southwestern Ontario. Talbot had the reputation as a strict superintendent and vigorously enforced the requirement which stipulated that all settlers clear and open at least half of the roadway along their lot. Settlers who ignored the requirement often had their right to settle on their land revoked (Westminster Township Historical Society (WTHS) 2006: 395).

In 1811, Provincial Land Surveyor Mahlon Burwell, a close associate of Colonel Talbot, began to survey additional sections of Westminster Township. He laid out the north branch of Talbot Road (present-day Colonel Talbot Road) to just north of present-day Lambeth, south of the Study Area. Shortly before the war of War of 1812, the former Indigenous trail now called Commissioner's Road, located about 2.4 kilometres north of the Study Area, was widened and improved. Burwell's survey of the remainder of Westminster Township was put on hold during the War of 1812 (Baker and Neary 2003: 28).



Historical Overview February 17, 2022

The War of 1812 caused considerable disruption to the settlement of southwestern Ontario and Westminster Township. Until the War of 1812, the majority of immigrants to Upper Canada, including Westminster Township, were from the United States. Many of these immigrants arrived from New England and New York. Other early settlers to Westminster Township included Scottish immigrants (Miller 1992: 5). Some colonial officials expressed their wariness towards American settlers, with Colonel Talbot writing in 1800 that American immigrants were largely "enticed by a gratuitous offer of land, without any predilection on their part, to the British constitution" (Taylor 2007: 28). During the War of 1812, American settlers were perceived by Loyalists and the British military as disloyal or apathetic towards the war effort. There was some truth to this perception in Westminster Township, and several prominent settlers defected to American forces, including Simon Zelotes Watson (Hamil 1955: 76). After the war, the policy of encouraging immigration from the United States was largely abandoned and British administrators clamped down on granting land to American settlers (Taylor 2007: 31).



Historical Overview February 17, 2022

The survey of Westminster Township resumed in August 1816 with Burwell laying out a northern extension of the Talbot Road between Lots 42 and 43, Concession 1. The Talbot Road served as a direct link between the Township of Westminster and the main Talbot Road to the south. The last portion of the survey, Concessions 3 to 9, was completed between 1819 and 1821 by Deputy Land Surveyor John Bostwick (St. Denis 1985: 19-20). The township was surveyed using the double-front system, with most lots being 200 acres in size (Plate 1). Properties north of Baseline Road on the Broken Front concession were irregularly sized due to the meandering path of the Thames River. The Township was named in for the City of Westminster, the site of the British Parliament. The name was likely chosen because the township was bordered on the north by London Township (Gardiner 1899: 314).



Plate 1: Double Front Survey System (Dean 1969)

3.3.2 19th Century Development

The first administrative meeting for the United Townships of Westminster, Delaware, and Dorchester was held on March 4, 1817, in Archibald McMillan's tavern. In 1817, the township had a population of 428 people in 107 houses. The township had two schools and two mills. The average price of land in 1817 was 20 shillings per acre (Brock and Moon 1972:568). An article published in the Montreal Gazette in June 1831 described the first concession of the Township of Westminster as being settled primarily by Americans and that "many of the farms are extensive and tolerably well cultivated, having good framed barns, fine promising young orchards, and comfortable dwellings" (Brock 1975: 65).

The first post offices were established in Westminster Township in 1840. One was located in present-day Lambeth and another in present-day Byron (WTHS 2006:393). The fertile soil of the township made it agriculturally very productive. In 1849, the township's farmers produced 57,600 bushels of wheat, 54,000 bushels of oats, 12,000 bushels of peas, 22,000 pounds of wool, and 36,000 pounds of butter (WTHS 2006a: 69). The value of cleared land in the township had increased to 60 shillings an acre.



Historical Overview February 17, 2022

Many farmers in the township also produced maple syrup if the wood lots on their farm had maple trees (WTHS 2006a:114). Between 1851 and 1861 the population of Westminster Township increased from 5,069 to 6,285. By this time the population of the township consisted primarily of native-born Canadians, British immigrants, and a small but notable American population (Board of Registrations and Statistics 1853; Board of Registration and Statistics 1863). Railway service entered the township in 1853 when the London and Port Stanley Railway was constructed through the township. The railway linked to the Great Western Railway in London (Port Stanley Terminal Rail 2021).

Hamlets developed throughout the township including Hall's Mills (later Byron), Lambeth, Belmont, Nilestown, Ponds Mills, and Glanworth. Lambeth, located just south of the Study Area, became a major village in Westminster Township (WTHS 2006a: 88-89). Lambeth developed at the intersection of Colonel Talbot and Longwoods Road (WTHS 2006a: 143-144). By the 1880s, Lambeth had several stores, taverns, and a steam spoke factory and had a population of about 200 (Page 1878: vi).

To the north of Westminster Township, the City of London was incorporated in 1855, with a population of 10,000 (Armstrong 1986:68). The development of London and Westminster Township would become increasingly intertwined during the late 19th century as suburban development and the City's infrastructure began to encroach upon Westminster Township. The City constructed a waterworks in the township in 1878, which eventually became part of the popular Springbank Park (McTaggart and Merrifield 2010:17-18). Suburban development also began in an area known as London South, which was eventually annexed by the City in 1890 (Flanders 1977:3). As a result of the annexation, the population of Westminster Township decreased from 7,892 in 1881 to 6,335 in 1891 (Dominion Bureau of Statistics 1953).

3.3.3 **20**th Century Development

Westminster Township remained predominantly agricultural during the first half of the 20th century and the community of Lambeth remained clustered along the intersection of Colonel Talbot Road and Longwoods Road. In 1920, Colonel Talbot Road was incorporated into King's Highway 4. This north-south road ran through much of Southwestern Ontario and was eventually expanded to run from Elgin County to Bruce County (Bevers 2021a). The population of Westminster Township in 1921 was 5,687, an increase of 668 people since 1911 (Dominion Bureau of Statistics 1953). In 1921, a total of 31,254 acres of land were under cultivation in the township, the second highest total in Middlesex County (Dominion Bureau of Statistics 1925:408).



Historical Overview February 17, 2022

While the First World War and Great Depression curtailed major growth of the City of London, the postwar building boom led to the suburbanization of swaths of Westminster Township during the 1950s. Between 1951 and 1956, the population of Westminster Township increased 45%. In 1951, 1954, and 1959, the township allowed several parts of the township east of the Study Area to be annexed into the City to improve municipal services to the newly suburbanized areas (Meligrana 2000:14; Miller 1992: 212-213).

However, the City soon proposed a more ambitious annexation that would more than double the size of the City by incorporating additional lands from Westminster and London Townships. The townships opposed this plan and the Township of Westminster argued that much of the proposed land to be annexed was rural. Representatives of Westminster Township explained they had amicably agreed with the City about ceding suburbanized lands but expressed the belief that rural land did not belong in a City (Meligrana 2000:14). In May 1960, the Ontario Municipal Board ruled in favour of the City and, in 1961, portions of Westminster Township and London Township were annexed. The Study Area remained outside the newly annexed lands.

Another major postwar development in the township was the construction of King's Highway 401 and King's Highway 402. Highway 401, which runs from Windsor to the Quebec/Ontario border was constructed in phases through Southwestern Ontario in the 1960s (Bevers 2021b). Highway 402, which runs from Sarnia to London, was constructed in phases during the 1970s and early 1980s. In 1981, the final stretch of Highway 402 was completed and Highways 401 and 402 merged in Westminster Township (Bevers 2021c).

By the early 1980s, the City of London required more land for future industrial development. The City of London wanted to annex the Highway 401/402 corridor in the Township of Westminster, ideally located for industrial development and just outside of city limits. In 1988, Westminster Township was incorporated as the Town of Westminster, partially in response to London's annexation attempts (WTHS 2006a: 73). Despite the incorporation of the Town of Westminster, in 1992 the province approved an annexation that saw the City of London triple in size (Sancton 1994: 28-29). Effective January 1, 1993 the entire Town of Westminster, including the Study Area, was annexed into the City of London. Also included in the 1993 annexation were portions of London, Delaware, North Dorchester, and West Nissouri Townships (Middlesex County 2016). The population of London in 2016 was 383,822, an increase of 4.8% since 2011 (Statistics Canada 2019).



Historical Overview February 17, 2022

3.4 Property History

Lot 76, East of Talbot Road was granted by the Crown to Peter Swartz (also spelled Swarts) in 1835 (ONLand 2021a). Peter was the son of Henry Swartz, a United Empire Loyalist who initially settled in Thorold Township in Niagara and later relocated to Westminster Township. As the son of a Loyalist, Peter was entitled to his own land grant upon reaching the age of maturity (United Empire Loyalists' Association of Canada 2021; Library and Archives Canada 1830). He likely settled on the lot around 1830 and fulfilled the settlement obligations to obtain patent to the lot in 1835. Settlement obligations typically included clearing a specified amount of land and building a house. Upon completion of these duties, a settler received a patent (Archives of Ontario 2020).

Soon after he obtained patent to the lot, Swartz began to subdivide the property. In 1836, he sold 25 acres of the northwest part of the lot to Jesse Cornell, 50 acres of the northeast quarter to James Upgrove, and 50 acres of the southeast quarter, containing the Study Area, to William Adair (ONLand 2021a). William Adair resided on Gore Road and likely held the southeast quarter of the lot in speculation. He was born in 1796 in Grimsby and later moved to Westminster Township (WTHS 2006b: 4). In 1842, Adair and his wife sold the southeast quarter, containing the Study Area, to David Dale. In 1845, Upgrove sold the northeast quarter to David Dale, resulting in Dale owning the entire east half of Lot 76, East of Talbot Road (ONLand 2021a). David Dale was a son of Jacob Dale, an immigrant from Pennsylvania who moved to Upper Canada in 1811. The Dale family were prominent early settlers in Westminster Township and became extensive landowners, resulting in a part of the township at the intersection of present-day Southdale Road and Wharncliffe Road becoming known as Dale's Corners (present-day Glendale) (WTHS 2006b: 144).

The Census of 1851 lists David Dale as a 40-year-old farmer born in Canada. He lived with his wife Eliza, age 28; son John, age 11; son Caleb, age 9; daughter Anne, age 7; daughter Elizabeth, age 5; daughter Eliza, age 4; and daughter Mary, age 2. The Agricultural Census of 1851 lists David Dale as owning land in Lot 35, Concession 1 and Lot 76, East of Talbot Road. He owned a total of 190 acres of land and had 90 acres under cultivation. The acres under cultivation included 72 acres of crops, 15 acres of pasture, and three acres of gardens or orchards (Library and Archives Canada 1851). The Census of 1861 lists the Dale family as residing in a one- and one-half storey brick house. It is likely Dale and his family resided on Lot 35, Concession 1 as the agricultural return for the Census of 1861 lists Dale with other residents along Concession 1 (Library and Archives Canada 1861). However, historical mapping from 1862 does not show a structure on either of the lots owned by David Dale (Figure 3). David Dale died in 1878 and is buried at Brick Street Cemetery on Commissioners Road (Find-A-Grave 2021a).



Historical Overview February 17, 2022

Following David's death, the Study Area was conveyed via probate to John Dale, the eldest son (ONLand 2021b). Historical mapping from 1878 depicts John Dale as the owner of the property and shows a residence and orchard at the approximate location of present-day 6092 Pack Road (Figure 4). The Census of 1891 lists John Dale as a 49-year-old farmer born in Ontario. He lived with his wife Delaney, age 41; son Robert, age 18; and son John H., age 16 (Library and Archives Canada 1891). Topgographic mapping depicts the present-day residence at 6092 Pack Road and depicts the surrounding area as rural (Figure 5). John Dale died in 1927 and is also buried at Brick Street Cemetery (Find-A-Grave 2021b). Following his death, the property was sold to John Henry Dale (ONLand 2021b).

John Henry Dale and his wife Mary (née Grive) lived on Lot 76, East Talbot Road (Plate 2). In 1934 he leased part of his property to the Hydro Electric Power Commission of Ontario for the erection of transmission lines and in 1939 he leased the oil and gas rights of the property to Luke Smith (ONLand 2021b). Aerial photography from 1942 shows the present-day residence and a barn located at the northeast corner of the property (Figure 6). John H. Dale died around 1962 and Mary Dale died around 1966. Their son Norman took up residence on the property after their deaths. Norman married Marilyn (née Wild) and together they had James Robert, Caroline Susan, Mary Angela, and Lori-Anne (WTHS 2006b: 146-147). Norman Dale and his wife continued to reside on the east half of the Study Area into the 1970s (ONLand 2021b). Lot 76, East of Talbot Road, including the Study Area, remained rural and agricultural into the early 21st century. According to aerial photography, suburban development on the lot began around 2006 near Colonel Talbot Road.





Plate 2: John Henry Dale and Mary Dale (WTHS 2006b: 146)








Study Area (approximate)

Figure Not to Scale

Notes - I. Source: Tremaine, George R. 1862. Tremaine's Map of the County of Middlesex, Canada West. Toronto: George R. & G.M. Tremaine.




Project Location

160940814 REVA Prepared by KB on 2022-01-21 Technical Review by DH on 2022-01-21

MAGNIFICENT HOMES 6092 PACK ROAD, LONDON, ONTARIO HERITAGE IMPACT ASSESSMENT

3

Historical Mapping, 1862






Legend

Study Area (approximate)

Figure Not to Scale

Notes: Page. H.R. 1878. Illustrated Historical Atlas of the County of Middlesex, ONT. Toronto: H.R. Page & Co.



Project Location City of London

160840814 REVA Prepared by KB on 2022-01-21 Technical Review by DH on 2022-01-21

MAGNIFICENT HOMES 6092 PACK ROAD, LONDON, ONTARIO HERITAGE IMPACT ASSESSMENT

Historical Mapping, 1878






Figure Not to Scale

Notes
1. Source: Department of Militia and Defence. 1913. St. Thomas, Ontario.



160940814 REVA Prepared by KB on 2022-01-21 Technical Review by DH on 2021-01-21






Study Area (approximate)

Figure Not to Scale

Notes
1. Source: Department of Lands and Forests. 1942. Line 19, Photo 22.



Project Location City of London

160940814 REVA Prepared by KB on 2022-01-21 Technical Review by DH on 2022-01-21

Client/Project
MAGNIFICENT HOMES
6092 PACK ROAD, LONDON, ONTARIO
HERITAGE IMPACT ASSESSMENT

Aerial Photo, 1942

Site Description February 17, 2022

4.0 Site Description

4.1 Introduction

As outlined in Section 2.3, a site visit was undertaken on July 19, 2021 by Lashia Jones and Frank Smith, both Cultural Heritage Specialists with Stantec. The weather conditions were sunny and seasonably warm. The site visit consisted of a pedestrian survey of the property. Interior access was not granted. Photographs were taken on Nikon D5300 at a resolution of 300 dots per inch and 6000 by 4000 pixels.

4.2 Landscape Setting

The Study Area is located on the north side of Pack Road, approximately 280 metres west of the intersection of Bostwick Road and Pack Road. Pack Road is a two-lane asphalt paved roadway with narrow gravel shoulders. The roadway contains no sidewalks and utility poles run along the north side of the road. West of the Study Area, the south side of the roadway is lined with municipal streetlighting affixed to wooden poles (Plate 3). The Study Area is set is transitioning from a rural and agricultural streetscape to a suburban streetscape. The south side of Pack Road and immediately east of the Study Area remain a rural and agricultural landscape (Plate 4 and Plate 5). West of the Study Area, new detached residences are being constructed adjacent to an existing residential subdivision (Plate 6).

The property at 6092 Pack Road is accessed via two gated entrances located off Pack Road. The primary entrance contains a gravel driveway connected to Pack Road while a secondary entrance is surrounded by lawn (Plate 7 and Plate 8). The property boundary is delineated by post and wire fencing and sections of timber rail fencing (Plate 9). The south border of the property is landscaped with a row of small and intermediate sized cedar hedges while the east and west borders are landscaped with windbreaks of mature Norway spruce trees (Plate 10 to Plate 12). The property is landscaped with a lawn and landscaping along the residence includes cedar bushes, a small Japanese maple tree, and various ornamental perennial plantings (Plate 13). Located to the north of the residence is a deck and pool (Plate 14).



Site Description February 17, 2022



Plate 3: Looking west on Pack Road showing roadway, shoulders, and utility poles



Plate 4: Looking south on Pack Road



Plate 5: Looking east on Pack Road towards Bostwick Road



Plate 6: Looking west at new residential construction



Site Description February 17, 2022



Plate 7: Main entrance, looking southeast



Plate 8: Secondary entrance, looking north



Plate 9: Looking north at section of post and wire and split rail fencing



Plate 10: Cedar hedge, looking south



Site Description February 17, 2022



Plate 11: East and west windbreaks, looking south



Plate 12: Details of west windbreak, looking northwest



Plate 13: Lawn, shrubs, and perennials, looking north



Plate 14: Deck and pool, looking northeast

4.3 Residence

The residence at 6092 Pack Road is a two- and one-half storey structure with a medium pitched cross hip roof with a gable dormer on the main (south) elevation. The roof is clad in asphalt shingles and contains a brick chimney. The residence has a simple compound plan and contains a projecting bay on the east elevation (Plate 15). The exterior of the residence is buff brick with a Flemish bond pattern (Plate 16). The foundation of the residence is rusticated concrete block (Plate 17).

The main (south) elevation contains a gable dormer with bargeboard, fish scales, and a small one pane window with a wood surround. The second storey contains two modern



Site Description February 17, 2022

1/1 windows with segmental arch window openings, buff brick voussoirs, and concrete sills (Plate 18). The first storey contains a rusticated concrete block front porch which wraps around to part of the east elevation. The porch is supported by classically inspired wood columns. The first storey contains a modern horizontal sliding window with a segmental arch window opening, buff brick voussoir, concrete sill, and stained-glass transom (Plate 19). Just east of this window is a modern 1/1 window with a segmental arch window opening, buff brick voussoir, concrete sill, and stained-glass transom (Plate 20). The main entrance is located on projecting bay and consists of a modern door with a stained-glass transom and buff brick voussoir (Plate 21).

The second storey of the east elevation contains two modern 1/1 windows with segmental arch window openings, buff brick voussoirs, and concrete sills. The northeast corner of the second storey contains a modern commercial light fixture. Utility conduits run between the windows of the second and first storeys. The first storey contains two modern windows with segmental arch openings, buff brick voussoirs, concrete sills, and stained-glass transoms. To the north of these windows is a modern entrance door with a buff brick voussoir and small light fixture (Plate 22). Located to the south of these windows is a oval shaped stained-glass window with a buff brick window surround (Plate 23). The basement contains two modern horizontal sliding windows with buff brick voussoirs.

The north elevation contains one modern 1/1 window with a segmental arch opening, buff brick voussoir, and concrete sill in the second storey near the northwest corner and one modern 1/1 window with a segmental arch opening, buff brick voussoir, and concrete sill near the northeast corner. A utility conduit is located just east of the first storey window (Plate 24). A shed roof addition leading to a hip roof garage is attached to the north elevation. The addition and garage are clad in shingle siding and contains a metal roof. The garage doors are composite wood (Plate25).

The second storey of the west elevation contains a modern door that does not lead to a porch or staircase. Above the door is a buff brick voussoir. To the south of this door is a modern 1/1 window with a buff brick voussoir and concrete sill and a commercial light fixture. The first storey contains three modern 1/1 windows with buff brick voussoirs and concrete sills. The basement contains three horizontal sliding windows with buff brick voussoirs (Plate 26).



Site Description February 17, 2022



Plate 15: Looking north showing two and one half storey structure, hip roof, brick chimney, gable dormer, and projecting east bay



Plate 16: Flemish brick bond pattern



Plate 17: Looking west at foundation



Plate 18: Looking north at gable dormer and second storey windows



Site Description February 17, 2022



Plate 19: Looking north at first storey



Plate 20: Stained glass transom, looking north



Plate 21: Main entrance, looking north



Plate 22: East elevation, looking west



Plate 23: Oval window, looking west



Plate 24: North elevation, looking south



Site Description February 17, 2022



Plate25: Additions, looking south



Plate 26: West elevation, looking east

4.4 Outbuildings

An outbuilding approximately 10 metres in length is located at the north end of the property. The outbuilding is a gable roof structure with metal roof cladding (Plate 27). The outbuilding is clad in timber siding and rests on concrete footings (Plate 28). The main (east) elevation contains a modern garage door and modern metal door. The north, south, and west elevations contain no entrances or windows.

Located southeast of the outbuilding are the ruins of a barn. Based on a review of aerial photography, the barn collapsed or was demolished between 1968 and 2006. The area around the former barn contains various debris and is overgrown with vegetation (Plate 29). However, sections of concrete and stone foundations are visible (Plate 30).



Plate 27: Gable roof outbuilding, east elevation looking west



Plate 28: Concrete footing, looking south



Site Description February 17, 2022



Plate 29: Barn ruins area, looking northeast



Plate 30: Remaining stone foundation, looking southwest



Comparative Analysis February 17, 2022

5.0 Comparative Analysis

The property at 6092 Pack Road is listed on the City's Register as a "vernacular" building constructed in 1900. It was added to the Register on March 26, 2007. The City of London defines vernacular architecture as "a term which relies on the common architectural influences of a building's period of construction; exhibiting local design characteristics and uses easily available building materials. May be influenced by, but not necessarily defined by, a particular architectural style. A building considered to be reflective of its time" (City of London 2019). The property at 6092 Pack Road is one of 469 properties in the City classified as vernacular on the Register. The Register contains 5,948 properties and vernacular structures account for 7.8% of all listed and designated properties.

Based on historical research and the site investigation, the residence at 6092 Pack Road is an Ontario vernacular structure which exhibits Queen Anne design elements. Vernacular design elements of 6092 Pack Road include the use of buff brick, rusticated concrete block, and its incorporation of Queen Anne design elements, which was a popular design style in the late 19th and early 20th centuries.

Within southwestern Ontario, buff brick was one of the most readily available building materials in the 19th and early 20th centuries. Buff brick is comprised of Erie Clay, which gives the bricks their distinctive buff colouring. Due to the high costs associated with transporting such a heavy material, buff brick was prevalent in southwestern Ontario due to its local availability (Tausky and DiStefano 1986: 1986: 90). Rusticated concrete block, also called rock faced concrete block, was developed during the 1890s and popularized in 1900 when Harmon S. Palmer received a United States patent for a machine that produced hollow concrete blocks. Rusticated concrete block quickly became a popular and low-cost building material and was most prevalently used between 1905 and 1930 (Simpson 1989:108-109). In London, cement blocks became widespread in the first decade of the 20th century, and the first blocks were manufactured in London starting in 1907 (Tausky and DiStefano 1986:97).

Queen Anne design elements of 6092 Pack Road include the use of bargeboard and fish scales in the gable dormer, the use of stained glass, including the oval window, and the compound plan. The Queen Anne design style was popular in Ontario from about 1880 to 1910 (Blumenson 1990: 102-103). Based on the architectural style of the residence and the use of rusticated concrete block as a foundation material, the residence was likely built between approximately 1900 and 1910. It likely replaced an earlier residence on the site built in the 1870s. The residence retains a high degree of integrity and aside from the replacement of windows and the addition of an attached garage, remains relatively unmodified.



Evaluation of Cultural Heritage Value or Interest February 17, 2022

6.0 Evaluation of Cultural Heritage Value or Interest

6.1 Introduction

The criteria for determining CHVI is defined by O. Reg. 9/06. If a property meets one or more of the criteria it is determined to contain, or represent, a cultural heritage resource. A summary statement of cultural heritage value will be prepared, and a list of heritage attributes which define the CHVI identified. The evaluation of 6092 Pack Road according to O. Reg. 9/06 is provided in subsequent sections below.

6.2 Design or Physical Value

The residence at 6092 Pack Road has design value as a representative example of an early 20th century Ontario vernacular structure with Queen Anne design elements. Vernacular design elements of 6092 Pack Road include the use of buff brick, rusticated concrete block, and its incorporation of Queen Anne design elements, which was a popular design style in the late 19th and early 20th centuries. The Queen Anne design elements of 6092 Pack Road include the use of bargeboard, fish scales, stained glass, an oval shaped window, and the compound plan of the residence. The residence retains a high degree of integrity and aside from the replacement of windows and the addition of an attached garage, remains relatively unmodified. The residence cannot be considered rare or unique as many examples of Ontario vernacular structures and Queen Anne structures remain in the City of London and were a common design style throughout Ontario in the late 19th to early 20th centuries. As a vernacular structure, the building materials, construction methods, and quality of craftsmanship were typical and industry standard at the time of the construction of the residence. Therefore, the residence does not demonstrate a high degree of craftsmanship or a high degree of technical or scientific achievement.

The outbuildings do not demonstrate physical or design value. The gable roof outbuilding has been modified with modern doors, including a garage door. Its current configuration reflects a modern garage, not an outbuilding associated with agricultural activity. The barn has collapsed or was demolished, and little tangible signs remain visible aside from small sections of foundation.



31

Evaluation of Cultural Heritage Value or Interest February 17, 2022

6.3 Historic or Associative Value

The property at 6092 Pack Road is directly associated with the Dale family and was occupied by members of the Dale family from 1842 until at least the early 1970s. The Dale family in the former Westminster Township traces its origins to Jacob Dale, an early settler to Westminster Township from Pennsylvania. Dale and his children became extensive landholders in Westminster Township, particularly around the intersection of present-day Southdale Road and Wharncliffe Road. This area is still referred to as Glendale in recognition of the family. The Study Area was occupied by four generations of the Dale family, including David Dale (a son of Jacob Dale), John Dale, John Henry Dale, and Norman Dale. The Dale family, through their extensive landholdings have made a notable contribution to the pattern of settlement of the former Westminster Township, most notably demonstrated by the continued use of the name Glendale within London.

The property contains a residence, outbuilding, Norway spruce windbreaks, and the ruins of a barn. These property components do not offer or potentially offer new knowledge that can contribute to a greater understanding of the former Township of Westminster or City of London. The architect or designer of the residence at 6092 Pack Road is unknown.

6.4 Contextual Value

The property is set in a landscape that remains largely rural and agricultural but is in the process of transitioning to a suburban landscape. The property consists of a residence and small outbuilding and while set on a large lot, has been severed from agricultural fields and little tangible signs remain of the former agricultural use of the property. Therefore, 6092 Pack Road does not contribute to the agricultural character of the area. While it is a rural property, suburban subdevelopment is encroaching upon this character from the west, giving Pack Road an increasingly mixed streetscape. The property is set in the broader context of an area transitioning from a rural to a suburban landscape. The property is no longer used for agricultural purposes and no physical, functional, or visual link to its past agricultural use exists on the property or within the broader context of the area.

The property at 6092 Pack Road is one of many rural properties located on the southern outskirts of London. The property is not located on a main road and is not particularly memorable or easily discernible from a wayfinding perspective. Therefore, the property is not considered to be a landmark.



Evaluation of Cultural Heritage Value or Interest February 17, 2022

6.5 Summary of Evaluation

Table 1 provides a summary of the findings of CHVI based on an evaluation according to O. Reg. 9/06.

Table 1 Evaluation of 6092 Pack Road according to O. Reg. 9/06

	Criteria of O. Reg. 9/06	Yes/No	Comments
Design or Physical Value	Is a rare, unique, representative, or early example of a style, type, expression, material, or construction method	Yes	The residence at 6092 Pack Road has design value as a representative example of an early 20th century Ontario vernacular structure with Queen Anne design elements. Vernacular design elements of 6092 Pack Road include the use of buff brick, rusticated concrete block, and its incorporation of Queen Anne design elements, which was a popular design style in the late 19th and early 20th centuries. The Queen Anne design elements of 6092 Pack Road include the use of bargeboard, fish scales, stained glass, an oval shaped window, and the compound plan of the residence.
	Displays a high degree of craftsmanship or artistic merit	No	The craftsmanship and artistic merit of the property is typical and industry standard for the early 20 th century.
	Demonstrates a high degree of technical or scientific achievement	No	As a vernacular structure, the building materials, construction methods, and quality of craftsmanship were typical and industry standard at the time of the construction of the residence.



Evaluation of Cultural Heritage Value or Interest February 17, 2022

	Criteria of O. Reg. 9/06	Yes/No	Comments
Historic or Associative Value	Has direct associations with a theme, event, belief, person, activity, organization, or institution that is significant to a community	Yes	The property at 6092 Pack Road is directly associated with the Dale family and was occupied by members of the Dale family from 1842 until at least the early 1970s. The Dale family in the former Westminster Township traces its origins to Jacob Dale, an early settler to Westminster Township from Pennsylvania. Dale and his children became extensive landholders in Westminster Township, particularly around the intersection of present-day Southdale Road and Wharncliffe Road. This area is still referred to as Glendale in recognition of the family.
	Yields, or has the potential to yield, information that contributes to an understanding of a community or culture	No	The property contains a residence, outbuilding, Norway spruce windbreaks, and the ruins of a barn. These property components do not offer or potentially offer new knowledge that can contribute to a greater understanding of the former Township of Westminster or City of London.
	Demonstrates or reflects the work or ideas of an architect, artist, builder, designer, or theorist who is significant to a community	No	The architect or builder is unknown.
Contextual Value	Is important in defining, maintaining, or supporting the character of an area	No	The property is set in a landscape that remains largely rural and agricultural but is in the process of transitioning to a suburban landscape, resulting in Pack Road having an in increasingly mixed streetscape.
	Is physically, functionally, visually, or historically linked to its surroundings	No	The property is set in the broader context of an area transitioning from a rural to a suburban landscape. The property is no longer used for agricultural purposes and no physical, functional, or visual link to its past agricultural use exists on the property or within the broader context of the area.



Evaluation of Cultural Heritage Value or Interest February 17, 2022

Criteria of O. Reg. 9/06	Yes/No	Comments
Is a landmark	No	The property at 6092 Pack Road is one of many rural properties located on the southern outskirts of London. The property is not located on a main road and is not particularly memorable or easily discernible from a wayfinding perspective.

6.6 Statement of Cultural Heritage Value

6.6.1 Description of Property

The property at 6092 Pack Road is located in the City of London on the north side of Pack Road, approximately 280 metres west of the intersection of Bostwick Road and Pack Road. The property contains a residence, Norway spruce windbreak, outbuilding, and barn ruins. The residence was built between approximately 1900 and 1910 and is an example of an Ontario vernacular structure with Queen Anne design elements.

6.6.2 Cultural Heritage Value

The residence at 6092 Pack Road has design value as a representative example of an early 20th century Ontario vernacular structure with Queen Anne design elements. Vernacular design elements of 6092 Pack Road include the use of buff brick, rusticated concrete block, and its incorporation of Queen Anne design elements, which was a popular design style in the late 19th and early 20th centuries. The Queen Anne design elements of 6092 Pack Road include the use of bargeboard, fish scales, stained glass, an oval shaped window, and the compound plan of the residence.

The property demonstrates historical and associative value through its four-generation connection to the Dale family. The Dale family in the former Westminster Township traces its origins to Jacob Dale, an early settler to Westminster Township from Pennsylvania. Dale and his children became extensive landholders in Westminster Township, particularly around the intersection of present-day Southdale Road and Wharncliffe Road. This area is still referred to as Glendale in recognition of the family. The property at 6092 Pack Road was occupied by David Dale, John Dale, John Henry Dale, and Norman Dale. The Dale family, through their extensive landholdings have made a notable contribution to the pattern of settlement of the former Westminster Township, most notably demonstrated by the continued use of the name Glendale within London.



Evaluation of Cultural Heritage Value or Interest February 17, 2022

6.6.3 Heritage Attributes

- Representative example of an early 20th century Ontario vernacular structure with Queen Anne design elements, including:
 - Two- and one-half storey structure with compound plan
 - Hip roof with brick chimney and gable dormer containing bargeboard and fish scales
 - Buff brick exterior
 - Segmental arch window openings with buff brick voussoirs and concrete sills
 - Stained glass transoms located above main entrance and first storey windows on the south and east elevations
 - Wrap around rusticated concrete block porch with classically inspired wood columns
 - Oval shaped stained-glass window on east elevation
 - Rusticated concrete block foundation



Impact Assessment February 17, 2022

7.0 Impact Assessment

7.1 Description of Proposed Undertaking

2847011 Ontario Inc. is proposing to redevelop the property at 6092 Pack Road. The concept plan envisions the development of a mix of housing forms on the site including 33 two and one half storey cluster townhouse units, six three and one half storey back-to-back townhouse units, and the retention of the original part of the existing early 20th century residence. The proposed undertaking includes the removal of the shed roof and hip roof additions on the north elevation of the residence. Each townhouse unit and the existing residence will contain two parking spots. A vision brief of the proposed redevelopment is contained in Appendix A. The six three and one half storey back-to-back townhouse units will be located just west of the existing early 20th century residence. Renderings of the proposed back-to-back townhouse units are contained in Appendix B.

7.2 Assessment of Impacts

The residence at 6092 Pack Road has CHVI since it meets two criteria for determining CHVI in O. Reg 9/06. Accordingly, an assessment of potential impacts is limited to the heritage attributes of 6092 Pack Road (see Section 6.6.3). Impacts are defined by Info Sheet #5 (Section 2.5). Table 2 and Table 3 contains an assessment of impacts.

Table 2: Evaluation of Potential Direct Impacts

Direct Impact	Impact Anticipated	Relevance to 745 Waterloo Street
Destruction of any, or part of any, significant heritage attributes or features.	No	The proposed undertaking would not result in the demolition of any heritage attributes at 6092 Pack Road. Therefore, no mitigation measures are required.
Alteration that is not sympathetic, or is incompatible, with the historic fabric and appearance.	No	The proposed undertaking would not result in alteration that is unsymphathetic or incompatibale with the historic fabric and appearance of 6092 Pack Road. While the rear shed roof and hip roof additions will be removed, these additions contain no heritage attributes and include a modern garage clad in shingles. Therefore, no mitigation measures are required.



37

Impact Assessment February 17, 2022

Table 3: Evaluation of Potential Indirect Impacts

Indirect Impact	Impact Anticipated	Relevance to 745 Waterloo Street
Shadows created that alter the appearance of a heritage attribute or change the viability of a natural feature or plantings, such as a garden	No	No natural features were identified as heritage attributes at 6092 Pack Road. Therefore, no mitigation measures are required.
Isolation of a heritage attribute from its surrounding environment, context, or a significant relationship	No	No contextual relationships were identified as heritage attributes at 6092 Pack Road. Therefore, no mitigation measures are required.
Direct or indirect obstruction of significant views or vistas within, from, or of built and natural features	No	Views at the Study Area or the surrounding streetscape were not identified as heritage attributes. As such, significant views will not be obstructed by the proposed undertaking. Therefore, no mitigation measures are required.
A change in land use such as rezoning a battlefield from open space to residential use, allowing new development or site alteration to fill in the formerly open spaces	No	The property is currently zoned as Urban Reserve, which provides for and regulates existing uses on lands which are primailry undeveloped for urban uses. Permitted uses for Urban Reserve zoned lands includes the use of existing dwellings. The proposed undertaking will result in a rezoning to allow for medium density residential development. Development on the site will continue to be residential in nature, and while density on the site will increase, it will not result in a change in land use that impacts the heritage attributes of the property.
		Therefore, no mitigation measures are required.
Land disturbances such as a change in grade that alters soil, and drainage patterns that adversely affect an archaeological resource	Possible	Typically, indirect impacts resulting from land disturbances apply to archaeological resources, which are beyond the scope of this report. No further consideration to archaeological resources is provided in this report. However, land disturbance from construction (e.g., site grading and related construction activities) may also have the potential to impact built heritage resources through temporary vibrations during the construction period that may cause shifts in foundations or masonry structures that can



Impact Assessment February 17, 2022

Indirect Impact	Impact Anticipated	Relevance to 745 Waterloo Street
		impact the heritage resource. Therefore, mitigation measures are required.

7.3 Discussion of Impacts

The proposed undertaking would not result in direct impacts to the property at 6092 Pack Road. The existing residence will be retained *in situ* and no heritage attributes will be altered as part of the proposed undertaking. While the existing shed roof addition and hip roof addition of the residence will be removed, both do not contain heritage attributes.

No indirect impacts are anticipated from shadows, isolation, or obstruction. There may be potential for indirect impacts related to land disturbance during the construction phase that could result in vibrations that are damaging to the structure. While a change in land use is anticipated to allow for higher density than is currently permitted, the property will remain residential in nature and the proposed changes are not anticipated to impact the heritage attributes or heritage value of the property.

While impacts of vibration on heritage buildings are not well understood, studies have shown that impacts may be perceptible in buildings 40 metres from the curbside when heavy traffic is present (Ellis 1987). Construction of the proposed undertaking may involve heavy vehicles on site to grade, excavate, or pour foundations, which may result in vibrations that have potential to affect the historic foundations of 6092 Pack Road. If left unaddressed, these could result in longer-term issues for the maintenance, continued use, and conservation of the building.



Mitigation February 17, 2022

8.0 Mitigation

The property at 6092 Pack Road was determined to contain CHVI as it meets two criteria of O. Reg 9/06. As identified in Table 2 and Table 3, the proposed undertaking has the potential to result in an indirect impact to 6092 Pack Road as on site construction activity could result in vibrations that have potential to affect historic foundations. Accordingly, the mitigation options identified in InfoSheet #5 Mitigation Options (see Section **Error! Reference source not found.**) have been explored below.

8.1 InfoSheet #5 Mitigation Options

Alternative development approaches: The proposed development will retain the existing residence and its heritage attributes *in situ*. Alternative development approaches to isolate the residence from land disturbance is not feasible given the size of the property and the proposed residential intensification. Therefore, to retain the residence *in situ*, construction activity will be required within 50 metres of the property and this mitigation measure is not feasible.

Isolating development and site alteration from significant built and natural features and vistas: The proposed development has isolated new structures from the existing residence and its heritage attributes. The existing residence will be retained *in situ* and all heritage attributes will remain visible. As such, this mitigation measure has already been implemented in the proposed development.

Design guidelines that harmonize, mass, setback, setting, and materials: The proposed undertaking includes design guidelines that harmonize mass, setback, setting and materials. The six townhomes proposed just west of the existing residence contain a massing, setback, setting, and materials that is symphathetic to the existing residence. The massing of these six townhomes are similar to the existing two and one half storey residence. In addition, the main elevation of the six townhomes contains projecting gable bays complimentary to the massing and form of the existing residence. The setback and setting of the six new townhomes has been designed to be in-line with the existing residence, and current concept plans indicate that the setback difference between the new townhomes and existing residence will be 2.1 metres (6 feet 8 inches). Materials selected for the six new townhomes are symphathetic to the existing residence and include the use of buff brick. As such, this mitigation measure has already been implemented in the proposed development.

Limiting height and density: The height and density of the proposed development has been designed to not overshadow the existing residence and to provide open common amenity areas near the existing residence. Therefore, the proposed undertaking contains considerations to limit height and density in relation to the existing residence.



Mitigation February 17, 2022

Allowing only compatible infill: Redevelopment at the property is to be residential in nature and retain the existing residence *in situ*. The six townhomes proposed just west of the existing residence contain a massing, setback, setting, and materials that is symphathetic to the existing residence. The townhomes to be located north of the existing residence will be two and one half storeys, a height compatible with the massing of the existing residence. Therefore, this mitigation measure has been implemented in the proposed development.

Reversible alterations: Given that the proposed development retains the residence *in situ* and does not directly impact the heritage attributes, reversible alterations are not required.

Buffer zones, site plan control, and other planning mechanisms: The proposed development may result in the potential for land disturbance during the construction phase of the project. As such, planning mechanisms and site plan controls may be considered at this phase of study to avoid impacts to the built heritage resource. Site plan controls and planning mechanisms may be used to identify appropriate thresholds for vibration or zones of influence related to construction activity. Construction activity should be planned to minimize vibrations on built heritage resources. Therefore, this mitigation measure is appropriate for the proposed development.

8.2 Mitigation Discussion

Based on the discussion of Mitigation Options in Section 8.1, it has been determined that planning mechanisms and site plan controls are appropriate mitigation measures. These measures are intended to lessen the impact on identified heritage attributes resulting from the potential for land disturbance due to temporary vibrations during the construction phase of the project..

A typical approach to mitigating the potential for vibration effects is twofold. First, a preconstruction vibration assessment can be completed to determine acceptable levels of vibration given the site-specific conditions (including soil conditions, equipment proposed to be used, and building characteristics). Second, depending on the outcome of the assessment, further action may be required in the form of site plan controls, site activity monitoring, or avoidance. This should be considered prior to the commencement of any construction activities onsite.



Recommendations February 17, 2022

9.0 Recommendations

The proposed undertaking will conserve the built heritage resource at 6092 Pack Road. An assessment of impacts resulting from the proposed undertaking at 6092 Pack Road has determined no direct impacts are anticipated and the undertaking may possibly result in indirect impacts from land disturbance due to temporary vibrations during the construction phase of the project. Based on the impacts identified to the cultural heritage resource and the proposed undertaking, the following mitigation measure is recommended:

- Retain a qualified person(s) to complete a pre-construction vibration assessment to determine acceptable levels of vibration given the site-specific conditions (including soil conditions, equipment proposed to be used, and building characteristics)
- Should the residence be determined to be within the zone of influence, additional steps should be taken to secure the building from experiencing negative vibration effects (i.e., adjustment of machinery or establishment of buffer zones)

9.1 Deposit Copies

To assist in the retention of historic information, copies of this report should be deposited with local repositories of historic material as well as with municipal and regional planning staff. Therefore, it is recommended that this report be deposited at the following location:

London Public Library 251 Dundas Street London, ON N6A 6H9



Closure February 17, 2022

10.0 Closure

This report has been prepared for the sole benefit of 2847011 Ontario Inc. and may not be used by any third party without the express written consent of Stantec Consulting Ltd. Any use which a third party makes of this report is the responsibility of such third party.

We trust this report meets your current requirements. Please do not hesitate to contact us should you require further information or have additional questions about any facet of this report.

Stantec Consulting Ltd.

Meaghan Rivard MA, CAHP Senior Heritage Consultant Tel: (519) 645-3350 Cell: (226) 268-9025 meaghan.rivard@stantec.com **Tracie Carmichael** BA, B.Ed. Managing Principal, Environmental Services Cell: (226) 927-3586 tracie.carmichael@stantec.com



References February 17, 2022

11.0 References

- Archives of Ontario. 2020. From Grant to Patent: A Guide to Early Land Settlement Records ca. 1790-ca.1850. Electronic Document:

 http://www.archives.gov.on.ca/en/access/documents/research_guide_215_grant_to_patent.pdf. Last Accessed: January 13, 2022.
- Armstrong, Frederick. 1986. *The Forest City, An Illustrated History of London, Canada.*Windsor: Windsor Publications Ltd.
- Baker, Michael and Neary, Hilary Bates. 2003. *London Street Names*. Toronto: James Lorimer & Company.
- Bevers, Cameron. 2021a. *History of King's Highway 4*. Electronic Document: http://www.thekingshighway.ca/Highway4.htm. Last Accessed: January 13, 2022..
- Bevers, Cameron. 2021b. *History of King's Highway 401*. Electronic Document: http://www.thekingshighway.ca/Highway401.htm. Last Accessed: January 13, 2022.
- Bevers, Cameron. 2021c. *History of King's Highway 402*. Electronic Document: http://www.thekingshighway.ca/Highway402.htm. Last Accessed: January 13, 2022.
- Blumenson, John. 1990. Ontario Architecture. Canada: Fitzhenry and Whiteside.
- Brock, Daniel and Muriel Moon. 1972. *The History of the County of Middlesex, Canada*. Belleville: Mika Studio.
- Board of Registration and Statistics. 1853. *Census of the Canadas for 1851-52.* Quebec: John Lovell.
- Board of Registration and Statistics. 1863. *Census of the Canada 1860-61*. Quebec: S.B. Foote.
- Dominion Bureau of Statistics. 1953. *Census of Canada 1951, Volume 1—Population.*Ottawa: Edmond Cloutier.
- Chapman, L.J. and Putnam D.F. 1984. *The Physiography of Southern Ontario Third Edition*, Ontario Geological Survey. Special Volume 2. Ontario: Ministry of Natural Resources.



- City of London. 2016. *The London Plan*. Electronic Document:

 https://london.ca/government/council-civic-administration/master-plans-strategies/london-plan-official-plan. Last accessed: January 13, 2022.
- City of London. 2019. *City of London Register of Cultural Heritage Resources*. Electronic Document: https://london.ca/sites/default/files/2020-10/Register-2019-AODA.pdf. Last Accessed: January 13, 2022.
- City of London. 2021. *City of London Land Acknowledgement*. Electronic Document: https://london.ca/city-london-land-acknowledgement. Last Accessed: January 13, 2022.
- Craig, Gerald. 1963. *Upper Canada: The Formative Years.* Don Mills: Oxford University Press.
- Crispino, M. and M. D'Apuzzo. 2001. Measurement and Prediction of Traffic-induced Vibrations in a Heritage Building. *Journal of Sound and Vibration* 246 (2): 319-335.
- Dean, W.G. 1969. *Economic Atlas of Ontario*. Ontario: University of Toronto Press.
- Department of Lands and Forests. 1942. *Line 19, Photo 22.* Accessed via Western University.
- Ellis, Patricia. 1987. Effects of Traffic Vibration on Historic Buildings. *The Science of the Total Environment* 59: 37-45.
- Find-a-Grave. 2021a. *David Dale*. Electronic Document: https://www.findagrave.com/memorial/157084969/david-dale. Last Accessed: January 13, 2022.
- Find-a-Grave. 2021b. John Dale. Electronic Document:

 <a href="https://www.findagrave.com/memorial/search?firstname=John&middlename=&lastname=Dale&birthyear=&birthyearfilter=&deathyear=&deathyearfilter=&location=Middlesex+County%2C+Ontario%2C+Canada&locationId=county_5476&memo_rialid=&mcid=&linkedToName=&datefilter=&orderby=r.. Last Accessed: January 13, 2022.
- Flanders, Douglas. 1977. The South London Planning District: A Report for the Local Advisory Committee for Architectural Conservation in London, Ontario.
- Gardiner, Herbert F. 1899. *Nothing But Names.* Toronto: George N. Morang and Company.



- Government of Ontario. 1990. *Planning Act, R.S.O. 1990, CHAPTER P.13*. Electronic Document: https://www.ontario.ca/laws/statute/90p13. Last accessed: January 13, 2022.
- Government of Ontario. 2006a. *Ontario Regulation 9/06, Criteria for Determining Cultural Heritage Value or Interest, Under the Ontario Heritage Act.* Electronic document: https://www.ontario.ca/laws/regulation/060009. Last accessed: January 13, 2022.
- Government of Ontario. 2006b. InfoSheet #5 in Heritage Resources in the Land Use Planning Process, Cultural Heritage and Archaeology Policies of the Ontario Provincial Policy Statement, 2005. Ministry of Heritage, Sport, Tourism, and Culture Industries Toronto: Queen's Printer for Ontario.
- Government of Ontario. 2020. *Provincial Policy Statement, 2020.* Electronic Document: https://files.ontario.ca/mmah-provincial-policy-statement-2020-accessible-final-en-2020-02-14.pdf. Last Accessed: January 13, 2022.
- Hamil, Fred. 1955. Lake Erie Baron. Toronto: MacMillan Company.
- Library and Archives Canada. 1830. *Upper Canada Land Petitions (1763-1865).* Volume 469, Bundle S 18, Petition 162.
- Library and Archives Canada. 1851. *Census of 1851, Canada East, Canada West, New Brunswick, and Nova Scotia*. District 23, Subdistrict 222, Reel C-11738.
- Library and Archives Canada. 1861. Census of Canada, Canada East, Canada West, Prince Edward Island, New Brunswick and Nova Scotia. District Middlesex, Subdistrict Westminster, Reel C-1051.
- Library and Archives Canada. 1891. *Census of Canada, 1891.* District 92, Subdistrict D, Reel T-6353.
- McTaggart, Ken and Paul Merrifield. 2010. *The History of the Pumphouse and Springbank Park.* London: Ken McTaggart.
- Meligrana, John F. 2000. The Politics of Municipal Annexation: The Case of the City of London's Territorial Ambitions during the 1950s and 1960s. In *Urban History Review 291: 3-20.*
- Middlesex County. 2016. *History of Middlesex County.* Electronic Document: https://www.middlesex.ca/living-here/history-middlesex-county. Last Accessed: January 13, 2022.
- Miller, Orlo. 1992. London 200: An Illustrated History. London: Chamber of Commerce



- ONLand. 2021a. *Middlesex County (33), Westminster, Book 3.* Electronic Document: https://www.onland.ca/ui/33/books/57936/viewer/163191320?page=39. Last Accessed: July 16, 2021.
- ONLand. 2021b. *Middlesex County (33), Westminster, Book 8.* Electronic Document: https://www.onland.ca/ui/33/books/57944/. Last Accessed: July 16, 2021.
- Page. H.R. 1878. *Illustrated Historical Atlas of the County of Middlesex, ONT.* Toronto: H.R. Page & Co.
- Paddon, Wayne. 1976. The Story of the Talbot Settlement 1803-1840. Canada: Wayne Paddon.
- Port Stanley Terminal Railway. 2021. *A Brief History of the L&PS and PTSR.* Electronic Document: https://www.pstr.on.ca/history.htm. Last Accessed: January 13, 2022.
- Sancton, Andrew. 1994. *Governing Canada's City Regions: Adapting Form to Function.*Montreal: Institute for Research on Public Policy.
- Simpson, Pamela H. 1989. Cheap, Quick, and Easy: The Early History of Rockfaced Concrete Block Building. In *Perspectives in Vernacular Architecture*, 3, pp. 108-118.
- Statistics Canada. 2019. Census Profile, 2016 Census, London, City. Electronic Document: <a href="https://www12.statcan.gc.ca/census-recensement/2016/dp-pd/prof/details/Page.cfm?Lang=E&Geo1=CSD&Code1=3539036&Geo2=PR&Code2=47&Data=Count&SearchText=North&SearchType=Begins&SearchPR=01&B1=All. Last Accessed: July 15, 2021.
- Tausky, Nancy and Lynne DiStefano. 1986. *Victorian Architecture in London and Southwestern Ontario: Symbols of Aspiration*. Toronto: University of Toronto Press and London Regional Art Gallery.
- Taylor, Alan. 2007. "The Late Loyalists: Northern Reflections of the Early American Republic." In *Journal of the Early Republic* Volume 27, Number 1.
- Tremaine, George R. 1862. Tremaine's Map of the County of Middlesex, Canada West. Toronto: George R. & G.M. Tremaine.
- United Empire Loyalists' Association of Canada. 2021. Loyalist Directory, Henry Swarts. Electronic Document: http://www.uelac.org/Loyalist-lnfo/detail.php?letter=s&line=1015. Last Accessed: January 13, 2022.




- Westminster Township Historical Society (WTHS). 2006a. *Delaware and Westminster Townships, Honouring our Roots, Volume I.* Aylmer: Westminster Township Historical Society.
- Westminster Township Historical Society (WTHS). 2006b. *Delaware and Westminster Townships, Honouring our Roots, Volume II.* Aylmer: Westminster Township Historical Society
- Rainer, J.H. 1982. Effects of Vibrations on Historic Buildings. *The Association for Preservation Technology* XIV (1) 2-10.
- Wiss, J.F. 1981. Construction Vibrations: State-of-the-Art. *Journal of Geotechnical Engineering Division* 107: 167-181.



Appendix A Concept Plan





[SIV-IK] PLANNING

VISION BRIEF

Client

Project Site

2847011 Ontario Inc. 6092 Pack Road /

6092 Pack Road / London / ON.

Description

Background Info and Summary of Development Vision

09.21.2021

Contact

Jerzy Smolarek jsmolarek@siv-ik.ca | 519.694.6924 | siv-ik.ca

CONTENTS

51: Background	U
S2: Planning Intelligence	0!
S3: Design Considerations	0
S4: Design Principles	09
S5: Zoning Approach	1
S6: Preliminary Concept	1:
S7: Planning Issues	1

ABOUT THIS REPORT

This brief has been prepared by Siv-ik Planning and Design Inc. for 2847011 Ontario Inc. as part of Phase 2 of our *EXPLORE* process. The brief contains background information about the project site, an overview of the key design considerations, a description of our preliminary design principles and highlights of the preliminary development concept. The brief is meant to articulate our understanding of, and vision for, the site in a manner that supports preliminary stakeholder consultation for the proposed development of 6092 Pack Road.

Siv-ik's focus on research allows us to see innovative solutions and strategies where others can't. From concept to reality, our commitment to explore drives success.

www.siv-ik.ca

PREPARED BY

Siv-ik Planning and Design Inc.

PREPARED FOR

2847011 Ontario Inc.

VERSION 1.0

ISSUED

09.21.2021

CONTACT

Jerzy Smolarek I Partner 519.694.6924 jsmolarek@siv-ik.ca

COPYRIGHT NOTICE

Copyright © 2021 by Siv-ik Planning and Design Inc. The content of this document is the intellectual property of Siv-ik Planning and Design Inc. Reproduction or redistribution of any portion of this document or use of the intellectual ideas contained within it for any purpose is prohibited without the written consent of Siv-ik Planning and Design Inc.

S1: BACKGROUND

S1.1 Introduction

6092 Pack Road (the project site) is a remnant "rural residential" parcel located in the southwest quadrant of London, on the north side of Pack Road and approximately 275 metres (~2.5 minute walk) west of Bostwick Road. The project site is located in the North Talbot Community which encompasses the area generally bounded by Southdale Road to the north, Bostwick Road to the east, Pack Road to the south and Colonel Talbot Road to the west. The site contains an existing 20th-Century Farm Dwelling with an added attached garage and an outbuilding in the rear yard. None of the land is actively farmed and it is of sufficient size and shape to accommodate urban residential development. With the site being located in proximity to municipal services and the planned urbanization of the broader area, 2847011 Ontario Inc. is exploring a residential development project to implement the planned intent of the North Talbot Community Plan.

S1.2 Project Site

At-A-Glance

SITE AREA FRONTAGE		DEPTH	EXISTING USE	
.996	60.9	163.45	Residential	
Hectares	Metres	Metres	20th-Century Farm Dwelling	

SERVICING

Municipal ServicesAvailable Nearby

Project Site | 6092 Pack Road

Fig 1. The Project Site

S1.3 Neighbourhood Spatial Analysis

Figure 2 shows the physical and spatial characteristics of the lands surrounding the project site. The lands on the west side of Regiment Road form part of an actively developing residential subdivision (see City of London Staff Report 39T-14506/Z-8436 for further details). The lands are comprised primarily of 2.5-storey single detached dwellings. The dwellings sited along Regiment Road face directly onto Regiment Road with individual driveway accesses to the street. For the dwellings sited along Pack Road, the subdivision pattern is varied including a mix of "side-lotting" conditions onto Pack Road as well as intervening "window-streets" which allow for the dwellings to face Pack Road without having individual driveway accesses connecting them to Pack Road.

Immediately west of the subject site is a planned school site. The school block was planned and zoned through the subdivision planning process for the lands to the west. The size and shape of the school block was confirmed through the same process. A detailed site design for the adjacent school site is not currently available, however, it is anticipated that the school building and corresponding vehicular access would be oriented towards Regiment Road, with the project site being in the "rear yard" of the school.

Lands to the east of the site are designated for a mix of residential uses with medium density residential uses in proximity to Pack Road and Bostwick Road and low density residential uses in interior portions of that future subdivision. Lands to the south will be comprised of a similar mix of residential uses, with medium density residential uses also focused along Pack Road.



Fig 2. Neighbourhood Spatial Context (400m)

S2: PLANNING INTELLIGENCE

S2.1 City Planning Policy

Figure 3 provides visual context for the site's positioning relative to London's city-structure. Of note, the site is located within a planned *Neighbourhood* area. Also highlighted in Figure 3 is London's network of major streets. The project site contains direct frontage on Pack Road, identified as a *Civic Boulevard* by the London Plan.

The site is located within an actively developing residential area outside of the *Primary Transit Area*. It's relationship to the overall structure of London, as laid out in the London Plan, provides a framework for how development policies are to be viewed and applied in relation to this site. The following key characteristics of the site provide context for how the site is to be considered from a London Plan perspective:

- » Neighbourhoods Place Type
- » Outside of Primary Transit Area
- » Frontage on Civic Boulevard



1 Southwest Area Sec. Plan

The project site is within the boundaries of the Southwest Area Secondary Plan (SWAP). Section 20.5.1.5 of the SWAP explains that some areas of the plan are also subject to pre-existing "Area Plans". Where conflicts arise between the general policies of the SWAP and the approved Area Plan policies, the Area Plan prevails. In this case, the lands are subject to he North Talbot Community Area Plan. Relevant policy direction is contained in Section 3.5.11 of the 1989 Official Plan.

2 1989 Official Plan


The project site is designated Multi-Family, Medium Density Residential and Low Density Residential in accordance with the 1989 City of London Official Plan. The MFMDR designation permits multiple-unit residential developments having a low-rise profile, with a maximum density of 75 units per hectare (uph) Permitted uses include multiple-attached dwellings, such as apartments, row houses or cluster houses. These areas may include single-detached, semi-detached and duplex dwellings. The site is also subject to Section 3.,5.11 which provides specific policies for the North Talbot Community.

3 The London Plan

Map 7 - Policies for Specific Areas - of the London Plan identifies the project site as being within a Secondary Plan Area (SWAP) and the North Talbot Community Plan Area. Much of the land north of the project site are within the Neighbourhoods Place Type in accordance with Map 1. Pack Road is identified as a Civic Boulevard on Map 3 of the London Plan while Regiment Road is identified as a Neighborhood Connector Street. Policies 994-999 of the London Plan provide specific guidance that carry through the objectives of the Area Plan.



Not Subject to SWAP



Low Density Res.
 High Density Res.





Fig 3. City-Wide Context

05

Subject to SWAP


North Talbot Community

S3: **DESIGN CONSIDERATIONS**




1 Official Plan Interpretation

The project site is identified on Schedule A - Land Use of the Official Plan as being within both the Medium Density Residential and Low Density Residential designations. Section 19.1.1 of the Official Plan explains that the boundaries of the designations are not meant to be rigid except in cases where they align with distinct physical features. In this case, given that the site bounds a school site and future development lands to the east, and can be developed on its own, it is reasonable to interpret the entire parcel as being within the Medium Density Residential Designation.




2 Road Widening

A road widening dedication of 8.0 metres from the existing front lot line along the Pack Road right-of-way is anticipated. This portion of the site will need to be left free and clear of new built form. Pack Road is currently not developed to an urban cross-section but will be urbanized and widened to a 4-lane cross section with an anticipated 36.0 metre ROW through the Bradley Avenue Extension project. Timing for the improvements is currently unknown.



Built Heritage

6092 Pack Road is listed on the City of London's register of properties that are of cultural heritage value or interest (CHVI). Demolition is generally not supported by the City and heritage resources/attributes are encouraged to be incorporated into new development. In this regard, the project will seek to retain the existing 20th-Century Farmhouse. It is assumed that the attached garage, which formed an addition to the dwelling at some point in time, does not posses cultural heritage value and may be removed as part of the site's redevelopment.



4 Edge Conditions

All new buildings on the site in proximity in Pack Road should be oriented such that the primary building frontages face Pack Road. Further, the existing heritage building on the site establishes the "streetwall". In this regard, new buildings should generally be setback from Pack Road in-line with the front face of the existing heritage building. Edge conditions to the west, north and east are currently undefined as there are no specific plans available for the development of the adjacent sites. However, some measure of sensitivity should be paid so as to not hinder future development of those sites.

S4: **DESIGN PRINCIPLES**

S4.1 **Key Design Principles**

The applicable policies of the SWAP, 1989 Official Plan and the London Plan allow for and encourage a mix of residential dwelling types to be developed at 6092 Pack Road. The form-based policies for new development in this area requires a detailed understanding of the context of the site with regard for issues such as fit and compatibility. It is expected that new development will have regard for and respond to it's context. The detailed urban design analysis that follows interprets the form-based policies of the applicable policy framework in a tangible way to shape a realistic design outcome that could be implemented through a rezoning application. The following urban design principles are critical in the context of 6092 Pack Road and should be maintained in any specific development concept contemplated for the project site:

- **Mixed Housing Development:** the MFMDR policies allow for a range of housing forms including multiple-attached dwellings, such as apartments, row houses or cluster houses. These areas also allow for single-detached, semi-detached and duplex dwellings. Building heights are generally limited to 4-storeys and densities of up to 75 units per hectare are allowable.
- Account for the Road Widening: An approximately 8.0 metre road right-of-way widening will be required to be dedicated to the City of London along the frontage of the project site. This reduction in land area must be accounted for in the development design.
- Retain the Heritage: An important principle of new development on the site is to ensure retention of any significant cultural heritage resources. This goal will be achieved through full retention of the original volume of the 20th-Century Farmhouse. The concept plan involves removal of some minor, more recent, building additions but retains the full volume of the original building. The proposed new building forms do not alter the appearance, proportions or heritage attributes of the heritage structure from the street.
- Plan for Access: New development will require a new 6.5 metres access/driveway from Pack Road. In order to allow for the preservation of the heritage farmhouse and visual exposure of the wraparound porch, the new site access should occur on the east side of the site.
- Shape Massing to Respect Context: The orientation, setbacks and massing of new buildings should have regard for neighbouring uses. In this regard, the side and rear yard setbacks should vary based on building orientation to accommodate appropriate facing distances based on the type of orientation (e.g., side-to-rear, front-to-rear) and the design features (e.g., windows or no windows). The front yard setback should recognize the setback of the heritage farmhouse and generally be in-line with that building to preserve it's contextual relevance along Pack Road.
- **Animate Pack Road:** New buildings adjacent to Pack Road should be oriented such that primary building frontage faces towards Pack Road with principal unit entrances and walkways directly to the City sidewalk and no parking located between the building nearest to the street and the street itself.

S4.2 **Shaping the Zoning Box**




Fig 4. Visualizing the Design Principles

S5: **ZONING APPROACH**

S5.1 Proposed Zoning By-law Amendment

To support the development vision for 6092 Pack Road and implement the applicable planning policies, we propose to rezone the site from the Urban Reserve (UR3) Zone to a Residential R6 Special Provision (R6-5(_)) Zone. The proposed zone will provide a framework for medium density residential development in various housing forms of cluster housing from single detached dwellings to townhouses and stacked townhouses up to a maximum of 12.0 metres in height (4-storeys). The proposed zone includes special regulations to account for the unique context of the project site and implement applicable form-based policy directions of the Official Plan and North Talbot Community Plan. The proposed zone and special regulations are structured to facilitate a range of desirable site design outcomes and are not tied to a specific development design.




Fig 5. Proposed Rezoning

S5.2 Proposed Special Regulations


5092 Pack Road Zoning			
Regulation		R6-5	Proposed R6-5(_)
Permitted Uses		Section 10.2	Notwithstanding Section 10.2, Apartment Buildings shall not be permitted.
ot Area (min.)		850m²	-
ot Frontage (min.)		10.0m	-
Front and Exterior Side Yard Depth (min.)	Arterial	8.0m	10.0m
nterior and Rear Yard Depth (min.)		0.4 metres (1.3 feet) per 1 metre (3.28 feet) of main building height or fraction thereof, but in no case less than 3 metres (9.8 feet) when the end wall of a unit contains no windows to habitable rooms, or 6.0 metres (19.7ft.) when the wall of a unit contains windows to habitable rooms.	1.8 metres (5.9 feet) when the end wall of a unit contains no windows to habitable rooms, or 6.0 metres (19.7ft.) when the wall of a unit contains windows to habitable rooms.
andscaped Open Space (min.)		30%	-
ot Coverage (max.)		45%	-
Height (max.)		12.0m	-
Density (max.)		35uph	45uph
Parking		1.5/unit	-
Drientation		n/a	The front face and primary entrance of all dwellings unit located in new buildings adjacent to Pack Road shall be oriented to Pack Road.

Fig 6. Special Regulations Overview

S6: PRELIMINARY DEVELOPMENT CONCEPT

/ Mixed Towns + Heritage Farmhouse

The preliminary concept plan illustrated on page 15-16 of this brief envisions the development of a mix of housing forms on the site including thirty-three (33) 2.5-storey cluster townhouse units, six (6) 3.5-storey back-to-back townhouse units and the retention of the existing 20th-Century Farmhouse as a single detached unit. In total, the proposed development includes 40 residential units. The proposed building heights and densities are within the standard limits for site's in the MFMDR designation. All of the required vehicular parking will be provided in surface form with this concept, within integrated/attached garages and individual driveways. The conceptual site design allows for the creation of 9 visitor parking stalls in addition to the resident parking. The preliminary concept plan represents a desirable implementation of the proposed Zoning By-law Amendment outlined in Section 5 of this Vision Brief.



Perspective 1: View looking northwest

∇

Conceptual Site Plan

HIGHLIGHTS

Performance Metrics		
Units	Towns	33
	Back-to-Back	6
	Heritage Dwelling	1
	Total	40
Density		40.2 uph
Building Height		7.5-12.0m
Parking	Towns	2/unit
	Back-to-Back	2unit
	Heritage Dwelling	2/unit
	Visitor	9
Yard Depth	Front	10.9m
	East	1.9m-8.7m
	West	1.9m-6.0m
	North	6.0m
LOS		43.5%
Lot Coverage		30.6%

Shared Amenity
Space



S7: **PLANNING ISSUES**

S7.1 Applications Required

It is anticipated that the following *Planning Act* applications will be required in order to implement the planned vision for the project site:

- 1. **Zoning By-law Amendment:** To rezone the site from Urban Reserve (UR3) Zone to a Residential R6 Special Provision R6-5(_) Zone, with special provisions to address the site context and applicable policy framework.
- 2. Site Plan Control: To implement the specific development design envisioned in the preliminary development concept illustrations.
- 3. Draft Plan of Condominium (Optional): To establish tenure for the proposed residential units and common ownership for various physical elements of the site (e.g., common amenity space, surface parking areas, etc.).

S7.2 Issues for Clarification

From the proponent's perspective, the following attributes are critical to the success of the development vision. As such, the project team would appreciate any specific insights that City Staff are able to offer on the following:

- 1. The City's desired route/process for implementing the proposed heritage retention (e.g., Planning Act, Ontario Heritage Act, etc.).
- 2. Exploration of access opportunities and/or limitations along Pack Road (e.g., left turn lane warrant, RIRO access, etc.).
- 3. Staff's perspective on the proposed interpretation of the MFMDR designation applying across the entire parcel.



REFERENCES

- 1. City of London, Southwest Area Secondary Plan (2014)
- 2. 1989 City of London Official Plan
- 3. The London Plan
- 4. City of London Comprehensive Zoning By-law Z.-1.
- 5. H-8968 City of London Staff Report, dated November 12, 2018.
- 6. 39T-14506/Z-8436 City of London Staff Report, dated May 19, 2015.
- 7. City of London, London CityMap (Last updated October 1, 2020).



Appendix B Renderings



